

# MIVIDA AND STANDARD SHAFT PROJECT

## CONSTRUCTION SPECIFICATIONS

**AMR/037/909**


Spring, 2005

**Requisition Number 560 52000000006**

**San Juan County, UTAH**



**UTAH NATURAL RESOURCES**  
Abandoned Mine Reclamation Program  
Salt Lake City, Utah



Utah Oil Gas and Mining

Copy \_\_\_\_ of 20

**\*\*\* This is NOT a standard DFCM Specification Package \*\*\***

**STATE OF UTAH  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS & MINING  
ABANDONED MINE RECLAMATION PROGRAM**

*The Utah Department of Natural Resources receives federal aid and prohibits discrimination on the basis of race, color, sex, age, national origin, or handicap. For information or complaints regarding discrimination, contact Executive Director, Utah Department of Natural Resources, P.O. Box 145610, Salt Lake City, Utah 84114-5610 or Office of Equal Opportunity, U.S. Department of the Interior, Washington, D.C. 20240*

Completed Date: 5/3/2005

Document Filename: O:\Projects\Inventory\037SanJuan\Mivida\Construction\MiVidaspecs.doc

Revised: 06/07/04

**CONSTRUCTION SPECIFICATIONS FOR  
MIVIDA AND STANDARD SHAFT PROJECT  
RECLAMATION CONSTRUCTION**

**San Juan County, UTAH**

Requisition Number RX 560 52000000006

State of Utah

Department of Natural Resources  
Division of Oil, Gas and Mining  
Abandoned Mine Reclamation Program  
1594 West North Temple, Suite 1210  
P.O. Box 145801  
Salt Lake City, Utah 84114-5801  
(801) 538-5340  
<http://www.ogm.utah.gov/amr/contract.htm>

**\*\*\* This is NOT a standard DFCM Specification Package \*\*\***



## Table Of Contents

Project Summary And Bidding Check List .....	i
Instructions To Bidders .....	ii
<b>PROPOSAL AND BID SCHEDULES (Yellow Pages)</b>	
Proposal .....	1
Agency Contract Bond Statement .....	3
Bid Bond .....	4
Bidder's Proposed Subcontractors, Suppliers & Vendors List .....	5
Minority And Woman Business Enterprise Representation .....	7
Applicant/Violator System Eligibility Check .....	8
Bid Schedule .....	10
<b>CONTRACT (Orange Pages)</b>	
Contract Form .....	11
Performance Bond .....	19
Payment Bond .....	20
Certificate Of Substantial Completion .....	22
Certificate Of Final Acceptance .....	23
<b>GENERAL CONDITIONS (White Pages)</b>	
General Conditions .....	25
Supplemental General Conditions .....	43
<b>TECHNICAL SPECIFICATIONS (Blue Pages)</b>	
0200 General Site Information .....	46
0220 Mobilization/Demobilization .....	51
0225 Radiological Protection .....	53
0230 Access Improvements .....	60
0240 Demolition And Clean-Up .....	62
0250 Mine Closures .....	65
0254 Polyurethane Foam Mine Closures .....	73
0270 Site Grading/Earthwork .....	84
0280 Drainage Control & Stream Protection .....	89
0290 Revegetation .....	96
<b>SPECIFIC SITE REQUIREMENTS (Gray Pages)</b>	
0300 Specific Site Requirements .....	105
<b>APPENDICES</b>	
Appendix A: Revegetation Seed Mix	
Appendix B: Site Description and Mine Closure Schedule	
Appendix C: Contractor Report Forms	
Appendix D: Project Location and Site Maps	
Appendix E: Mine Closure Design Drawings	



## Project Summary And Bidding Check List

Sealed bids will be received by the Division of Purchasing, 3150 State Office Building, Salt Lake City, for the MIVIDA AND STANDARD SHAFT PROJECT RECLAMATION CONSTRUCTION in San Juan County, Utah. Bids will be received until 2:00 p.m., on Wednesday, June 1, 2005, at which time they will be opened and read aloud in the Division of Purchasing offices.

The WORK consists of reclamation construction at abandoned uranium mines located in San Juan County, Utah. The work includes installing mine closures and includes incidental tasks such as access improvement and revegetation of disturbed areas. Details of the WORK are contained in the Specifications.

Specifications may be obtained from the Division of Oil, Gas, and Mining, 1594 West North Temple, Suite 1210, Salt Lake City, for a nonrefundable fee of twenty dollars (\$20.00). Checks should be made payable to the Division of Oil, Gas and Mining.

### **AN OPTIONAL PRE-BID MEETING WILL BE HELD FOR ALL BIDDERS ON MONDAY, MAY 23, 2005.**

Meet at the turnoff to the Lisbon Valley Industrial Area/Steen Road along highway 191 at 12:00 noon. From there bidders will drive to project area. The meeting is expected to last two or three hours and will involve driving and hiking over rugged terrain. High clearance four-wheel-drive vehicles are recommended. This meeting is optional. *Because of the special nature of abandoned mine closure work, bidders are strongly encouraged to attend the pre-bid meeting*

Questions about bidding procedures should be directed to the Division of Purchasing. Contact person is Paul Mash, Purchasing Agent. Bids should be delivered to:

Division of Purchasing  
3150 State Office Building  
Salt Lake City, Utah 84114  
(801) 538-3026 FAX: (801) 538-3882

Technical questions about the project should be directed to the project manager at the Division of Oil, Gas and Mining. Contact person is:

Amber Fortner, Project Manager  
Division of Oil, Gas and Mining  
1594 West North Temple, Suite 1210  
Box 145801  
Salt Lake City, Utah 84114-5801  
(801) 538-5437 Fax: (801) 359-3940  
E-mail: [amberfortner@utah.gov](mailto:amberfortner@utah.gov)

The following is a check list of items that **must** be provided with the bid documents:

- ☐ Division of Purchasing bid documents
- ☐ Proposal
- ☐ Agency Contract Bond Statement
- ☐ Bid Security (Bid Bond or Cashier's Check)
- ☐ Minority and Woman Business Enterprise Representation
- ☐ Bid Schedule
- ☐ Photocopy of current Utah Contractor's License

### ***Required Submittals:***

- ☐ Section 0230, Part 1, 1.02
- ☐ Section 0240, Part 1, 1.02, A
- ☐ Section 0250, Part 1, 1.02, A-B-C
- ☐ Section 0254, Part 1, 1.02
- ☐ Section 0270, Part 1, 1.02, A-B
- ☐ Section 0280, Part 1, 1.02, A-D
- ☐ Section 0290, Part 1, 1.02, A-B

The following items are required within 24 hours after bid opening from the apparent two low bidders only. They may be submitted with the bid at the bidder's option or convenience.

- ☐ Bidder's Proposed Subcontractors, Suppliers & Vendors List
- ☐ AVS Eligibility Check information: AML Contractor Ownership & Control Information Package

**Bids must be delivered to the Division of Purchasing only. Do NOT deliver bids to DOGM.**

## Instructions To Bidders

### 1. Request for Bids

The Utah Division of Purchasing is accepting bids for the MiVida and Standard Shaft Project. The WORK consists of two mine closures, runoff control, and revegetation of disturbed areas at abandoned uranium mines in San Juan County, Utah. Details of the WORK are contained in these Specifications. **Sealed bids are due on Wednesday, June 1, 2005 no later than 2:00 P.M., at which time they will be opened and read aloud at the Division of Purchasing's office.**

### 2. Qualifications of Bidders

All CONTRACTORS must be currently licensed in Utah for the type of work to be done. Bidders shall submit a photocopy of their current Utah license covering the type of work to be done with their bid.

All CONTRACTORS who have previously performed WORK on a Utah Abandoned Mine Reclamation Program (UAMRP) project have been evaluated based on the Contractor Performance Rating Form (Appendix C). A rating of ten points or more is required to bid on this project.

### 3. Drawings and Specifications

Drawings and Specifications may be obtained from the Division of Oil, Gas and Mining for the amount stated in the Project Summary and Checklist. Checks should be made payable to the Utah Division of Oil, Gas and Mining. The payment is nonrefundable.

### 4. Pre-bid Meeting

**An optional pre-bid site meeting will be held for all interested bidders on Monday, May 23, 2005.**

Meet at the turnoff to the Lisbon Valley Industrial Area/Steen Road along highway 191 at 12:00 noon. From there bidders will travel to project area. The meeting is expected to last two or three hours and will involve driving and hiking over rugged terrain. High clearance four-wheel-drive vehicles are recommended.

This meeting is optional. Attendance is not required to bid, but attendance should result in a more responsible bid. Abandoned mine closure work is different from standard residential or commercial construction. It requires specialized work in unusual conditions and unique circumstances. *Because of the special nature of abandoned mine closure work, bidders are strongly encouraged to attend the pre-bid meeting.* If attendance at the meeting is not possible, bidders should make every effort to examine the project on their own time. Abandoned mines are hazardous. Do not enter the mines.

### 5. Proposals

Before submitting a proposal, each bidder shall carefully examine the drawings, specifications and other contract documents and shall visit the site of the WORK; shall fully inform him or herself as to all existing conditions and limitations; and shall include in the proposal the cost of all items included in the CONTRACT. CONTRACTOR shall fill out all blanks and include all forms and submittals, or be subject to having the bid disqualified. (See the check list of bid items on page i).

The pages required for bidding are included in these specifications. For convenience, additional unbound copies of these pages will be distributed at the pre-bid site meeting. The bidder must submit the Proposal, Agency Contract Bond Statement, Bid Bond, Minority and Woman Business Enterprise Representation, Bid Schedule, photocopy of Utah contractor's license, and required submittals in the sealed bid, along with the required Division of Purchasing bid documents.

**Deliver proposals to the Division of Purchasing only. Do not deliver proposals to DOGM.**



6. Contract and Bond

The contract agreement will be on a form similar to that which is bound in the specifications. The completion date of construction will be as indicated in the proposal. The successful bidder, within 14 days after the bid opening, will be required to furnish a performance bond and a payment bond in an amount equal to one hundred percent (100%) of the contract price, said bonds shall be secured from a company satisfactory to OWNER. **The surety company must be a U.S. Department of Treasury (Circular 570) listed company.**

7. Listing of Subcontractors

The experience and responsibility of Subcontractors may have bearing on the selection of a CONTRACTOR by the OWNER.

The apparent two low bidders shall deliver to OWNER within 24 hours (excluding Saturday, Sunday, and State holidays) for OWNER's approval, a list of the names of Subcontractors to be furnished for each of the principal parts of the work and the corresponding dollar amounts. Each principal part shall mean a subcontract dollar value in excess of \$5,000. A form for this submission is included in these Specifications. Such list shall be binding upon the CONTRACTOR; however, OWNER has a right to reject any or all Subcontractors listed or unlisted which OWNER feels are unqualified to do the work.

OWNER may withhold award of CONTRACT to any particular bidder if one or more of his or her proposed Subcontractors are considered by the OWNER to be unqualified.

8. Interpretation of Plans and Specifications

If any person contemplating submitting a bid for the proposed CONTRACT is in doubt as to the true meaning of any part of the drawings, specifications or other proposed CONTRACT documents, he or she may submit to the Division of Oil, Gas & Mining a written request for an interpretation thereof. The person submitting the request will be responsible for its prompt delivery.

**Any interpretation of the proposed documents will be made only by addendum duly issued. A copy of such addendum will be mailed or delivered to each person receiving a set of documents, and posted on the UAMRP website ([www.ogm.utah.gov](http://www.ogm.utah.gov)). The OWNER will not be responsible for any other explanations or interpretations of the proposed documents.**

9. Addenda or Bulletins

Any addenda or bulletins issued during the time of bidding shall become part of the documents issued to the bidders for the preparation of the bid, shall be covered in the bid, and shall be made a part of the CONTRACT.

10. Bid Schedule

Bidding CONTRACTORS shall examine the specifications and the Bid Schedule and *fill in all blanks* of the CONTRACTOR's Proposal and Bid Schedule and submit all required information contained in the Specifications Schedule, including required submittals, or have the bid subject to disqualification.

11. Award of CONTRACT

The CONTRACT will be awarded as soon as possible to the lowest responsible bidder, provided the bid is reasonable and is in the interests of the OWNER to accept. Responsible bidders will be considered to be those bidders who have fully evaluated the work to be performed, as detailed in their bids. For bidders who have previously performed WORK on a UAMRP project, evaluation of the responsibility of the bidder will also include consideration of past performance on AMR contracts for OWNER. Both the Lump Sum Amount and the Variation in Quantities Unit Price for all work items will be considered in awarding the CONTRACT. Lump Sum Amounts do not have to equal the product of the estimated quantity times the Variation in Quantity Unit Price, but OWNER may reject a bid if unit prices are substantially out of line with the Lump Sum Amount. The OWNER reserves the right to waive any technicalities or formalities in any

bid or in the bidding.

12. Qualifications

The CONTRACTOR's and Subcontractor's past performance, organization, equipment, and ability to perform and complete their contracts in the manner and within the time limit specified will be elements along with the cash amount of the bid, which will be considered by the OWNER in the letting of the CONTRACT. A rating of ten points or more on the Contractor Performance Rating Form (Appendix B) is required for any CONTRACTOR who has previously performed WORK on a Utah AMR project. The CONTRACTOR shall comply with and require all of his or her Subcontractors to comply with the license laws as required by the State of Utah.

13. Cost Breakdown

The CONTRACTOR shall, before starting WORK, submit to OWNER a cost breakdown showing the cost of various segments of the WORK according to a specification heading, the total amount equaling the CONTRACT price. This breakdown shall be used as the basis for the payment of estimates as stated in the contract documents.

14. Right to Reject Proposals

The OWNER reserves the right to reject any or all proposals.

15. Time is Essence and Award of CONTRACT

Time is of the essence in award of the CONTRACT.

16. Withdrawal of Bids

Bids may be withdrawn upon written or electronic request received from bidders prior to the time fixed for opening. Electronic request via FAX or E-mail must be received by OWNER in written form before bid opening. Negligence on the part of the bidder in preparing the bid confers no right for the withdrawal of the bid after it has been opened.

17. Bid Security

Bid Security in the amount of five percent (5%) of the bid, made payable to the Division of Oil, Gas & Mining, shall accompany bid. If a certified or cashier's check is used in lieu of bid bond, a current certificate from an approved surety company guaranteeing execution of a 100% Performance Bond and 100% Payment Bond must be on file with the OWNER.

18. Applicant Violator System (AVS) Eligibility Check

Federal regulations (30 CFR 874.16) effective July 1, 1994, require all successful bidders on contracts funded through Title IV of the Surface Mining Control and Reclamation Act (SMCRA) of 1977 to be eligible under 30 CFR 773.15(b)(1) to receive a permit to conduct surface coal mining operations. In general, this means that the Utah Abandoned Mine Reclamation Program may not hire a contractor who is or whose company is associated with a coal mine operator with outstanding unabated violations under SMCRA. The regulations further require that contractor eligibility be confirmed by the Applicant/Violator System (AVS) at the U.S. Office of Surface Mining (OSM). Compliance checks are also required for all subcontractors receiving 10% or more of the total contract amount.

19. Buy American Act

Compliance with the Buy American Act is required for this project. The Buy American Act requires the use of domestically produced materials.

20. Electronic Specs Available

OWNER has electronic versions of the Contract Specifications available on DOGM's website at <http://www.ogm.utah.gov/amr/contract.htm>. Files include the text of the Contract Specifications (as a Microsoft Word file and an Adobe Acrobat \*.pdf file), the maps (in \*.pdf format, readable with Adobe Acrobat Reader software available free online). Files can be downloaded from the website. Any questions regarding digital data should be directed to Amber Fortner, 801-538-5437, e-mail: [amberfortner@utah.gov](mailto:amberfortner@utah.gov)



## Proposal

NAME OF BIDDER \_\_\_\_\_ DATE \_\_\_\_\_

**TO THE DIVISION OF PURCHASING  
3150 STATE OFFICE BUILDING  
SALT LAKE CITY, UTAH 84114**

Re: RX No: 560 52000000006

Gentlemen:

The undersigned, in compliance with your invitation for bids for the

MIVIDA AND STANDARD SHAFT PROJECT RECLAMATION CONSTRUCTION

having examined the Drawings and Specifications, related documents, and the site of the proposed work and being familiar with all of the conditions surrounding the construction of the proposed project, including the availability of labor, hereby propose to furnish all labor, materials, and supplies as required for the WORK in accordance with the CONTRACT documents as specified and within the time set forth and at the price stated below. This price is to cover all expenses incurred in performing the WORK required under the CONTRACT Documents of which this Proposal is a part. Negotiation of BID PRICE shall be completed with the OWNER prior to final execution of the CONTRACT.

I/We acknowledge receipt of the following addenda:

For all WORK shown on the Drawings and described in the Specifications, I/we agree to perform for the sum of:

\_\_\_\_\_ DOLLARS (\$ \_\_\_\_\_)  
*(In case of discrepancy, written amount shall govern)*

For your consideration, we further propose the following ALTERNATIVES for the following total amounts to be added/deducted to/from the above bid amount:

\_\_\_\_\_ Add \$ \_\_\_\_\_ Deduct \$ \_\_\_\_\_

I/We guarantee to complete the WORK within 30 calendar days after receipt of Notice to Proceed, should I/we be the successful bidder.

For your consideration I/we propose an alternative amount of time to complete the WORK after Notice to Proceed, should I/we be the successful bidder. Such an extension allows the following total amount to be deducted from the bid amount:

Alternative: \_\_\_\_\_ Total Calendar Days \_\_\_\_\_ Deduct \$ \_\_\_\_\_

This bid shall be good for 45 days after bid opening.

Enclosed is \_\_\_\_\_, as required, in the sum of \$ \_\_\_\_\_  
(Bond or Check)

## PROPOSAL

Page 2

If applicable, the CONTRACTOR shall certify that all reclamation fees or civil penalty assessments required by the provision of the Surface Mining Control and Reclamation Act of 1977, P.L. 95-87, 30 U.S.C. Sec 1201 et seq., have been paid. Provided further, this certification requirement shall also apply to all Subcontractors utilized by the successful bidders.

Upon receipt of notice of acceptance of this bid, the undersigned agrees to execute the CONTRACT within five (5) days and deliver OWNER's protective bond (performance and bid) in the prescribed form in the amount of 100% of the general construction contract price for faithful performance of the CONTRACT. The certified check, cashier's check or Bid Bond attached, in the amount not less than five percent (5%) of the above BID PRICE, shall become the property of the Division of Oil, Gas & Mining in the event that the CONTRACT is not negotiated and/or the OWNER's Protective Bond delivered within the time set forth, as liquidated damages for the delay and additional expense caused thereby.

### SUBSTITUTIONS AND ALTERNATIVES:

The following substitutions and/or alternatives of materials and/or equipment are proposed for your consideration:

Item	Manufacturer and Description	Addition	Deduction
_____	_____	\$ _____	\$ _____
_____	_____	\$ _____	\$ _____
_____	_____	\$ _____	\$ _____

CONTRACTOR shall furnish and attach to this proposal all submittals as required in the specifications:

Section 0230, Part 1, 1.02  
Section 0240, Part 1, 1.02, A  
Section 0250, Part 1, 1.02, A-B-C  
Section 0254, Part 1, 1.02

Section 0270, Part 1, 1.02, A-B  
Section 0280, Part 1, 1.02, A-D  
Section 0290, Part 1, 1.02, A-B

The undersigned CONTRACTOR's License Number for Utah is \_\_\_\_\_

Type of Organization:

\_\_\_\_\_  
(Corporation, Co-Partnership, Individual, etc.)

SEAL  
(If a Corporation)

\_\_\_\_\_  
(Tax ID No.)

Respectfully submitted,

\_\_\_\_\_  
Name of Bidder

\_\_\_\_\_  
Address

\_\_\_\_\_  
Authorized Signature

**STATE OF UTAH**  
Division of Purchasing  
**Agency Contract Bond Statement**

---

**BIDDING REQUIREMENTS**

A 5% bid bond or cashier's check is required by all vendors bidding on this project. The bid bond must be attached to bid **or it will be disqualified**. Checks submitted will be returned certified mail after an official award has been made.

**AWARD REQUIREMENTS**

A 100% performance/payment bond will be required from the award vendor within 14 days after notification of award. Bonds must be in the form of a cashier's check (no personal or business checks) or a surety bond from a licensed surety company doing business in the State of Utah.

Performance/payment bonds (or checks) will be **held as security for a period of 12 months after completion of project**, per state law. Checks submitted will be returned certified mail only after this specified time. Bidder's name must be the same on both the bid forms and all bonds submitted.

Please indicate which method of bonding will be used if awarded this job:

\_\_\_\_\_ 100% CASHIERS CHECK

\_\_\_\_\_ 100% PERFORMANCE/PAYMENT BOND

Bond/Ins Company \_\_\_\_\_

Agent name \_\_\_\_\_

Fax # \_\_\_\_\_ Phone # \_\_\_\_\_

Upon awarding, the requesting agency will fax a verification to the bonding company listed above to start the bonding process. It is then the responsibility of the vendor to follow through with their bonding agent to assure the bond is processed. After the bonding company sends the bond to vendor for signatures, it is the responsibility of the vendor to mail or hand carry the original bond (no copies or faxes accepted) to the requesting agency, to the attention of the contract person listed on the bid. **No work can commence until the requesting agency has receipt of this performance/payment bond.** After this time the contract will be officially released to the award vendor.

## Bid Bond

\_\_\_\_\_  
Date Bond Executed

\_\_\_\_\_  
Principal

\_\_\_\_\_  
Surety

\_\_\_\_\_  
Sum of Bond

KNOW ALL MEN OF THESE PRESENTS, that we, the PRINCIPAL AND SURETY above named, are held and firmly bound unto the STATE OF UTAH, ACTING BY AND THROUGH THE DIVISION OF OIL, GAS AND MINING OF UTAH, IN THE SUM OF THE AMOUNT STATED ABOVE, FOR THE PAYMENT OF WHICH SUM WELL AND TRULY TO BE MADE, we bind ourselves, our heirs, executors, administrators, and successors, jointly and severally, firmly by these presents. THE CONDITION OF THIS OBLIGATION IS SUCH that whereas the principal has submitted the accompanying bid, dated as shown above, for

\$ \_\_\_\_\_

NOW THEREFORE, THE CONDITION OF THE ABOVE OBLIGATION IS SUCH, that if the said principal shall execute a CONTRACT and give bond to be approved by the Oblige for the faithful performance thereof within ten (10) days after being notified in writing of such CONTRACT to the principal, this obligation shall then be null and void; otherwise it shall remain in full force and effect.

IN WITNESS WHEREOF, the above bounden parties have executed this instrument under their several seals on the date indicated above, the name and corporate seal of each corporate party being hereto affixed and these presents duly signed by its undersigned representative, pursuant to authority of its governing body.

\_\_\_\_\_  
Individual or Partnership Principal

\_\_\_\_\_  
Corporate Principal

\_\_\_\_\_  
Business Address

\_\_\_\_\_  
Business Address

\_\_\_\_\_  
By:

Affix  
Corporate  
Seal

\_\_\_\_\_  
Title

\_\_\_\_\_  
Corporate Surety:

\_\_\_\_\_  
Business Address

NOTE: If certified or cashier's check is used in lieu of Bid Bond, a certificate from an approved surety company guaranteeing execution of a full performance bond must accompany bid.

\_\_\_\_\_  
By:

Affix  
Corporate  
Seal

\_\_\_\_\_  
Attorney-in-Fact

STATE OF UTAH )  
COUNTY OF SALT LAKE )

\_\_\_\_\_, being first duly sworn on oath, deposes and says that he/she is the Attorney-in-Fact of the above-named Surety Company, and that he/she is duly authorized to execute the same and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations.

Subscribed and sworn to before me this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_.

My commission expires \_\_\_\_\_.

\_\_\_\_\_  
Attorney-in-Fact



## Bidder's Proposed Subcontractors, Suppliers & Vendors List

### MIVIDA AND STANDARD SHAFT PROJECT RECLAMATION CONSTRUCTION AMR/037/909

Utah Division of Oil, Gas & Mining

We submit the following list of first-tier subcontractors, suppliers and vendors for OWNER approval. We recognize this list as binding on us, and acknowledge OWNER'S right to reject any or all subcontractors, suppliers or vendors listed or unlisted which the OWNER feels are unqualified to do the work.

SUBCONTRACTOR	CONTRACT AMOUNT	STATE CONTRACTOR'S LICENSE NO.	LICENSE LIMIT
Excavation:			
Concrete Fabrication:			
Masonry:			
Demolition:			
Steel Fabrication:			
Revegetation:			
Trucking/Transport:			
Polyurethane Foam:			
Other:			
Other:			
Other:			

**BIDDER'S PROPOSED SUBCONTRACTORS, SUPPLIERS & VENDORS LIST**

Page 2

SUPPLIER/VENDOR	AMOUNT	PRODUCT
Ready-Mix:		
Cement/Block:		
Steel:		
Polyurethane Foam:		
Other:		
Other:		
Other:		

We certify that:

1. This list includes all subcontractors, suppliers and vendors whose bids exceed \$5,000 (for prime contractor bids less than \$250,000) or \$25,000 (for prime contractor bids of \$250,000 or more).
2. Where we have listed "Self" it is our intent to perform said work and that we generally and regularly perform that type of work, and are appropriately licensed.
3. Any approved change in sub-bidders, suppliers or vendors which results in a lower contract price for sub-bid work shall accordingly reduce the total sum of the prime contract.

Signed by: \_\_\_\_\_

Firm: \_\_\_\_\_

Date: \_\_\_\_\_

**Note:** Failure to submit this form properly completed and signed within 24 hours (not including Saturday, Sunday, or State holidays) of the bid opening may be grounds for OWNER'S refusal to enter into a written CONTRACT with BIDDER. Action will be taken against BIDDER'S bid bond or cashier's check as deemed appropriate by OWNER. Timely notice of unacceptable subcontractors, suppliers or vendors will be given to the BIDDER. Reporting of subcontractors may be required for conformance with 63A-5-208 UCA.

## Minority And Woman Business Enterprise Representation

The offeror represents that it ☐ is ☐ is not a minority business enterprise.

A minority business enterprise is defined as a concern that:

- 1) is at least 51 percent owned by one or more individuals who are socially and economically disadvantaged, or a publicly owned business having at least 51 percent of its stock owned by one or more individuals who are socially and economically disadvantaged individuals; and
- 2) has its management and daily business controlled by one or more such individuals.

Qualified groups. The offeror shall presume that socially and economically disadvantaged individuals include Black Americans, Hispanic American, Native Americans, Asian-Pacific American, Asian-Indian Americans, and other individuals found to be qualified by the Small Business Administration under 13 CFR 124.I.

The offeror represents that it ☐ is ☐ is not a woman business enterprise.

A woman business enterprise is defined as a concern that:

- 1) is at least 51 percent owned by one or more women, or a publicly owned business having at least 51 percent of its stock owned by one or more women; and
- 2) has its management and daily business controlled by one or more of the women owners.

Business firms which are 51 percent owned by minorities or women, but are in fact managed and operated by non-minority individuals do not qualify as minority or woman business enterprises.

The offeror represents that the following proposed subcontractor(s) is (are) a minority or woman business enterprise:

---

---

---

Signature of Offeror

---

Title

---

Date

*This information is requested for Federal reporting purposes only. Minority/woman status has no bearing on the selection of a contractor.*

## **Applicant/Violator System Eligibility Check**

Federal regulations (30 CFR 874.16) effective July 1, 1994, require all successful bidders on contracts funded through Title IV of the Surface Mining Control and Reclamation Act (SMCRA) of 1977 to be eligible under 30 CFR 773.15(b)(1) to receive a permit to conduct surface coal mining operations. In general, this means that the Utah Abandoned Mine Reclamation Program may not hire a contractor who is or whose company is associated with a coal mine operator with outstanding unabated violations under SMCRA. The regulations further require that contractor eligibility be confirmed by the Applicant/Violator System (AVS) at the U.S. Office of Surface Mining (OSM). Compliance checks are also required for all subcontractors receiving 10% or more of the total contract amount.

To comply with these rules, prospective bidders must provide the Division of Oil, Gas and Mining with information on the ownership and control of the firm for AVS review. A bidder must receive a recommendation of "Issue" or "Conditional Issue" from the OSM AVS office to be awarded the contract.

The two apparent low bidders shall submit to DOGM within 24 hours (excluding weekends and holidays) of the bid opening either a notarized copy of the "AML Contractor Ownership and Control Information Package" or else a copy of the "AML Contractor Ownership and Control Data Certification" updating and certifying previously submitted information. DOGM will provide forms for these submissions or you may download from the Internet at <http://www.avs.osmre.gov>. DOGM will submit the ownership and control information to OSM for AVS review. OSM's review will be completed within 72 hours if the ownership and control data entry is complete.

Bidders may choose to submit the required information prior to submitting the bid proposal in order to facilitate data entry by OSM and expedite the AVS review and contract award process. Forms may be obtained from DOGM.

The following information is required for the "AML Contractor Ownership and Control Information Package":

- Contractor's identity (name, address, telephone, Social Security number, Employee ID number).
- Contractor's legal structure (sole proprietorship, partnership, corporation).
- Identities (name, address, telephone, SSN, EIN, % ownership) of every officer, general partner, shareholder (10% voting stock), director, or other controlling entity.
- Identities of parties with the authority to commit the assets of the firm.
- Identities of other relationships that give direct or indirect authority over the execution of the work.
- List (name, address, permit number, MSHA number) of all permits issued in the last five years to or pending permit applications for coal mining operations by any parties identified above.
- All of the above information for any subcontractor with 10% of the contract amount.

## MiVida and Standard Shaft Project Summary Bid Schedule

<u>Mine Group</u>	<u>Lump Sum Amount</u>
CONSTRUCTION SUBTOTAL Carried over from Bid Schedule	\$ _____
RADIOLOGICAL PROTECTION See Section 0225	\$ _____
MOBILIZATION/DEMOBILIZATION/CLEAN-UP FOR ALL MINE SITES See Section 0220	\$ _____
BONDS & INSURANCE	\$ _____
TOTAL CONTRACT BID PRICE	\$ _____

TOTAL CONTRACT BID PRICE WRITTEN:

\_\_\_\_\_  
\_\_\_\_\_

DATE: \_\_\_\_\_ BY: \_\_\_\_\_

FIRM: \_\_\_\_\_

By the above signature I/we acknowledge that I/we have examined the site conditions and have made the measurements and evaluations necessary to plan and bid the WORK.

Note: The "Variation in Quantity Unit Price" on the Mine Closure Bid Schedule will be used for adjustments to the CONTRACT amount where the actual WORK quantity varies by more than 15% from the estimated quantity listed in the bid schedule (see Supplementary Condition No. 6: Variation in Estimated Quantity). The "Variation in Quantity Unit Price" will also be used as the basis for determining costs for closures not currently specified in the WORK that may be added in the future by change order. Award of CONTRACT will be based on consideration of both the base "Bid Price" and the "Variation in Quantity Unit Price" for additional/reduced WORK.

### MiVida and Standard Shaft Project Bid Schedule

#### McCormick Tunnel

Feature ID/Tag No.	Specified Work	Est. Qty	Bid Price Amount	Variation in Quantity Unit Price
Site Access & Improvements	Section 0230, Part 3.02	Access 1 ea.	\$	N/A
4302411HO001	Section 300, Part A, 1. Temporary PUF plug	1 cyd	\$	\$ /cyd
Move mine cars	Section 300, Part A, 3.	6 cars 1 motor	\$	N/A
4302411HO001	Section 300, Part A, 4. Backfill	200 cyd	\$	\$ /cyd
Regrade dump	Section 0250	0.25 acre	\$	\$ /acre
Revegetation	Section 0290	0.40 acre	\$	\$ /acre

#### Standard Mine

Site Access & Improvements	Section 0230, Part 3.02	Access 1 ea.	\$	N/A
4302411VO001	Section 300, Part B	13,300 cyd	\$	\$ /cyd
Bat Exclusion	Section 0250, Part 3.01	Lump sum	\$	\$
Revegetation	Section 0290	0.20 acre	\$	\$ /acre
<b>CONSTRUCTION TOTAL:</b>			\$	

Note: Award of CONTRACT will be based on consideration of both the base "Bid Price" and the "Variation in Quantity Unit Price" for additional/reduced WORK.

## Contract Form

Contract # \_\_\_\_\_

1. CONTRACTING PARTIES: This contract is between the following agency of the State of Utah:

Department of Natural Resources      560      Division of Oil, Gas and Mining, referred to as OWNER,  
Agency Name      Agency Code      Division

and the following CONTRACTOR:

Name \_\_\_\_\_

Address \_\_\_\_\_

City \_\_\_\_\_ State \_\_\_\_\_ Zip \_\_\_\_\_

Contact Person \_\_\_\_\_

Phone \_\_\_\_\_ E-mail Address \_\_\_\_\_

### LEGAL STATUS OF CONTRACTOR

- ☐ Sole Proprietor  
☐ Non-Profit Corporation  
☐ For-Profit Corporation  
☐ Partnership  
☐ Government Agency

Federal Tax ID# \_\_\_\_\_

Vendor # \_\_\_\_\_

Commodity Code # 96273

### FI-NET Accounting Codes: MiVida Project

Fund	Agency	Org	Approp. Unit	Activity (Mine)	Expend. Object	Grant Category	Project or Job
746	560	9193			7316		NF MVD 09 B
100	560	2881	REG		7308	GBS1	NA BSW 03 G

2. GENERAL PURPOSE OF CONTRACT: The general purpose of this contract is for reclamation construction of abandoned mine sites in San Juan County, Utah, referred to as the MiVida and Standard Shaft Project.
3. PROCUREMENT: This contract is entered into as a result of the procurement process on Bid # \*\*\*PM, Requisition # RX 560 52000000006, FY2005, or the attached pre-approved sole source.
4. CONTRACT PERIOD: Effective date \*\*\*MONTH DAY, 2005. Termination date \*\*\*MONTH DAY, 2005 unless terminated early or extended in accordance with the terms and conditions of this contract. Renewal options (if any) \*\*\*.
5. CONTRACT COSTS: CONTRACTOR will be paid a maximum of \$ \*\*\* for costs authorized by this contract.
6. ATTACHMENT A: Division of Purchasing's Standard Terms and Conditions.

ATTACHMENT B: SCOPE OF WORK, hereinafter the WORK, to be performed is that contained in the Drawings and Technical Specifications prepared by: the Division of Oil, Gas & Mining and entitled *TECHNICAL SPECIFICATIONS: MiVida and Standard Shaft Project Reclamation Construction*; the General Specifications prepared by the Division of Oil, Gas and Mining entitled *GENERAL CONDITIONS FOR ABANDONED MINE RECLAMATION PROJECTS*, dated June, 1988; and the Supplementary Conditions listed in the Technical Specifications cited above.

ATTACHMENT C: Division of Oil, Gas and Mining Construction Terms and Conditions.

ATTACHMENT D: Cost Schedule

Contract  
MiVida and Standard Shaft Project

Any conflicts between Attachment A and other Attachments will be resolved in favor of Attachment A.

7. DOCUMENTS INCORPORATED INTO THIS CONTRACT BY REFERENCE BUT NOT ATTACHED:

- a. All other governmental laws, regulations, or actions applicable to the goods and/or services authorized by this contract.
- b. Utah State Procurement Code, Procurement Rules, and CONTRACTOR'S response to Bid #\_ PM\*\*\*, dated \*\*\*MONTH DAY, 2005.

IN WITNESS WHEREOF, the parties sign and cause this contract to be executed.

**FOR THE CONTRACTOR:**

ATTEST:

CONTRACTOR:

\_\_\_\_\_  
Secretary of Corporation or Witness

BY: \_\_\_\_\_

NAME: \_\_\_\_\_

TITLE: \_\_\_\_\_

TAXPAYER ID #: \_\_\_\_\_

**FOR THE STATE OF UTAH:**

APPROVED FOR AVAILABILITY OF FUNDS:  
DEPARTMENT OF NATURAL RESOURCES  
DIVISION OF OIL, GAS & MINING

\_\_\_\_\_  
Anthony Gallegos, Acting AMR Administrator

\_\_\_\_\_  
Mary Ann Wright, Acting Director

\_\_\_\_\_  
Paula Dupin-Zahn, Budget/Accounting

APPROVED FOR EXPENDITURE:  
DIVISION OF PURCHASING

DIVISION OF FINANCE

\_\_\_\_\_  
Douglas G. Richins, Director of Purchasing

\_\_\_\_\_  
(for) Kim S. Thorne, Director of Finance

Agency Contact	Phone Number	Fax Number	E-mail Address
Tony Gallegos	(801) 538-5267	(801) 359-3940	anthonygallegos@utah.gov
Amber Fortner	(801) 538-5437	(801) 359-3940	amberfortner@utah.gov

APPROVED AS TO FORM BY  
ATTORNEY GENERAL'S OFFICE  
DOGM Construction Contract (revised 06/17/04)  
Reference: Division of Finance Form FI 84 (revised 08/26/03)



**ATTACHMENT A**  
**STANDARD TERMS AND CONDITIONS**

- 1. AUTHORITY:** Provisions of this contract are pursuant to the authority set forth in 63-56, Utah Code Annotated, 1953, as amended, Utah State Procurement Rules (Utah Administrative Code Section R33), and related statutes which permit the State to purchase certain specified services, and other approved purchases for the State.
- 2. CONTRACT JURISDICTION, CHOICE OF LAW, AND VENUE:** The provisions of this contract shall be governed by the laws of the State of Utah. The parties will submit to the jurisdiction of the courts of the State of Utah for any dispute arising out of this Contract or the breach thereof. Venue shall be in Salt Lake City, in the Third Judicial District Court for Salt Lake County.
- 3. LAWS AND REGULATIONS:** Any and all supplies, services and equipment furnished will comply fully with all applicable Federal and State laws and regulations.
- 4. RECORDS ADMINISTRATION:** The CONTRACTOR shall maintain, or supervise the maintenance of all records necessary to properly account for the payments made to the CONTRACTOR for costs authorized by this contract. These records shall be retained by the CONTRACTOR for at least four years after the contract terminates, or until all audits initiated within the four years, have been completed, whichever is later. The CONTRACTOR agrees to allow State and Federal auditors, and State Agency Staff, access to all the records to this contract, for audit and inspection, and monitoring of services. Such access will be during normal business hours, or by appointment.
- 5. CONFLICT OF INTEREST:** CONTRACTOR represents that none of its officers or employees are officers or employees of the State of Utah, unless disclosure has been made in accordance with 67-16-8, Utah Code Annotated, 1953, as amended.
- 6. CONTRACTOR, AN INDEPENDENT CONTRACTOR:** The CONTRACTOR shall be an independent contractor, and as such, shall have no authorization, express or implied, to bind the State to any agreements, settlements, liability, or understanding whatsoever, and agrees not to perform any acts as agent for the State, except as herein expressly set forth. Compensation stated herein shall be the total amount payable to the CONTRACTOR by the State. The CONTRACTOR shall be responsible for the payment of all income tax and social security amounts due as a result of payments received from the State for these contract services. Persons employed by the State and acting under the direction of the State shall not be deemed to be employees or agents of the CONTRACTOR.
- 7. INDEMNITY CLAUSE:** The CONTRACTOR agrees to indemnify, save harmless, and release the State of Utah, and all its officers, agents, volunteers, and employees from and against any and all loss, damages, injury, liability, suits, and proceedings arising out of the performance of this contract which are caused in whole or in part by the negligence of the CONTRACTOR's officers, agents, volunteers, or employees, but not for claims arising from the State's sole negligence.
- 8. EQUAL OPPORTUNITY CLAUSE:** The CONTRACTOR agrees to abide by the provisions of Title VI and VII of the Civil Rights Act of 1964 (42USC 2000e) which prohibits discrimination against any employee or applicant for employment or any applicant or recipient of services, on the basis of race, religion, color, or national origin; and further agrees to abide by Executive Order No. 11246, as amended, which prohibits discrimination on the basis of sex; 45 CFR 90 which prohibits discrimination on the basis of age; and Section 504 of the Rehabilitation Act of 1973, or the Americans with Disabilities Act of 1990 which prohibits discrimination on the basis of disabilities. Also, the CONTRACTOR agrees to abide by Utah's Executive Order, dated March 17, 1993, which prohibits sexual harassment in the work place.
- 9. SEPARABILITY CLAUSE:** A declaration by any court, or any other binding legal source, that any provision of this contract is illegal and void shall not affect the legality and enforceability of any other provision of this contract, unless the provisions are mutually dependent.
- 10. RENEGOTIATION OR MODIFICATIONS:** This contract may be amended, modified, or supplemented only by written amendment to the contract, executed by the same persons or by persons holding the same position as persons who signed the original agreement on behalf of the parties hereto, and attached to the original signed copy of the contract.

Contract  
MiVida and Standard Shaft Project

**11. DEBARMENT:** The CONTRACTOR certifies that neither it nor its principals are presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction (contract), by any governmental department or agency. If the CONTRACTOR cannot certify this statement, attach a written explanation for review by the State. The CONTRACTOR must notify the State Director of Purchasing within 30 days if debarred by any governmental entity during the Contract period.

**12. TERMINATION:** Unless otherwise stated in the Special Terms and Conditions, this contract may be terminated, with cause by either party, in advance of the specified termination date, upon written notice being given by the other party. The party in violation will be given ten (10) working days after notification to correct and cease the violations, after which the contract may be terminated for cause. This contract may be terminated without cause, in advance of the specified expiration date, by either party, upon 90 days prior written notice being given the other party. On termination of this contract, all accounts and payments will be processed according to the financial arrangements set forth herein for approved services rendered to date of termination.

**13. NONAPPROPRIATION OF FUNDS:** The CONTRACTOR acknowledges that the State cannot contract for the payment of funds not yet appropriated by the Utah State Legislature. If funding to the State is reduced due to an order by the Legislature or the Governor, or is required by State law, or if federal funding (when applicable) is not provided, the State may terminate this contract or proportionately reduce the services and purchase obligations and the amount due from the State upon 30 days written notice. In the case that funds are not appropriated or are reduced, the State will reimburse CONTRACTOR for products delivered or services performed through the date of cancellation or reduction, and the State will not be liable for any future commitments, penalties, or liquidated damages.

**14. SALES TAX EXEMPTION:** The State of Utah's sales and use tax exemption number is E33399. The tangible personal property or services being purchased are being paid from State funds and used in the exercise of that entity's essential functions. If the items being purchased are construction materials, they will be converted into real property by employees of this government entity, unless otherwise stated in the contract.

**15. WARRANTY:** The CONTRACTOR agrees to warrant and assume responsibility for all products (including hardware, firmware, and/or software products) that it licenses, contracts, or sells to the State of Utah under this contract for a period of one year, unless otherwise specified and mutually agreed upon elsewhere in this contract. The CONTRACTOR (seller) acknowledges that all warranties granted to the buyer by the Uniform Commercial Code of the State of Utah apply to this contract. Product liability disclaimers and/or warranty disclaimers from the seller are not applicable to this contract unless otherwise specified and mutually agreed upon elsewhere in this contract. In general, the CONTRACTOR warrants that: (1) the product will do what the salesperson said it would do, (2) the product will live up to all specific claims that the manufacturer makes in their advertisements, (3) the product will be suitable for the ordinary purposes for which such product is used, (4) the product will be suitable for any special purposes that the State has relied on the CONTRACTOR's skill or judgment to consider when it advised the State about the product, (5) the product has been properly designed and manufactured, and (6) the product is free of significant defects or unusual problems about which the State has not been warned. Remedies available to the State include the following: The CONTRACTOR will repair or replace (at no charge to the State) the product whose nonconformance is discovered and made known to the CONTRACTOR in writing. If the repaired and/or replaced product proves to be inadequate, or fails of its essential purpose, the CONTRACTOR will refund the full amount of any payments that have been made. Nothing in this warranty will be construed to limit any rights or remedies the State of Utah may otherwise have under this contract.

**16. PUBLIC INFORMATION:** CONTRACTOR agrees that the contract will be a public document, and may be available for distribution. And CONTRACTOR gives the State express permission to make copies of the contract and/or of the response to the solicitation in accordance with the State of Utah Government Records Access and Management Act. The permission to make copies as noted will take precedence over any statements of confidentiality, proprietary information, copyright information, or similar notation.

**17. DELIVERY:** Unless otherwise specified in this contract, all deliveries will be F.O.B. destination with all transportation and handling charges paid by the CONTRACTOR. Responsibility and liability for loss or damage will remain with CONTRACTOR until final inspection and acceptance when responsibility will pass to the State except as to latent defects, fraud and CONTRACTOR's warranty obligations.

**18. ORDERING AND INVOICING:** All orders will be shipped promptly in accordance with the delivery schedule. The CONTRACTOR will promptly submit invoices (within 30 days of shipment or delivery of services) to the State.

The State contract number and/or the agency purchase order number shall be listed on all invoices, freight tickets, and correspondence relating to the contract order. The prices paid by the State will be those prices listed in the contract. The State has the right to adjust or return any invoice reflecting incorrect pricing.

19. PAYMENT: Payments are normally made within 30 days following the date the order is delivered or the date a correct invoice is received, whichever is later. All payments to the CONTRACTOR will be remitted by mail unless paid by the State of Utah's Purchasing Card.

20. PATENTS, COPYRIGHTS, ETC.: The CONTRACTOR will release, indemnify and hold the State, its officers, agents and employees harmless from liability of any kind or nature, including the CONTRACTOR's use of any copyrighted or un-copyrighted composition, secret process, patented or un-patented invention, article or appliance furnished or used in the performance of this contract.

21. ASSIGNMENT/SUBCONTRACT: CONTRACTOR will not assign, sell, transfer, subcontract or sublet rights, or delegate responsibilities under this contract, in whole or in part, without the prior written approval of the State.

22. DEFAULT AND REMEDIES: Any of the following events will constitute cause for the State to declare CONTRACTOR in default of the contract: 1. Nonperformance of contractual requirements; 2. A material breach of any term or condition of this contract. The State will issue a written notice of default providing a ten (10) day period in which CONTRACTOR will have an opportunity to cure. Time allowed for cure will not diminish or eliminate CONTRACTOR's liability for damages. If the default remains, after CONTRACTOR has been provided the opportunity to cure, the State may do one or more of the following: 1. Exercise any remedy provided by law; 2. Terminate this contract and any related contracts or portions thereof; 3. Impose liquidated damages, if liquidated damages are listed in the contract; 4. Suspend CONTRACTOR from receiving future solicitations.

23. FORCE MAJEURE: Neither party to this contract will be held responsible for delay or default caused by fire, riot, acts of God and/or war which is beyond that party's reasonable control. The State may terminate this contract after determining such delay or default will reasonably prevent successful performance of the contract.

24. PROCUREMENT ETHICS: The CONTRACTOR understands that a person who is interested in any way in the sale of any supplies, services, construction, or insurance to the State of Utah is violating the law if the person gives or offers to give any compensation, gratuity, contribution, loan or reward, or any promise thereof to any person acting as a procurement officer on behalf of the State, or who in any official capacity participates in the procurement of such supplies, services, construction, or insurance, whether it is given for their own use or for the use or benefit of any other person or organization (63-56-73, Utah Code Annotated, 1953, as amended).

25. CONFLICT OF TERMS: CONTRACTOR Terms and Conditions that apply must be in writing and attached to the contract. No other Terms and Conditions will apply to this contract including terms listed or referenced on a CONTRACTOR's website, terms listed in a CONTRACTOR quotation/sales order, etc. In the event of any conflict in the contract terms and conditions, the order of precedence shall be: 1. State Standard Terms and Conditions; 2. State Special Terms and Conditions; 3. CONTRACTOR Terms and Conditions.

DOGM Standard Terms and Conditions (revised 06/11/04)

Reference: Division of Purchasing Standard Terms and Conditions (revised 11/21/03)

End Attachment A

Contract  
MiVida and Standard Shaft Project

ATTACHMENT B  
SCOPE OF WORK

SCOPE OF WORK, hereinafter the WORK, to be performed is that contained in the Drawings and Technical Specifications prepared by: the Division of Oil, Gas & Mining and entitled *TECHNICAL SPECIFICATIONS: MiVida and Standard Shaft Project Reclamation Construction*; the General Specifications prepared by the Division of Oil, Gas and Mining entitled *GENERAL CONDITIONS FOR ABANDONED MINE RECLAMATION PROJECTS*, dated June 1988; and the Supplementary Conditions listed in the Technical Specifications cited above.

The CONTRACTOR agrees to furnish all labor, materials and equipment to complete the WORK as described the Drawings, Specifications, and addenda to the specifications which are hereby made a part of this CONTRACT by reference. It is understood and agreed by the parties hereto that all WORK will be performed as required in the Drawings and Specifications and will be subject to inspection and approval prior to final acceptance by the OWNER. The relationship of the CONTRACTOR to the OWNER hereunder is that of an independent CONTRACTOR.

End Attachment B

ATTACHMENT C  
DIVISION OF OIL, GAS AND MINING  
CONSTRUCTION TERMS AND CONDITIONS

ARTICLE 1. TIME OF COMPLETION. The WORK under this CONTRACT shall be commenced upon notice to proceed and shall be completed within 30 calendar days after date marked on registered receipt of said Notice to Proceed and no later than December 31, 2005. WORK delays caused by weather may, at the discretion of the OWNER, extend the completion date. CONTRACTOR also agrees to the liquidated damages provisions of Article 12.

ARTICLE 2. PAYMENT. OWNER will promptly pay for services performed by the CONTRACTOR. Vouchers for reimbursement of expenditures under this Agreement must be filed promptly with OWNER's Representative by the tenth day of the month following the month in which WORK has been performed. OWNER will withhold from payment an amount not to exceed 10% of the total CONTRACT cost, except for Mobilization, which will have 40% withheld, until all WORK has been performed by the CONTRACTOR and is approved and accepted by OWNER.

ARTICLE 3. INDEBTEDNESS. Before final payment is made, the CONTRACTOR must submit evidence including lien waivers, satisfactory to the OWNER that all payrolls, materials bills, subcontracts and outstanding indebtedness in connection with the WORK have been paid or that arrangements have been made for their payment. Payment will be made without unnecessary delay after receipt of such evidence as mentioned above and Final Acceptance of the WORK by the OWNER.

ARTICLE 4. ADDITIONAL WORK. It is understood and agreed by the parties hereto that no money will be paid to the CONTRACTOR for any additional WORK, labor or materials furnished unless a new CONTRACT in the form of a Change Order or a modification hereof for such additional materials or labor has been executed by OWNER and CONTRACTOR. The OWNER specifically reserves the right to modify or amend this CONTRACT and the total sum due hereunder either by enlarging or restricting the WORK through a change order.

ARTICLE 5. ACCEPTANCE. The WORK will be inspected for acceptance by the OWNER promptly upon receipt of notice from the CONTRACTOR that the WORK is complete and ready for inspection.

ARTICLE 6. DISPUTES PERTAINING TO PAYMENT FOR WORK. Any disputes which may arise respecting the value of any WORK done, or any WORK omitted, or of any ADDITIONAL WORK which CONTRACTOR may be required to perform, or respecting any other elements involved in this CONTRACT, will be decided by the Director of the Division of Oil, Gas & Mining, acting as the OWNER.

ARTICLE 7. TERMINATION OF CONTRACT

- a. If the CONTRACTOR is adjudged bankrupt or if the CONTRACTOR makes a general assignment for the benefit of CONTRACTOR'S creditors or if a receiver is appointed on account of CONTRACTOR'S insolvency, or if CONTRACTOR or any of his/her Subcontractors violates any of the provisions of this CONTRACT, or if the

CONTRACTOR does not perform the WORK according to the Specifications, the OWNER may serve written notice upon CONTRACTOR of its intention to terminate the CONTRACT; and unless within ten (10) days after the serving of the notice, the violation ceases, the OWNER then may take over the WORK and at the expense of the CONTRACTOR, complete it by contract or by any other method it may deem advisable. The CONTRACTOR will be liable to the OWNER for any excess cost incurred by the OWNER and the OWNER may, without liability for so doing, take possession of and utilize in completing the WORK, such materials, appliances, paint, and any other property belonging to the CONTRACTOR as may be on the site of the WORK.

- b. OWNER may terminate this Agreement upon thirty days written notice to CONTRACTOR in the event the U.S. Department of the Interior fails to grant to OWNER sufficient funds to meet its obligations under this Agreement. In such event, CONTRACTOR will be entitled to receive just and equitable compensation for any satisfactory WORK completed up to the time of termination.

ARTICLE 8. OWNER'S RIGHT TO WITHHOLD CERTAIN AMOUNT AND MAKE APPLICATION THEREOF. The OWNER may withhold from payment to the CONTRACTOR an amount or amounts as, in the OWNER'S judgment, may be necessary to pay just claims against the CONTRACTOR or any Subcontractor for labor and services rendered and materials furnished in and about the WORK. The OWNER in its discretion may apply the withheld amounts on the payment of such claims. In so doing the OWNER will be deemed the agent of the CONTRACTOR and payments so made by the OWNER will be considered as a payment made under the CONTRACT by the OWNER to the CONTRACTOR and the OWNER will not be liable to the CONTRACTOR for any such payments made in good faith. Such payments may be made without prior determination of the claim or claims.

ARTICLE 9. INDEPENDENT CONTRACTOR. The CONTRACTOR will be considered an independent contractor, and, as such, has no authorization, expressed or implied, to bind the State of Utah or the OWNER to any agreement, settlement, liability or understanding whatsoever, nor to perform any acts as agent for the State of Utah, except as herein expressly set forth. The compensation provided for herein will be the total compensation payable hereunder by the State of Utah or the OWNER.

ARTICLE 10. LIABILITY AND INDEMNIFICATION. It is agreed that the CONTRACTOR will at all times protect and indemnify and save harmless, the State of Utah and all institutions, agencies, departments, authorities and instrumentalities of the State of Utah and any member of their governing bodies or of their boards or commissions or any of their elected or appointed officers or any of their employees or authorized volunteers, or the private landowners who have consented to reclamation construction and/or have consented to allow ingress or egress to a reclamation site, as described in the general conditions of the project specifications which are included herein by reference, from any and all claims, damages of every kind and nature made, rendered or incurred by or in behalf of any person or corporation whatsoever, including the parties hereto and their employees that may arise, occur or grow out of any acts, actions, work or other activity done by the CONTRACTOR in the performance and execution of this CONTRACT.

ARTICLE 11. SUBCONTRACTOR. No part of this CONTRACT may be sublet by the CONTRACTOR without the prior written approval of the OWNER. The CONTRACTOR and the OWNER for themselves, their heirs, successors, executors, and administrators, hereby agree to the full performance of the covenants herein contained.

ARTICLE 12. LIQUIDATED DAMAGES. In the event the CONTRACTOR fails to complete the WORK within the time agreed upon in CONTRACTOR's schedule as set forth in Article 2, or within such additional time as may have been allowed by the OWNER, there will be deducted from any moneys due or that may become due the CONTRACTOR the sum of \$781.00 per day for each and every calendar day beyond the agreed or extended completion day that the WORK remains uncompleted. Such sum is fixed and agreed upon by the OWNER and the CONTRACTOR as liquidated damages due the OWNER by reason of the inconvenience and added costs of administration, engineering and supervision resulting from the CONTRACTOR's default, and not as a penalty.

Permitting the CONTRACTOR to continue and finish the WORK or any part of it after the time fixed for its completion, or after the date to which the time for completion may have been extended, in no way operates as a waiver on the part of the OWNER of any of OWNER'S rights under the CONTRACT.

ARTICLE 13. DEFAULT: In the event of default by the CONTRACTOR, termination may be executed as described by the Termination for Default Clause of the DIVISION OF OIL, GAS AND MINING GENERAL CONDITIONS FOR ABANDONED MINE RECLAMATION PROJECTS.

Contract  
MiVida and Standard Shaft Project

**ARTICLE 14. NONAPPROPRIATION OF FUNDS:** Financial obligations of the OWNER payable after the current fiscal year are contingent upon funds for the purpose being appropriated, budgeted or otherwise made available. If funds are not appropriated or otherwise available to continue the payment, this contract may be terminated without penalty by giving thirty (30) days written notice.

**ARTICLE 15. CERTIFICATIONS:** PART A: Certification Regarding Debarment, Suspension, Ineligibility and Voluntary Exclusion – Lower Tier Covered Transactions. 1) The CONTRACTOR certifies that neither it nor its principals is presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this transaction (contract), by any Federal department or agency. 2) Where the CONTRACTOR is unable to certify to any of the statements in this certification, such prospective participant shall attach an explanation to this proposal. PART B: Certification Regarding Lobbying. The undersigned certifies, to the best of his or her knowledge and belief, that: 1) No Federal appropriated funds have been paid or will be paid, by or on behalf of the undersigned, to any person for influencing or attempting to influence an officer or employee of an agency, a Member of Congress and officer or employee of Congress, or an employee of a Member of Congress in connection with the awarding of any Federal contract, the making of any Federal grant, the making of any Federal loan, the entering into of any cooperative agreement and the extension, continuation, renewal, amendment, or modification of any Federal contract, grant, loan, or cooperative agreement. 2) If any funds other than Federal appropriated funds have been paid or will be paid to any person for influencing or attempting to influence an officer or employee of any agency, a Member of Congress, an officer or employee of Congress, or an employee of a Member of Congress in connection with this Federal contract, grant, loan, or cooperative agreement, the undersigned shall complete and submit Standard Form-LLL, "Disclosure Form to Report Lobbying," in accordance with its instructions. This certification is a material representation of fact upon which reliance was placed when this transaction was made or entered into. Submission of this certification is a prerequisite for making or entering into this transaction imposed by Section 1352, title 31, U.S. Code. Any person who fails to file the required certification shall be subject to a civil penalty of not less than \$10,000 and not more than \$100,000 for each such failure.

The CONTRACTOR was selected for this contract in accordance with the State of Utah, Division of Purchasing's Regulations for the Procurement of Construction and Professional Services.

DOGM Construction Terms and Conditions (revised 09/24/03)

End Attachment C

ATTACHMENT D  
COST SCHEDULE

*The Cost Schedule will be generated from the Bid Schedule following the award of the CONTRACT.*

## Performance Bond

(Title 63, Chapter 56, U. C. A. 1953, as Amended)

KNOW ALL MEN BY THESE PRESENTS:

That \_\_\_\_\_, hereinafter referred to as the "Principal," and \_\_\_\_\_, a corporation organized and existing under the laws of the State of \_\_\_\_\_, with its principal office in the City of \_\_\_\_\_, hereinafter referred to as the "Surety," are held and firmly bound unto \_\_\_\_\_, hereinafter referred to as the "Obligee," in the amount of \_\_\_\_\_ DOLLARS (\$\_\_\_\_\_) for the payment whereof, the said Principal and Surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has entered into a certain written Contract with the Obligee, dated the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_, which Contract is hereby referred to and made a part hereof as fully and to the same extent as if copied at length herein.

NOW, THEREFORE, the condition of this obligation is such that if the said Principal shall faithfully perform the Contract in accordance with the Plans, Specifications and conditions thereof, then this obligation shall be void; otherwise it shall remain in full force and effect.

PROVIDED, HOWEVER, that this Bond is executed pursuant to the provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as Amended, and all liabilities on this Bond shall be determined in accordance with said provisions to the same extent as if it were copied at length herein.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

WITNESS OR ATTESTATION:

\_\_\_\_\_

WITNESS:

\_\_\_\_\_

\_\_\_\_\_  
Principal (Seal)

\_\_\_\_\_  
By (Seal)

Surety

\_\_\_\_\_  
By

STATE OF UTAH )  
 ) ss  
COUNTY OF SALT LAKE )

\_\_\_\_\_, being first duly sworn on oath, deposes and says that he/she is the Attorney-in-fact of the \_\_\_\_\_ and that he/she is duly authorized to execute and deliver the foregoing obligation that said company is authorized to execute the same, and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations.

Subscribed and sworn to before me this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_.

\_\_\_\_\_  
NOTARY PUBLIC  
My commission expires: \_\_\_\_\_

APPROVED AS TO FORM: ATTORNEY GENERAL'S OFFICE

## Payment Bond

(Title 63, Chapter 56, U. C. A. 1953, as Amended)

KNOW ALL MEN BY THESE PRESENTS:

That \_\_\_\_\_, hereinafter referred to as the "Principal," and \_\_\_\_\_, a corporation organized and existing under the laws of the State of \_\_\_\_\_, with its principal office in the City of \_\_\_\_\_, hereinafter referred to as the "Surety," are held and firmly bound unto \_\_\_\_\_, hereinafter referred to as the "Obligee," in the amount of \_\_\_\_\_ DOLLARS (\$\_\_\_\_\_) for the payment whereof, the said Principal and surety bind themselves and their heirs, administrators, executors, successors and assigns, jointly and severally, firmly by these presents.

WHEREAS, the Principal has entered into a certain written Contract with the Obligee, dated the \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_, which Contract is hereby referred to and made a part hereof as fully and to the same extent as if copied at length herein.

NOW, THEREFORE, the condition of this obligation is such that if the said Principal shall pay all claimants supplying labor or materials to him/her or his/her subcontractors in the prosecution of the work provided for in said Contract, then, this obligation shall be void; otherwise it shall remain in full force and effect.

PROVIDED, HOWEVER, that this bond is executed pursuant to the provisions of Title 63, Chapter 56, Utah Code Annotated, 1953, as amended and all liabilities on this bond to all such claimants shall be determined in accordance with said provisions to the same extent as if it were copies at length herein.

IN WITNESS WHEREOF, the said Principal and Surety have signed and sealed this instrument this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_.

(Seal)

WITNESS OR ATTESTATION:

(Seal)

WITNESS:

\_\_\_\_\_  
Principal

\_\_\_\_\_  
By

\_\_\_\_\_  
Surety

\_\_\_\_\_  
By

STATE OF UTAH                    )  
  ) ss  
COUNTY OF SALT LAKE        )

\_\_\_\_\_, being first duly sworn on oath, deposes and says that he/she is the Attorney-in-fact of the \_\_\_\_\_ and that he/she is duly authorized to execute and deliver the foregoing obligation that said company is authorized to execute the same, and has complied in all respects with the laws of Utah in reference to becoming sole surety upon bonds, undertakings and obligations.

Subscribed and sworn to before me this \_\_\_\_\_ day of \_\_\_\_\_, 20\_\_\_\_\_.

\_\_\_\_\_  
NOTARY PUBLIC

My commission expires: \_\_\_\_\_

APPROVED AS TO FORM: ATTORNEY GENERAL'S OFFICE



# STATE OF UTAH CONTRACT AMENDMENT

**AMENDMENT #** \_\_\_\_\_ **to CONTRACT #** \_\_\_\_\_

TO BE ATTACHED TO AND MADE A PART OF the above numbered contract by and between the State of Utah, Division Of Oil, Gas And Mining, referred to as STATE and, FIRM NAME, referred to as CONTRACTOR.

MiVida and Standard Shaft Project

AMR/037/909

**THE PARTIES AGREE TO AMEND THE CONTRACT AS FOLLOWS:**

- |   |  |
|---|--|
| <p><b>1. Contract period:</b><br/>(original starting date) _____<br/><br/>(current ending date) _____<br/><br/><b>new ending date</b> _____</p> | <p><b>2. Contract amount:</b><br/>(current contract amount) _____<br/><br/>(amendment amount) _____<br/><br/><b>new contract amount</b><br/>(add current amount to amendment amount) _____</p> |
|---|--|

**3. Change Details:**

Fund	Agency	Org	Approp. Unit	Activity (Mine)	Grant Category	Project or Job
100	560	2881	REG			NF MDV 08 B

ITEM NO.	DESCRIPTION OF CHANGES IN QUANTITIES, UNIT PRICES, SCHEDULE, ETC.	INCREASE (DECREASE)
1.	DESCRIPTION OF CHANGES IN QUANTITIES, UNIT PRICES, SCHEDULE.	\$***
2.	DESCRIPTION OF CHANGES IN QUANTITIES, UNIT PRICES, SCHEDULE.	\$***
3.	DESCRIPTION OF CHANGES IN QUANTITIES, UNIT PRICES, SCHEDULE	\$***
4.	SUBTOTAL	\$***
5.	BONDS & INSURANCE (6% of Change Order Amount)	\$***
6.	TOTAL AMOUNT OF CHANGE ORDER	\$***

**4. Effective Date of Amendment:**

All other conditions and terms in the original contract remain the same.  
IN WITNESS WHEREOF, the parties sign and cause the amendment to be executed.

Approved by _____	Date: _____
Contract Rep: _____	
Approved by _____	Date: _____
AMR Admin: _____	
Accepted by _____	Date: _____
Contractor: _____	
Approved by _____	Date: _____
DOGM Budget Off: _____	
Approved by _____	Date: _____
DOGM Director: _____	
Approved by _____	Date: _____
Div'n Purchasing: _____	
Approved by _____	Date: _____
Div'n of Finance: _____	

## Certificate Of Substantial Completion

UTAH DIVISION OF OIL, GAS AND MINING

PROJECT MiVida and Standard Shaft Project

PROJECT NO. AMR/037/909

CONTRACT NO. #

The WORK performed under the subject CONTRACT has been reviewed on this date and found to be substantially completed.

### DEFINITION OF SUBSTANTIAL COMPLETION

*The date of substantial completion of a project or specified area of a project is the date when the construction is sufficiently completed in accordance with the Contract Documents, as modified by any change orders agreed to by the parties, so that the OWNER can occupy the project or specified area of the project for the use for which it was intended.*

A list of items to be completed or corrected, prepared by the Division of Oil, Gas & Mining and verified by the OWNER, is appended hereto. This list may not be exhaustive, and the failure to include an item on it does not alter the responsibility of the CONTRACTOR to complete all the WORK in accordance with the Contract Documents, including authorized changes thereof.

Division of Oil, Gas & Mining

\_\_\_\_\_  
CONTRACT REPRESENTATIVE      DATE

The CONTRACTOR will complete or correct the work on the list of items appended hereto within \_\_\_\_\_ days from the above date of issuance of this Certificate.

\_\_\_\_\_  
CONTRACTOR

\_\_\_\_\_  
AUTHORIZED REPRESENTATIVE      DATE

The OWNER accepts the project or specified area of the project as substantially complete and will assume full possession of the project or specified area of the project at \_\_\_\_\_ (time) on \_\_\_\_\_ (date).

Division of Oil, Gas & Mining

OWNER

\_\_\_\_\_  
CONTRACT REPRESENTATIVE      DATE

\_\_\_\_\_  
ADMINISTRATOR, AMR      DATE

RESPONSIBILITIES AND/OR EXCEPTIONS:

This form used by permission of A.I.A.  
DIVISION OF FACILITIES CONSTRUCTION AND MANAGEMENT

## Certificate Of Final Acceptance

### UTAH DIVISION OF OIL, GAS AND MINING

PROJECT MiVida and Standard Shaft Project

PROJECT NO. AMR/037/909  
CONTRACT NO. #

The WORK performed under the subject CONTRACT has been reviewed on this date and found to be completed.

### DEFINITION OF FINAL ACCEPTANCE

*The date of final acceptance of a project is the date when the construction is completed in accordance with the Contract Documents, as modified by any change orders agreed to by the parties, so that the OWNER can occupy the project for the use for which it was intended.*

Items listed on the Certificate of Substantial Completion, as prepared by the Division of Oil, Gas & Mining, have been completed or corrected and verified by the OWNER as having been completed or corrected.

Division of Oil, Gas & Mining  
OWNER

\_\_\_\_\_  
INSPECTOR DATE

\_\_\_\_\_  
CONTRACT REPRESENTATIVE DATE

\_\_\_\_\_  
CONTRACTOR

\_\_\_\_\_  
AUTHORIZED REPRESENTATIVE DATE

The OWNER accepts the project as complete and will assume full possession of the project or specified area of the project at \_\_\_\_\_ pm (time) on \_\_\_\_\_, 20\_\_\_\_ (date).

Division of Oil, Gas & Mining  
OWNER

\_\_\_\_\_  
ADMINISTRATOR, AMRP DATE



# **General Conditions For Abandoned Mine Reclamation Projects**

## **CONTENTS**

1. Definitions
2. Correlation and Intent of Documents
3. Copies Furnished
4. Dimensions
5. Detail Drawings and Instructions
6. Drawings and Specifications on the Work
7. Ownership of Drawings
8. Shop Drawings
9. Samples
10. Materials, Appliances, Employees
11. Royalties and Patents
12. Surveys, Permits and Regulations
13. Protection of WORK and Property
14. Inspection of WORK
15. Superintendence and Supervision
16. Changes
17. Claims Based on OWNER's Actions or Omissions
18. Deductions for Uncorrected Work
19. Delays and Extension of Time
20. Correction of WORK Before Final Payment
21. Correction of WORK After Final Payment
22. Termination for Default Clause
23. Application for Payments
25. Liability Insurance
26. Property Insurance
27. Indemnification
28. Guarantee Bonds
29. Liens
30. Assignment
31. Mutual Responsibility of CONTRACTORS
32. Separate Contracts
33. Subcontractors
34. Relations of CONTRACTOR and Subcontractor
35. State's Inspection
36. Contract Representative's Status
37. Contract Representative's Decisions
38. Cash Allowances
39. Use of Premises
40. Cutting, Patching and Digging
41. Cleaning Up
42. Substitutions
43. Laying Out WORK
44. Emergencies
45. Testing of Materials
46. Temporary Enclosing, Drying Out, Etc.
47. Examination of Site
48. Storage and Care of Materials
49. Construction Risks
50. Temporary Appurtenances and Conveniences
51. Scaffolding, Tools, Etc.
52. Sanitary Provisions
53. Refuse
54. Removing Water
55. Taxes
56. Citizens Preferred
57. Code Requirements
58. Nondiscrimination and Affirmative Action
59. Affirmative Action
60. Safety
61. Rubbish Disposal
62. Subcontractors Financial Bid Limits and License Classification
63. Balancing and Testing
64. Substantial Completion
65. Other Prohibited Interests
66. Conflicting Conditions
67. Monthly Progress Meetings
68. Suspension of WORK
69. Differing Site Conditions
70. Price Adjustment
71. Termination for Convenience of the OWNER
72. Liquidated Damages
73. Termination for Breach, Etc.
74. Normal Daylight Hours
75. Normal Working Days
76. Use of Explosives
77. Compliance with Copeland Regulations
78. Overtime Compensation
79. Clean Air and Water

## General Conditions

### **DIVISION OF OIL, GAS AND MINING GENERAL CONDITIONS FOR ABANDONED MINE RECLAMATION PROJECTS**

#### **1. Definitions:**

- A. The CONTRACT documents consist of the agreement, the general conditions of the CONTRACT, the drawings and specifications, including all modifications thereof incorporated in the documents before their execution. These form the CONTRACT.
- B. The OWNER and the CONTRACTOR or pronouns used in place thereof, are those mentioned as such in the agreement. They are treated throughout the CONTRACT documents as if each were in the singular number.
- C. The term "Subcontractor," as employed herein, includes anyone having a direct CONTRACT with anyone except the OWNER to provide material and/or labor under this CONTRACT, and it includes one who furnishes material worked to a special design according to the plans and/or specifications of this WORK, but does not include one who merely furnishes material not so worked.
- D. The word "state," or pronoun used in place thereof, is to designate the State of Utah, as represented by the Division of Oil, Gas & Mining.
- E. The word "OWNER," or pronoun used in place thereof, is to designate the State of Utah, as represented by the Division of Oil, Gas & Mining.
- F. The term "WORK" of the CONTRACTOR or subcontractor includes labor or materials or both, and the SCOPE OF WORK.
- G. The term "site" shall be used to refer to all areas where the WORK is to be performed.
- H. The term "engineer" shall be used to refer to a consultant representing the OWNER or a designated representative of the OWNER.
- I. The applicable laws and regulations of the State of Utah shall govern the execution of the WORK embodied in the contract documents.

#### **2. Correlation and Intent of Documents:**

The CONTRACT documents are complementary, and what is called for by any one shall be as binding as if called for by all. The intention of the documents is to include all labor and materials, equipment, and transportation necessary for the proper and complete execution of the WORK, and equal in quality and workmanship to the highest standards. The CONTRACTOR is to abide by and comply with the true intent and meaning of all drawings and specifications taken as a whole and is not to avail himself to the detriment of the WORK, of any manifestly unintentional error or omission, should any exist. All minor details of WORK which are not shown on the plans, as well as such items as are not specifically mentioned in the

specifications but are obviously necessary for the proper completion of the WORK, shall be considered as incidental and as being part of the WORK.

#### **3. Copies Furnished:**

Unless otherwise provided in the CONTRACT documents, the OWNER will furnish the CONTRACTOR, free of charge to the CONTRACTOR, copies of drawings and specifications, reasonably necessary for the execution of the WORK.

#### **4. Dimensions:**

Where no figures or memoranda are given, the drawings shall be accurately followed according to their scale, but figures or memoranda are to be preferred to the scale, in all cases of difference, and the larger scale details shall take preference over those of smaller scale.

#### **5. Detail Drawings and Instructions:**

The OWNER shall furnish, with reasonable promptness, additional instructions, by means of drawings or otherwise, necessary for the proper execution of the WORK. All such drawings and instructions shall be consistent with the CONTRACT documents, true developments thereof, and reasonably inferable therefrom. The WORK shall be executed in conformity with the drawings and instructions. Any WORK performed by the CONTRACTOR in advance of these drawings and instructions shall be entirely at the CONTRACTOR's risk.

#### **6. Drawings and Specifications on the Work:**

The CONTRACTOR shall keep at the jobsite one copy of all drawings and specifications on the WORK in good order, available to the OWNER and their representatives.

#### **7. Ownership of Drawings:**

All copies of drawings and specifications furnished the CONTRACTOR by the OWNER are the property of the OWNER. They are not to be used by the CONTRACTOR on other work, and are to be returned to the OWNER, upon request, at the completion of the WORK.

#### **8. Shop Drawings/As Built Drawings:**

The CONTRACTOR shall submit to the OWNER, with such promptness as to cause no delay in his/her WORK or in that of any other CONTRACTOR, six copies of all shop/as built drawings or setting drawings and schedules required for the WORK of the various trades and the OWNER shall pass upon them with reasonable promptness, making desired corrections. Said corrections shall pertain to conformance with the basic design concepts embodied in the CONTRACT documents. The CONTRACTOR shall make any corrections required by the OWNER. The OWNER shall distribute the corrected drawings as follows: Two drawings to the OWNER; three drawings back to the general CONTRACTOR; and one drawing to the project inspector (if one is assigned to the job). The OWNER's

approval of such drawings or schedules shall not relieve the CONTRACTOR from responsibility for deviations from drawings or specifications, unless he/she has in writing called the OWNER's attention to such deviations at the time of submission, and has received the OWNER's written approval of such deviation; nor shall it relieve him/her from responsibility for errors of any sort in shop/as built drawings or schedules.

### **9. Samples:**

The CONTRACTOR shall furnish to the OWNER for approval, all samples as directed. The WORK shall be in accordance with approved samples.

### **10. Materials, Appliances, Employees:**

Unless otherwise stipulated, the CONTRACTOR shall provide and pay for all materials, labor, water, tools, equipment, light, power, transportation, and other facilities and services necessary for the execution and completion of the WORK.

Unless otherwise specified, all materials shall be new, and both workmanship and materials shall be of high quality. The CONTRACTOR shall, if required, furnish satisfactory evidence as to the kind and quality of materials.

The CONTRACTOR shall at all times enforce strict discipline and order among his/her employees, and shall not employ on the WORK any unfit person or anyone not skilled in the work assigned to him/her.

### **11. Royalties and Patents:**

The CONTRACTOR shall pay all royalties and license fees. He/she shall defend all suits or claims for infringement of any patent rights and shall save the OWNER harmless from loss on account thereof.

### **12. Surveys, Permits and Regulations:**

The OWNER shall furnish surveys necessary to establish site boundaries and existing topography. The OWNER shall provide those surveys necessary for laying out the WORK.

The CONTRACTOR shall give all notices and comply with all applicable laws, ordinances, rules and regulations bearing on the conduct of the WORK as drawn and specified. If the CONTRACTOR observes that the drawings and specifications are at variance therewith, he/she shall promptly notify the OWNER in writing, and any necessary changes shall be adjusted as provided in the contract for changes in the WORK. If the CONTRACTOR performs any work knowing it to be contrary to such laws, ordinances, rules and regulations and without such notice to the OWNER, he/she shall bear all costs arising therefrom.

Inasmuch as the WORK under this contract will be performed for the State of Utah, it will not be necessary to take out local building permits, electrical permits and plumbing permits, nor will it be necessary to pay fees for inspections pertaining thereto; however, it will be necessary to obtain a permit from the city, county, and

or Department of Transportation having jurisdiction whenever the WORK involves their property. The CONTRACTOR shall cooperate as necessary with these jurisdictions to comply with all their requirements, which may include a bond and permit fee.

Fees for connection to utilities such as water and power must be borne by the CONTRACTOR.

### **13. Protection of Work and Property:**

The CONTRACTOR shall continuously maintain adequate protection of all his/her WORK from damage and shall protect the OWNER's property from injury or loss arising in connection with this CONTRACT. CONTRACTOR shall make good any such damage, injury, or loss, except such as may be directly due to errors in the CONTRACT documents or caused by agents or employees of the OWNER. CONTRACTOR shall adequately protect adjacent property as provided by law and the CONTRACT documents.

The CONTRACTOR shall take all necessary precautions for the safety of employees on the WORK and shall comply with all applicable provisions of federal, state and municipal safety laws and building codes to prevent accidents or injury to persons on, about, or adjacent to the premises where the WORK is being performed. CONTRACTOR shall erect and properly maintain at all times, as required by the conditions and progress of the WORK, all necessary safeguards for the protection of workers and the public and shall post danger signs warning against hazardous conditions.

### **14. Inspection of Work:**

The OWNER and the representatives thereof and authorized federal government inspectors shall at all times have access to the WORK, and the CONTRACTOR shall provide proper facilities for such access and for inspection.

If the specifications or the OWNER requires any work to be specially tested or approved, the CONTRACTOR shall give the OWNER timely notice of its readiness for inspection. Inspections shall be promptly made and, where practicable, at the source of supply. If any WORK should be covered up without approval or consent of the OWNER, it must, if required by the OWNER, be uncovered for examination at the CONTRACTOR's expense.

### **15. Superintendence and Supervision:**

The CONTRACTOR shall keep on the WORK, during its progress, a competent superintendent and any necessary assistants, all satisfactory to the OWNER. The superintendent shall represent the CONTRACTOR in his/her absence, and all directions given to superintendent shall be as binding as if given to the CONTRACTOR.

The CONTRACTOR shall give efficient supervision to the WORK, using his/her best skill and attention. CONTRACTOR shall carefully study and compare all drawings, specifications and other instructions, and shall

## General Conditions

at once report to the OWNER any error, inconsistency, or omission which CONTRACTOR may discover, but shall not be held responsible for their existence or discovery.

### 16. Changes:

- A. Change Order. The OWNER, at any time, unilaterally and without notice to sureties, in writing designated or indicated to be a change order, may order:
- (1) Changes in the WORK within the scope of this CONTRACT;
  - (2) Changes in the time for performance of this CONTRACT that do not alter the scope of WORK of this CONTRACT; and/or
  - (3) Changes necessary to continue the WORK or to accommodate the OWNER with essential services required to complete the WORK as normally intended in accordance with specifications.
- B. Adjustments of Price or Time for Performance. If any change order increases or decreases the CONTRACTOR's cost of, or the time required for, performance of any part of the WORK under this CONTRACT, whether changed or not changed by any such change order, an equitable adjustment shall be made in the contract price or completion date, or both, and this contract shall be modified in writing accordingly. Any adjustment in contract price made pursuant to this clause shall be determined in accordance with the Price Adjustment Clause of this contract.

Failure of the parties to agree to an adjustment shall not excuse the CONTRACTOR from proceeding with this contract as changed, provided that the OWNER promptly and duly makes such provisional adjustments in payments or time for performance as the OWNER deems to be reasonable.

- C. Written Certification. No change order shall be authorized without a written certification, signed by an official of the OWNER responsible for monitoring and reporting the status of the costs of the total project or the contract budget, stating that funds are available therefor.

Where the OWNER has assigned an engineer to the project, the CONTRACTOR shall submit such proposals to the engineer in sufficient number that one copy may be transmitted to the OWNER, one to the project inspector, and one retained by the engineer. Upon acceptance of the proposal by all parties, a written change order will be issued.

Whenever a request for a change order proposal is received by the CONTRACTOR, he/she shall indicate thereon his/her proposed price to be added or deducted from the CONTRACT sum due to the change, together with his/her request for any adjustment in time of final completion of the entire CONTRACT.

It is further agreed that all time extensions to the completion date of the CONTRACT and any costs or changes in the CONTRACT price from any cause whatsoever that may be incurred as a result of the change order(s) are included in the change order as authorized.

### 17. Claims Based on OWNER's Actions or Omissions:

Notice of Claim. If any action or omission on the part of the OWNER, requiring performance changes within the scope of the CONTRACT and which are not covered by other clauses of this CONTRACT, constitutes the basis for a claim by the CONTRACTOR for additional compensation, damages, or an extension of time for completion, the CONTRACTOR shall continue the performance of the CONTRACT in compliance with the directions or orders of the OWNER, but by so doing, the CONTRACTOR shall not be deemed to have prejudiced any claim for additional compensation, damages, or an extension of time for completion; provided:

- (1) The CONTRACTOR shall have given written notice to the OWNER:
  - (a) Prior to the commencement of the WORK involved, if at that time the CONTRACTOR knows of the occurrence of such action or omission; or
  - (b) Within thirty (30) days after the CONTRACTOR knows of the occurrence of such action or omission, if the CONTRACTOR did not have such knowledge prior to the commencement of the WORK; or
  - (c) Such further time as may be allowed by the OWNER in writing.

This notice shall state that the CONTRACTOR regards the act or omission as a reason which may entitle the CONTRACTOR to additional compensation, damages, or an extension of time. The OWNER, upon receipt of such notice, may rescind such action, remedy such omission, or take such other steps as may be deemed advisable in the discretion of the OWNER.

- (2) The notice required by Subparagraph (A)(1) of this paragraph describes as clearly as practicable at the time the reasons why the CONTRACTOR believes that additional compensation, damages, or an extension of time may be remedies to which the CONTRACTOR is entitled; and
- (3) The CONTRACTOR maintains and, upon request, makes available to the OWNER within a reasonable time, detailed records to the extent practicable, of the claimed additional costs or basis for an extension of time in connection with such changes.

### 18. Deductions for Uncorrected Work:

If the OWNER deems it inexpedient to correct WORK damaged or done not in accordance with the CONTRACT, an equitable deduction from the CONTRACT price shall be made therefor.



**19. Delays and Extension of Time:**

If the CONTRACTOR is significantly delayed at any time in the progress of the WORK by any act or neglect of the OWNER, or of any employee of either, or by any separate CONTRACTOR employed by the OWNER, or by significant changes ordered in the WORK or by strikes, lockouts, fire, unavoidable casualties or any causes beyond the CONTRACTOR's control, or by any cause which the OWNER shall decide justifies the delay, then the time of completion shall be extended for such reasonable time as the OWNER may decide. No action shall lie against the OWNER for damages or other claims due to losses attributable to hindrances or delays from any cause whatsoever, including acts and omissions of the OWNER or its agents; however, the CONTRACTOR may receive an extension of time in which to complete the WORK under this CONTRACT as provided above. The right to apply for such an extension of time shall be the exclusive remedy available to the CONTRACTOR or any Subcontractor as against the OWNER for such loss.

Any request for extension of time shall be made to the OWNER in writing within seven (7) days from the time of occurrence of cause for delay. In case of a continuing cause of delay, only one claim is necessary.

**20. Correction of WORK Before Final Payment:**

The CONTRACTOR shall promptly remove from the premises all WORK condemned by the OWNER as failing to conform to the CONTRACT, whether incorporated or not, and the CONTRACTOR shall promptly replace and reexecute his/her own WORK in accordance with the CONTRACT and without expense to the State of Utah and shall bear the expense of making good all WORK of other CONTRACTORS destroyed or damaged by such removal or replacement.

If the CONTRACTOR does not remove such condemned WORK within a reasonable time, fixed by written notice, the OWNER may have the materials removed and stored at the expense of the CONTRACTOR.

**21. Correction of WORK After Final Payment:**

Neither the final certificate of payment nor any provision in the CONTRACT documents nor partial or entire occupancy of the premises by the OWNER shall constitute an acceptance of WORK not done in accordance with the CONTRACT documents or relieve the CONTRACTOR of liability in respect to any express warranties or responsibility for faulty materials or workmanship. The CONTRACTOR shall remedy any defects in the WORK and pay for any damage to other WORK resulting therefrom which shall appear within a period of one year from the date of substantial completion of the WORK, unless a longer period is specified. The OWNER will give notice of observed defects with reasonable promptness.

**22. Termination for Default Clause:**

- A. The OWNER may, subject to the provisions of Paragraph (C) below, by written notice of default to

the CONTRACTOR, terminate the whole or any part of this CONTRACT in any one of the following circumstances:

- (1) If the CONTRACTOR fails to perform this CONTRACT within the time specified herein or any extension thereof; or
  - (2) If the CONTRACTOR fails to perform any of the other provisions of this CONTRACT, or so fails to make progress as to endanger performance of this CONTRACT in accordance with its terms, and in either of these two circumstances does not cure such failure within a period of five (5) days (or such longer period as the OWNER may authorize in writing) after receipt of notice from the OWNER specifying such failure.
- B. In the event the OWNER terminates this CONTRACT in whole or in part as provided in Paragraph (A) of this clause, the OWNER may procure, upon such terms and in such manner as the OWNER may deem appropriate, supplies or services similar to those so terminated, and the CONTRACTOR shall be liable to the OWNER for any excess costs for such similar supplies or services; provided that the CONTRACTOR shall continue the performance of this CONTRACT to the extent not terminated under the provisions of this clause.
  - C. Except with respect to defaults of Subcontractors, the CONTRACTOR shall not be liable for any excess costs if the failure to perform the CONTRACT arises out of causes beyond the control and without the fault or negligence of the CONTRACTOR. Such causes may include, but are not restricted to, acts of God or of the public enemy, acts of the state or federal government in either their sovereign or contractual capacity, fires, floods, epidemics, quarantine restrictions, strikes, freight embargoes, and unusually severe weather; but in every case the failure to perform must be beyond the control and without the fault or negligence of the CONTRACTOR. If the failure to perform is caused by the default of a Subcontractor, and if such default arises out of causes beyond the control of both the CONTRACTOR and the Subcontractor, and without the fault or negligence of either of them, the CONTRACTOR shall not be liable for any excess costs for failure to perform unless the supplies or services to be furnished by the Subcontractor were obtainable from other sources in sufficient time to permit the CONTRACTOR to meet the required delivery or completion schedule.

If this CONTRACT is terminated as provided in Paragraph (A) of this clause, the OWNER, in addition to any other rights provided in this clause, may take over the WORK and prosecute the same to completion, by contract or otherwise, and may take possession of, and utilize in completing the WORK, such materials, equipment and plants as may be on the site of the WORK and necessary therefor. The OWNER may require the CONTRACTOR to transfer title and deliver to the OWNER, in the manner and to the extent directed

## General Conditions

by the OWNER:

- (1) Any completed portion of the WORK; and
- (2) Any partially completed portion of the WORK and any parts, tools, dies, jigs, fixtures, plans, drawings, information, and CONTRACT rights (hereinafter called "construction materials") as the CONTRACTOR has specifically produced or specifically acquired for the performance of such part of this CONTRACT as has been terminated; and the CONTRACTOR shall, upon direction of the OWNER, protect and preserve property in the possession of the CONTRACTOR in which the OWNER has an interest.

Payment for completed WORK accepted by the OWNER shall be at the contract price. Payment for construction materials delivered to and accepted by the OWNER and for the protection and preservation of property shall be in an amount agreed upon by the CONTRACTOR and OWNER. The OWNER may withhold from amounts otherwise due the CONTRACTOR for such completed WORK or construction materials such sum as the OWNER determines to be necessary to protect the OWNER against loss because of outstanding liens or claims of former lien holders.

- E. If, after notice of termination of the contract under the provisions of this clause, it is determined for any reason that the CONTRACTOR was not in default under the provisions of this clause, or that the default was excusable under the provisions of this clause, the rights and obligations of the parties shall, if the CONTRACT contains a clause providing for termination for convenience of the OWNER, be the same as if the notice of termination had been issued pursuant to such clause. If, after notice of termination of this CONTRACT under the provisions of this clause, it is determined for any reason that the CONTRACTOR was not in default under the provisions of the clause, and if this CONTRACT does not contain a clause providing for termination for convenience of the OWNER, the CONTRACT shall be equitably adjusted to compensate for such termination and the contract modified accordingly.
- F. The rights and remedies of the OWNER provided in this clause shall not be exclusive and are in addition to any other rights and remedies provided by law or under this CONTRACT.

### 23. Application for Payments:

The CONTRACTOR shall submit an application monthly for progress payments to the OWNER for approval. The CONTRACT REPRESENTATIVE shall approve the payment, and obtain the signature of the inspector for payment. Receipts or other vouchers showing payments for the materials and labor, including payments to Subcontractors, for the preceding month shall be submitted with the application if required.

If payments are made on valuation of WORK done, such application shall be submitted at least ten days before each payment falls due. The CONTRACTOR shall,

before the first application, submit to the OWNER, a schedule of values for the various parts of the WORK, including quantities, aggregating the total sum of the CONTRACT, divided so as to facilitate payments as outlined above and made out in such form as the OWNER and the CONTRACTOR may agree upon, and supported by such evidence as to its correctness as the OWNER may direct. This schedule, when approved by the OWNER, shall be used as a basis for payment, unless it be found to be in error. In applying for payments, the CONTRACTOR shall submit in duplicate a statement based upon this schedule and itemized in such form and supported by such evidence as the OWNER may direct, showing CONTRACTOR's right to the payment claimed.

In making payments to the CONTRACTOR for completed WORK or for materials stored on site, it is understood between the OWNER and the CONTRACTOR that proportionate parts of such payments as are made to the CONTRACTOR for completed WORK of Subcontractors and/or suppliers will be transmitted to such Subcontractors and/or suppliers in the form of payments for completed WORK within ten (10) days after receipt of such payments by the CONTRACTOR. The submittal of an application by a CONTRACTOR for a progress payment shall constitute prima facie representation by that CONTRACTOR that all previous proportionate payments made by the OWNER to the CONTRACTOR for completed WORK of Subcontractors and/or suppliers have been transmitted to all appropriate Subcontractors and/or suppliers for their completed WORK within ten (10) days after receipt of respective payments.

For projects in excess of \$100,000, the CONTRACTOR may request retainage to be paid to an escrow agent for interest to accrue to the CONTRACTOR's benefit. See OWNER for forms and more information.

### 24. OWNER's Right to Withhold Certain Amounts and Make Application Thereof:

The OWNER may withhold from payment to the CONTRACTOR such an amount or amounts as, in its judgment, may be necessary to pay just claims against the CONTRACTOR or any Subcontractor for labor and services rendered and materials furnished in and about the WORK. The OWNER may apply such withheld amounts on the payment of such claims in its discretion. In so doing, the OWNER shall be deemed the agent of the CONTRACTOR and payments so made by the OWNER shall be considered as a payment made under the CONTRACT by the OWNER to the CONTRACTOR and the OWNER shall not be liable to the CONTRACTOR for any such payments in good faith made. Such payments may be made without prior determination of the claim or claims.

Neither the final certificate of payment nor any provision in the CONTRACT documents, nor partial or entire occupancy of the premises by the OWNER shall constitute an acceptance of WORK not done in accordance with the contract documents or relieve the CONTRACTOR of liability in respect to any express warranties or responsibility for faulty materials or workmanship. The CONTRACTOR shall remedy any defects in the WORK and pay for any damage to other

WORK resulting therefrom, which shall appear within a period of one year from the date of the certificate of substantial completion of the WORK, unless a longer period is specified. The OWNER will give notice of observed defects with reasonable promptness.

**25. Liability Insurance:**

To protect against liability, loss, or expense arising from damage to property or injury or death of any person or persons incurred in any way out of, in connection with or resulting from the WORK provided hereunder, CONTRACTOR shall obtain at its own expense from reliable insurance companies acceptable to OWNER's Risk Manager and authorized to do business in the state in which the work is to be performed, and shall maintain in full force during the entire period of this contract the following or equivalent insurance:

- (a) Workers' Compensation Insurance and Employers' Liability Insurance providing statutory benefits.
- (b) Comprehensive General Liability Insurance, including premises-operations; explosion; collapse and underground hazards; products and completed operation hazards; blanket contractual; broad form property damage; independent CONTRACTORS; and personal injury including employees with limits not less than \$1,000,000 combined single limit per occurrence.
- (c) Comprehensive Automobile Liability Insurance including owned, hired and non-owned automobiles with limits not less than \$1,000,000 combined single limit per occurrence.
- (d) CONTRACTOR using its own aircraft, or employing aircraft in connection with the WORK performed under this contract shall maintain Bodily Injury and Property Damage Liability coverage with a combined single limit of not less than \$1,000,000 per occurrence.

Any policy required by this section may be arranged under a single policy for the full limit required, or by a combination of underlying policies with the balance provided by an Excess or Umbrella Liability policy.

OWNER may accept equivalent self-insured programs in lieu of insurance upon specific approval of OWNER's Risk Manager.

Irrespective of the requirements as to insurance to be carried by CONTRACTOR as provided herein, insolvency, bankruptcy or failure of any insurance company to pay all claims accruing, shall not be held to relieve CONTRACTOR of any obligations hereunder.

The State of Utah and all Institutions, Agencies, Departments, Authorities and Instrumentalities of the State of Utah, and while acting within the scope of their duties as such: any member of their governing bodies, or of their boards, commissions, or advisory committees, or any of their elected or appointed officials, or any of their employees or authorized volunteers shall be listed as additional insureds under each of the policies required to be purchased and maintained by

CONTRACTOR, with the exception of Workers' Compensation. Each policy so required shall be primary to the aforesaid additional insureds listed above, and shall apply to the full policy limits prior to any other insurance coverage which the aforesaid additional insureds may have in the event of claim under any of said policies, but, only with respect to WORK being performed by CONTRACTOR on behalf of the aforesaid additional insureds.

Before the WORK is commenced, certificates evidencing that satisfactory coverage of the type and limits set forth above are in effect, shall be furnished to the OWNER. Such insurance policies shall contain provisions that no alteration, cancellation or material change therein shall become effective except upon thirty (30) days prior written notice to OWNER's Risk Manager as evidenced by return of registered or certified letter sent to OWNER's Risk Manager.

Any and all deductibles in the above described policies shall be assumed by, for the account of, and at sole risk of CONTRACTOR.

**26. Property Insurance:**

OWNER shall provide "all risk" property insurance to protect OWNER, as well as all CONTRACTORS, Subcontractors and sub-subcontractors with respect to WORK performed hereunder at OWNER's own cost and expense, according to the policy forms currently in force with insurance carriers selected by OWNER's Risk Manager. OWNER's Risk Manager will furnish, upon request, all parties in interest with copies of said policies authenticated by authorized agents of the insurers or the State Risk Management Fund.

The above described policies shall be subject to a total deductible of \$500.00 per loss occurrence, which shall be assumed by all insureds in proportion to their share of the total amount of an insured loss occurrence.

Any insured property loss is to be adjusted with the OWNER's Risk Manager, and made payable to the OWNER's Risk Manager as trustee for the insureds, as their interests may appear, subject to the requirements of any applicable loss payable clause.

CONTRACTOR and OWNER hereby waive all rights against each other for damages caused by perils insured against under the property insurance provided by OWNER, except such rights as CONTRACTOR may have to the proceeds of such insurance held by the OWNER's Risk Manager as trustee.

If the CONTRACTOR requests in writing that insurance for special hazards be included in the property insurance policy, the OWNER's Risk Manager shall, if possible, include such insurance, and the cost thereof shall be charged to the CONTRACTOR by appropriate change order.

**27. Indemnification:**

"Indemnities" shall be defined for the purposes of this section: the State of Utah and all institutions, agencies, departments, authorities, and instrumentalities of the

## General Conditions

State of Utah, and any member of their governing bodies, or of their boards or commissions, or any of their elected or appointed officers, or any of their employees or authorized volunteers.

The CONTRACTOR will protect, indemnify and hold harmless indemnities from every kind and character of damages, losses, expenses, demands, claims and causes of action arising against indemnities and their Subcontractors, their officers, agents, employees or any other person, firm or corporation whatsoever from, against, or on account of any and all claims damages, losses, demands causes of action and expenses (including attorney's fees) arising out of or resulting from any violation or alleged violation by CONTRACTOR, his officers, agents and employees, or his Subcontractors or their officers, agents and employees of any federal, state or local law, statute or ordinance, relating to the WORK to be performed by the CONTRACTOR on the project growing out of or incident to the WORK to be performed and operations to be conducted by CONTRACTOR, or his Subcontractors, under this agreement, whether such claims, death or damages, result from or are claimed to have resulted from the negligence of CONTRACTOR, his officers, agents or employees, or his Subcontractors, their officers, agents, employees, or whether resulting from or alleged to have resulted from the concurrent negligence of indemnities and/or CONTRACTORS, their officers, agents or employees. The CONTRACTOR, at his own expense, shall defend any suit or action brought against OWNER based on any such alleged injury, death or damage, and shall pay all damages, costs and expenses, including attorney's fees in connection therewith or in any manner resulting therefrom. Such damages will include all the injuries or damages occasioned by the failure of, use of, or misuse of any and all kinds of equipment, whether owned or rented by CONTRACTOR or furnished by a Subcontractor.

The OWNER shall be fully informed by the CONTRACTOR of settlement negotiations regarding any matter referred to in the preceding paragraph and shall first approve any settlement to be made by CONTRACTOR. Any such settlement shall include a release of all claims relating to OWNER. The form copy of all releases obtained shall be furnished by OWNER. If CONTRACTOR is unable to make settlement of any such claims within fifteen (15) days after the final completion date, the OWNER reserves the right, at his/her option, to either make settlement of the claim and charge the amount to CONTRACTOR or to withhold the dollar amount, in whole or in part, of the claim or claims in question from payment to CONTRACTOR until OWNER receives a release for such claim or claims.

In any and all claims against indemnities by any employee or CONTRACTOR, any Subcontractor, anyone directly or indirectly employed by any of them or anyone for whose acts any of them may be liable, the indemnification obligation under this article shall not be limited in any way by any limitation on the amount or type of damages, compensation or benefits payable by or for CONTRACTOR or any Subcontractor under workers' compensation acts, disability benefit acts or other employee benefit acts.

The CONTRACTOR shall indemnify and hold harmless indemnities from all claims, demands, causes of action or suits of whatever nature arising out of services, equipment, supplies, materials and/or labor furnished by CONTRACTOR or its Subcontractors under this agreement; from all labor and/or mechanic or materialmen liens upon the real property upon which the work is located arising in favor of laborers and/or materialmen, Subcontractors and suppliers, out of services, equipment, supplies, materials and/or labor furnished by CONTRACTOR or any of his/her Subcontractors from all liens, claims and encumbrances arising from the performance of CONTRACTOR or his/her Subcontractors.

### 28. Guarantee Bonds:

The CONTRACTOR shall include in his/her bid, as part of the quoted total, all costs involved in securing and furnishing the following bonds based on the completed cost of the CONTRACT:

- (a) A full 100% performance bond covering the faithful execution of the CONTRACT; and
- (b) A full 100% payment bond of all obligations arising thereunder.

### 29. Liens:

Neither the final payment nor any part of the retained percentage shall become due until the CONTRACTOR, if required, shall deliver to the OWNER a complete release of all liens arising out of this CONTRACT, or receipts in full in lieu thereof, and, if required in either case, an affidavit that so far as CONTRACTOR has knowledge or information the releases and receipts include all the labor and materials for which a lien could be filed, but the CONTRACTOR may, if any Subcontractor refuses to furnish a release or receipt in full, furnish a bond satisfactory to the OWNER to indemnify him/her against any lien. If any lien remain unsatisfied after all payments are made, the CONTRACTOR shall refund to the OWNER all moneys that the latter may be compelled to pay in discharging such a lien, including all costs and a reasonable attorney's fee.

### 30. Assignment:

The CONTRACTOR shall not assign the CONTRACT or sublet it as a whole without the written consent of the OWNER, nor shall the CONTRACTOR assign any moneys due or to become due to CONTRACTOR hereunder, without the previous written consent of the OWNER.

### 31. Mutual Responsibility of Contractors:

Should the CONTRACTOR cause damage to any separate CONTRACTOR on the WORK, the CONTRACTOR agrees, upon due notice, to settle with such CONTRACTOR by agreement or arbitration, if he/she will so settle. If such separate CONTRACTOR sues the OWNER on account of any damage alleged to have been so sustained, the OWNER shall notify the CONTRACTOR, who shall defend such proceedings at his/her own expense, and if any judgment against the

OWNER arises therefrom, the CONTRACTOR shall pay or satisfy it in its entirety.

**32. Separate Contracts:**

The OWNER reserves the right to let other CONTRACTS in connection with this WORK. The CONTRACTOR shall afford other CONTRACTORS reasonable opportunity for the introduction and storage of their materials and the execution of their work and shall properly connect and coordinate his/her WORK with theirs.

If any part of the CONTRACTOR's WORK depends for proper execution or results upon the WORK of any other CONTRACTOR, the CONTRACTOR shall inspect and promptly report to the OWNER any defects in such WORK that render it unsuitable for such proper execution and results. His/her failure so to inspect and report shall constitute an acceptance of the other CONTRACTOR's work as fit and proper for the reception of his/her work, except as to defects which may develop in the other CONTRACTOR's WORK after the execution of his/her WORK. To insure the proper execution of his/her subsequent WORK, the CONTRACTOR shall measure WORK already in place and shall at once report to the OWNER any discrepancy between the executed WORK and the drawings.

**33. Subcontractors:**

The two apparent low bidders shall furnish to the OWNER, within twenty-four (24) hours after the opening of bids, a list of the Subcontractors by name and amounts where Subcontractors' bids are in excess of \$5,000 and shall not employ any that the OWNER may, within a reasonable time, object to as incompetent or unfit. Bidders shall not list themselves or "self" under any category as Subcontractor unless the bidder intends to perform as the Subcontractor for which he/she lists "self," and unless he/she generally and regularly performs that type of subcontract WORK. The OWNER shall, on request, furnish to any Subcontractor, wherever practicable, evidence of the amounts certified on this account.

The CONTRACTOR agrees that CONTRACTOR is as fully responsible to the OWNER for the acts and omissions of his Subcontractors and of persons either directly or indirectly employed by them, as he/she is for the acts and omissions of persons directly employed by CONTRACTOR.

Nothing contained in the CONTRACT documents shall create any contractual relation between any Subcontractor or supplier and the OWNER.

**34. Relations of CONTRACTOR and Subcontractor:**

The CONTRACTOR agrees to bind every Subcontractor and every Subcontractor agrees to be bound by the terms of the agreement, the general conditions, and the drawings and specifications as far as applicable to his/her WORK. Nothing in this article shall create any obligation on the part of the OWNER to pay or to see to the payment of any sums to any Subcontractor.

**35. State's Inspection:**

The OWNER, at his/her option, may assign a inspector to the project. Such staff inspector will cooperate with the CONTRACT REPRESENTATIVE and design engineer in noting deviations from, or necessary adjustments to, the CONTRACT documents or of deficiencies or defects in the construction. The staff inspector's presence on the project, however, shall in no way relieve the CONTRACT REPRESENTATIVE of the prime responsibilities as set forth herein.

**36. CONTRACT REPRESENTATIVE Status:**

The OWNER shall appoint a CONTRACT REPRESENTATIVE who shall have general supervision of the work and he/she is the agent of the OWNER to the extent provided in the CONTRACT documents and when in special instances he/she is authorized by the OWNER to so act.

As the CONTRACT REPRESENTATIVE is, in the first instance, an interpreter of the conditions of the CONTRACT and a judge of its performance, he/she shall side neither with the OWNER nor with the CONTRACTOR, but shall use his/her powers under the CONTRACT to enforce its faithful performance by both.

**37. CONTRACT REPRESENTATIVE's Decisions:**

The CONTRACT REPRESENTATIVE shall, within a reasonable time, make decisions on all claims of the OWNER or CONTRACTOR and on all other matters relating to the execution and progress of the WORK or the interpretation of the CONTRACT documents.

**38. Cash Allowances:**

The CONTRACTOR shall include in the BID PRICE all allowances named in the CONTRACT documents and shall cause the WORK so covered to be done by such CONTRACTORS and for such sums as the CONTRACT REPRESENTATIVE may specify and certify, the BID PRICE being adjusted in conformity therewith, upon approval of the OWNER.

**39. Use of Premises:**

The CONTRACTOR shall confine apparatus, the storage of materials and the operations of his/her workers to limits indicated by law, ordinances, permit or directions of the CONTRACT REPRESENTATIVE and shall not unreasonably encumber the premises with his/her materials. The CONTRACTOR shall not load or permit any part of the equipment or structure to be loaded with a weight that will endanger its safety or the safety of any person on the premises.

**40. Cutting, Patching and Digging:**

The CONTRACTOR shall do all cutting, patching or fitting of his/her WORK that may be required to make its several parts come together properly and fit it to receive or be received by WORK of other CONTRACTORS shown upon, or reasonably implied by, the drawings and specifications for the completed structure, and he shall make good after them as the CONTRACT

## General Conditions

REPRESENTATIVE may direct.

Any cost caused by defective or ill-timed work shall be borne by the party responsible therefor. The CONTRACTOR shall not endanger any WORK by cutting, digging or otherwise, and shall not cut or alter the WORK of any other CONTRACTOR save with the consent of the CONTRACT REPRESENTATIVE.

### 41. Cleaning Up:

The CONTRACTOR shall at all times keep the premises free from accumulations of waste material or rubbish caused by his/her employees or WORK. At the completion of the WORK, CONTRACTOR shall remove all rubbish from and about the building and all tools, scaffolding and surplus materials and shall leave his/her WORK "broom-clean" or its equivalent, unless more exactly specified. In case of dispute, the OWNER may remove the rubbish and charge the cost to the several CONTRACTORS as the CONTRACT REPRESENTATIVE may determine to be just.

### 42. Substitutions:

Where reference is made to one or more propriety products but restrictive descriptive material of one or more manufacturer(s) is used, it is understood that the products of other manufacturers will be accepted, provided they equal or exceed the standards set forth in the plans and specifications and are compatible with the intent and purpose of the design, subject to the written approval of the OWNER and the CONTRACT REPRESENTATIVE prior to the opening of bids. Requests for and information pertaining to said approval must be submitted to the OWNER no later than four (4) working days (not including Saturday, Sunday or state holidays) prior to bid opening. If the descriptive material is not restrictive, the products of other manufacturers specified will be accepted without prior approval provided they are compatible with the intent and purpose of the design.

The CONTRACTOR may propose the substitution of any material as a supplement to his/her bid with the monetary amount, additive or deductive as may be the case, clearly stated and shall include the manufacturer's complete descriptive information with the proposed substitution. This shall be completely apart and separate from the BID PRICE quotation and shall be solely for the information of the OWNER and the use of such proposed substitutions shall be strictly at the decision of the OWNER. If substitution is accepted by the OWNER, the CONTRACT sum shall be adjusted from the BID PRICE either up or down as indicated on the supplementary list by change order after award.

### 43. Laying Out WORK:

The CONTRACTOR shall be held strictly responsible for the accuracy of the laying out of his/her WORK and for its strict conformity with the existing conditions of the building and shall determine all changes and chases and openings before WORK is commenced.

### 44. Emergencies:

In an emergency affecting the safety of life, or of the

structure or of adjoining property, then the CONTRACTOR, without special instruction or authorization from the OWNER, shall act at his/her discretion to prevent such threatened loss or injury. Any compensation claimed to be due him/her therefrom shall be determined as provided for under Article 17, "Changes."

### 45. Testing of Materials:

In case the CONTRACT REPRESENTATIVE direct that any materials be tested or analyzed, then the CONTRACTOR shall furnish a sample for the test, such sample being selected according to the directions of the CONTRACT REPRESENTATIVE. The cost of testing or analysis of such sample or samples shall be borne by the manufacturer or supplier of the product. This provision shall not apply to the testing of concrete. The cost of testing shall be borne by the OWNER.

### 46. Temporary Enclosing, Drying Out, Etc.:

If applicable when openings are made in exterior walls, the CONTRACTOR shall, if required by the OWNER on account of weather or security conditions, close up all exterior openings (except one or more which are to be provided with battened doors, padlocks, etc.) with temporary frames covered with approved material.

The CONTRACTOR must, at all times, protect the building from damage from weather, surface water or subsoil drainage. He/she must keep the excavations dry, if necessary, by pumping, while concrete or masonry is being laid.

### 47. Examination of Site:

The CONTRACTOR shall visit the site and examine for himself/herself the site conditions. He/she shall furnish all labor and materials necessary for preparation of the site for the execution of this CONTRACT.

### 48. Storage and Care of Materials:

The CONTRACTOR shall provide, maintain and remove when directed, suitable, substantial, watertight storage sheds upon the premises where directed, in which he/her shall store his/her materials. All cement, lime and other materials affected by moisture shall be covered and protected to keep from damage while it is being transported to the site.

### 49. Construction Risks:

The construction and all materials and WORK connected therewith shall be at the CONTRACTOR's risk until they are accepted, and he/she will be held responsible for and liable for their safety in the amount paid to him/her by the OWNER on account thereof.

### 50. Temporary Appurtenances and Conveniences:

The CONTRACTOR shall provide well-fastened ladders and other means to facilitate inspection of the work.

### 51. Scaffolding, Tools, Etc.:

The CONTRACTOR shall provide and erect all the

necessary platforms, scaffolds and supports of ample strength required for the handling of the materials and other loading to be imposed. The same shall apply to all derricks and hoisting machinery, all appliances and materials, ladders, horses, poles, plants, ropes, wedges, centers, moulds, and other tools and materials, and the cartage thereof to and from the site as may become necessary for the performance of his/her contract.

**52. Sanitary Provisions:**

The CONTRACTOR shall provide a chemical toilet for his workers' use. The CONTRACTOR shall keep the toilet clean, neat and in first-class condition at all times.

**53. Refuse:**

Refuse barrels are to be provided by the CONTRACTOR for the workers' lunch boxes and papers.

**54. Removing Water:**

The CONTRACTOR shall remove, at his/her expense from all excavations and/or from the site, all unwanted water appearing from any cause during any stage of the WORK until the site is accepted by the OWNER. All excavations shall be free from water before any concreting or other WORK is done in them.

**55. Taxes:**

The CONTRACTOR shall include in his/her BID PRICE the cost of social security, unemployment compensation, and sales and use taxes as required by federal and state laws.

**56. Citizens Preferred:**

Preference shall be given in hiring citizens of the United States or those having declared their intention of becoming citizens; failure to comply may result in the OWNER declaring the contract void.

**57. Code Requirements:**

The provisions of the 1979 Uniform Building Code, and the 1980 Supplement to Uniform Building Code and Uniform Building Code Standards, the 1981 National Electrical Code, except as specific variances therewith may be authorized by the OWNER, and the 1979 Utah Plumbing Code as amended, shall apply.

If the drawings and specifications fail to meet the minimum standards of the above-mentioned codes, it shall be the responsibility of the CONTRACTOR to bring such information to the attention of the OWNER having jurisdiction. Subcontractors shall also inform the CONTRACTOR of any infractions of the above-mentioned codes regarding their own particular trades.

In the event that workmanship or incidental materials are not specified or indicated, they shall at least conform to the above-mentioned codes and shall be incorporated

into the work without any additional cost to the OWNER. If the plans and specifications call for items or workmanship which exceed the codes, the plans and specifications hold precedence over any code requirements.

**58. Nondiscrimination - Equal Employment Opportunity:**

In order to comply with the provisions of the Utah Anti-Discrimination Act of 1965, relating to unfair employment practices, the CONTRACTOR agrees as follows:

- A. The CONTRACTOR will not discriminate against any employee or applicant for employment because of race, color, sex, religion ancestry or natural origin.
- B. In all solicitations or advertisements for employees, the CONTRACTOR will state that all qualified applicants will receive consideration without regard to race, color, sex, religion, ancestry or national origin.
- C. The CONTRACTOR will send to each labor union or workers' representative notices to be provided, stating the CONTRACTOR's responsibilities under the statute.
- D. The CONTRACTOR will furnish such information and reports as requested by the division for the purpose of determining compliance with the statute.
- E. Failure of the CONTRACTOR to comply with the statute, the rules and regulations promulgated thereunder and this nondiscrimination clause shall be deemed a breach of contract and it may be canceled, terminated or suspended in whole or in part.
- F. The CONTRACTOR shall include the provisions of the above Paragraphs A through E in all subcontracts for this project.

**59. Affirmative Action:**

The CONTRACTOR will take affirmative action to ensure that applicants are employed and that employees are treated during employment without regard to their race, color, religion, sex or national origin. Such action shall include, but not be limited to the following: employment; upgrading; demotion or transfer; recruitment or recruitment advertising; layoff or termination; rates of pay or other forms of compensation; and selection for training, including apprenticeship.

At its discretion, the OWNER may perform a compliance review at the office and project of the CONTRACTOR to check on compliance in hiring practices, record-keeping, contracting of agencies and unions, advertising, informing of personnel of the requirements under this provision, etc. If the visit to the project site or other information received indicates need to perform a compliance review more frequently on a project, this will be done. The size of the project, complaint situation, and past record of CONTRACTOR will determine the

## General Conditions

frequency of on-the-job compliance reviews.

### 60. Safety:

The CONTRACTOR shall institute a safety program at the start of construction to minimize accidents; such program to continue to the end of the job and conform to the latest general safety orders of the State Industrial Commission. The CONTRACTOR shall post signs, erect barriers, etc., as necessary to implement this program. The CONTRACTOR shall have all workers and all visitors on site wear safety hard hats and obey all safety rules and regulations and statutes as soon as the CONTRACTOR proceeds. The CONTRACTOR shall post a sign regarding hats in a conspicuous location and furnish extra hats at his/her expense for visitors.

### 61. Rubbish Disposal:

Rubbish, trash, etc., shall not be burned on premises unless approved by the local fire authority, but rather, hauled from the site and legally disposed of or other methods as specified by OWNER.

### 62. Subcontractors Financial Bid Limits and License Classification:

The CONTRACTOR shall verify the license classification and bid limit of each of his/her Subcontractors. Regulations prohibit work of the above Subcontractors exceeding their respective bid limit and working outside of license classification as determined by the Department of Business Regulation, Department of Contractors.

In the event the bid limit or classification is not complied with, the respective Subcontractor(s) mentioned above will be disqualified by the OWNER, and the CONTRACTOR shall be responsible to provide a suitable and properly qualified Subcontractor as approved by the OWNER without a change in the contract price.

### 63. Balancing and Testing:

It is the intent of this specification that the site, when presented to the OWNER for final acceptance, be complete and operable in all respects, including, but not limited to, mechanical, utilities, and other systems which are tuned, tested, and balanced to the satisfaction of the OWNER, or his/her appropriate engineers and consultants. Any and all testing and balancing necessary shall be done as part of the CONTRACT with the state.

During, or in connection with the inspection of the WORK, the CONTRACTOR or his/her appropriate Subcontractor(s) shall perform such tests and/or demonstrations of the operation of the systems, or its components, as may be requested by the OWNER, or his/her appropriate engineers and consultants, as necessary to adequately determine the acceptability of the installation.

### 64. Substantial Completion:

The OWNER will conduct inspections to determine the

dates of substantial completion and final payment, will receive written guarantees and related documents required by the CONTRACT and assembled by the CONTRACTOR and submit these to the OWNER, and will issue a final certificate for payment.

The date of substantial completion of the WORK or designated portion thereof is the date certified by the OWNER when construction is sufficiently complete in accordance with the CONTRACT documents so the OWNER may occupy the site or designated portion thereof for the use for which it is intended. When the CONTRACTOR determines that the WORK, or a designated portion thereof acceptable to the OWNER, is substantially complete, the OWNER shall prepare a list of items to be completed or corrected. The failure to include any item on such list does not alter the responsibility of the CONTRACTOR to complete all WORK in accordance with the contract documents. When the OWNER, on the basis of an inspection, determines that this WORK is substantially complete, the CONTRACT REPRESENTATIVE then will prepare a Certificate of Substantial Completion which shall establish the date of substantial completion; shall state the responsibilities of the OWNER and the CONTRACTOR for maintenance, heat, utilities and insurance; and shall fix the time within which the CONTRACTOR shall complete the items listed therein, said time to be within the CONTRACT time unless extended pursuant to Article, "Delays and Extension of Time." The certificate of substantial completion shall be submitted to the OWNER and the CONTRACTOR for their written acceptance of the responsibilities assigned to them in such certificate. A sample form of the certificate of substantial completion is included in the specifications.

If within one year after the date of substantial completion or within such longer period of time as may be prescribed by law or by the terms of any applicable special guarantee required by the CONTRACT documents, any of the WORK is found to be defective or not in accordance with the CONTRACT documents, the CONTRACTOR shall correct it promptly after receipt of written notice from the OWNER to do so unless the OWNER has previously given the CONTRACTOR a written acceptance of such condition. The OWNER shall give such notice promptly after discovery of the condition.

### 65. Other Prohibited Interests:

No official of the OWNER who is authorized in such capacity and on behalf of the OWNER to negotiate, make, accept or approve, or to take part in negotiating, making, accepting, or approving any architectural engineering, inspection, construction or material supply contract or any subcontract in connection with the construction of the project, shall become directly interested personally in the contract or in any part hereof.

No officer, employee, attorney, engineer or inspector of or for the OWNER who is authorized in such capacity and on behalf of the OWNER to exercise any legislative, executive, supervisory or other similar functions in connection with the construction of the project shall become directly or indirectly interested personally in this



contract or in any part thereof, any material supply contract, subcontract, insurance contract, or any other contract pertaining to the project.

**66. Conflicting Conditions:**

Any provision in any of the CONTRACT documents which may be in conflict or inconsistent with any of the paragraphs in these general conditions shall be void to the extent of such conflict or inconsistency. In the event of conflicts of plans and specifications, the CONTRACTOR shall follow the most stringent requirements as approved by the OWNER.

**67. Monthly Progress Meetings:**

Monthly progress meetings may be held at the discretion of the OWNER or the general CONTRACTOR, at which time the Subcontractors and/or suppliers will be required to be present.

**68. Suspension of WORK:**

A. Suspension of WORK for the Convenience of the Owner. The OWNER may order the CONTRACTOR in writing to suspend, delay or interrupt all or any part of the WORK for such period of time as the OWNER may determine to be appropriate for the convenience of the OWNER.

B. Adjustment of Cost. If the performance of all or any part of the work is suspended, delayed or interrupted by an act or failure to act of the OWNER for an unreasonable period of time, an equitable adjustment in the CONTRACT price shall be made for any increase in the cost of performance of this CONTRACT necessarily caused by such unreasonable suspension, delay or interruption and an equitable adjustment of time for completion of the WORK will be allowed the CONTRACTOR and the CONTRACT shall be modified in writing accordingly. However, no adjustment shall be made under this clause for any suspension, delay or interruption to the extent:

- (1) That performance would have been so suspended, delayed or interrupted by any other cause, including the fault or negligence of the CONTRACTOR; or
- (2) For which an adjustment is provided or excluded under any other provision of this CONTRACT.

C. Time Period for Claims. Any claim by the CONTRACTOR for adjustment under this clause must be asserted by the CONTRACTOR, in writing, within thirty (30) days from the date of termination of such suspension, delay or interruption; provided that the OWNER may, in his/her sole discretion, receive and act upon any such claim asserted at any time prior to final payment under this CONTRACT.

D. Adjustments of Price. Any adjustment in contract price made pursuant to this clause shall be determined in accordance with the price adjustment clause of this CONTRACT.

**69. Differing Site Conditions:**

A. Notice. The CONTRACTOR shall promptly, and before such conditions are disturbed, notify the OWNER, in writing, concerning any:

- (1) Subsurface or latent physical conditions at the site differing materially from those indicated in this CONTRACT; or
- (2) Unknown physical conditions at the site of an unusual nature, differing materially from those ordinarily encountered and generally recognized as inherent in WORK of the character provided for in this CONTRACT.

B. Adjustments of Price or Time for Performance. After receipt of such notice, the OWNER shall promptly investigate the site, and if it is found that such conditions do materially so differ and cause an increase in the CONTRACTOR's cost of, or the time required for, performance of any part of the WORK under this contract, whether or not changed as a result of such conditions, an equitable adjustment shall be made and the CONTRACT modified in writing accordingly. Any adjustment in CONTRACT price made pursuant to this clause shall be determined in accordance with the Price Adjustment Clause of this CONTRACT.

C. Time Period for Notice of Claims. Any claim by the CONTRACTOR for an adjustment under this clause must be asserted by the CONTRACTOR, in writing, within thirty (30) days from the date of the CONTRACTOR's notice to the OWNER concerning the differing site conditions; provided that the OWNER may, in his/her sole discretion, receive and act upon any such claim asserted at any time prior to issuance of notice of substantial completion.

D. No claim shall be allowed unless the CONTRACTOR has given the notice required in Subparagraph (A) of this clause; provided that the time prescribed therefor may be extended by the OWNER.

E. Knowledge. Nothing contained in this clause shall be grounds for an adjustment in compensation if the CONTRACTOR had actual knowledge of the existence of such conditions prior to the submission of bids.

**70. Price Adjustment:**

A. Price Adjustment Methods. Any adjustment in BID PRICE pursuant to any clause in this CONTRACT shall be made in one or more of the following ways:

- (1) By agreement on a fixed-price adjustment before commencement of the pertinent performance;
- (2) By unit prices specified in this CONTRACT;
- (3) By the costs attributable to the applicable events or situations, plus appropriate profit or

## General Conditions

fee, in the following manner:

- (a) The CONTRACTOR shall furnish to the OWNER a detailed estimate of the actual cost of labor, materials, taxes and equipment required for the performance of such WORK. Equipment rental rates shall not exceed those of comparable rates charged by rental companies or as agreed to by the OWNER and CONTRACTOR prior to start of the project.
  - (b) For added or omitted work by a Subcontractor (not including unit price) the CONTRACTOR shall furnish to the OWNER a detailed estimate of the actual cost of the Subcontractors for labor, materials, taxes and equipment to be used for such WORK. Each such estimate shall be signed by the Subcontractor as his/her estimate of the costs thereto.
  - (c) The CONTRACTOR and Subcontractor agree that a fixed fee not exceeding 15% of the increased costs shall be full compensation to cover all costs of supervision, overhead, bond, and any other direct or indirect overhead expenses and profit.
  - (4) In such manner as the parties may mutually agree; or
  - (5) In the absence of agreement between the parties, by a unilateral determination by the OWNER of the costs attributable to the applicable event or situation, plus appropriate profit or fee, all as computed by the OWNER, subject to the CONTRACTOR's legal and contractual remedies.
- B. Submission of Cost or Pricing Data.** The CONTRACTOR shall submit certified cost or pricing data for any price adjustments, except where they are based upon established catalog prices or market prices, or upon adequate price competition or are set by law or regulation. Any price adjustments allowable hereunder shall exclude sums found by the OWNER to have resulted from any cost or pricing data furnished by the CONTRACTOR which were inaccurate, incomplete or not current as of the date of their submission to the OWNER.
- 71. Termination for Convenience of the Owner:**
- A. The performance of WORK under this contract may be terminated by the OWNER in accordance with this clause in whole, or from time to time, in part, whenever the OWNER shall determine that such termination is in the best interest of the OWNER or any person for whom the OWNER is acting under this CONTRACT. Any such termination shall be effected by delivery to the CONTRACTOR of a notice of termination specifying the extent to which performance of WORK under the contract is terminated, and the date upon which such termination becomes effective.
- No termination may be effected unless the CONTRACTOR is given (1) not less than ten calendar days written notice (delivered by certified mail, return receipt requested), and (2) an opportunity for consultation with the OWNER prior to termination.
- B. After receipt of a notice of termination, and except as otherwise directed by the OWNER, the CONTRACTOR shall:**
- (1) Stop WORK under the CONTRACT on the date and to the extent specified in the notice of termination;
  - (2) Place no further orders or subcontracts for materials, services or facilities, except as may be necessary for completion of such portion of the WORK under the CONTRACT as is not terminated;
  - (3) Terminate all orders and subcontracts to the extent that they relate to performance of WORK terminated by the notice of termination;
  - (4) Assign to the OWNER in the manner, at the times, and to the extent directed by the OWNER, all of the right, title, and interest of the CONTRACTOR under the orders and subcontracts so terminated, in which case the OWNER shall have the right, in his/her discretion, to settle or pay any or all claims arising out of the termination of such orders and subcontracts;
  - (5) Settle all outstanding liabilities and all claims arising out of such termination of orders and subcontracts, with the approval or ratification of the OWNER, which approval or ratification shall be final for all the purposes of this clause:
  - (6) Transfer title and deliver to the OWNER in the manner, at the times, and to the extent, if any, directed by the OWNER:
    - (a) The fabricated or unfabricated parts, WORK in process, completed WORK, supplies, and other material produced as a part of, or acquired in connection with the performance of the WORK terminated by the notice of termination; and
    - (b) The completed or partially completed plans, drawings, information, and other property which, if the CONTRACT had been completed, would have been required to be furnished to the OWNER;
  - (7) Use his/her best efforts to sell, in the manner, at the times, to the extent, and at the price or prices directed or authorized by the OWNER, any property of the types referred to in (6) above; provided, however, that the CONTRACTOR:
    - (a) Shall not be required to extend credit to any purchaser; and

## General Conditions

- (b) May acquire any such property under the conditions prescribed by and at a price or prices approved by the OWNER; and provided further that the proceeds of any such transfer of disposition shall be applied in reduction of any payments to be made by the OWNER to the CONTRACTOR under this CONTRACT or shall otherwise be credited to the price or cost of the work covered by this CONTRACT or paid in such other manner as the OWNER may direct;
  - (8) Complete performance of such part of the WORK as shall not have been terminated by the notice of termination; and
  - (9) Take such action as may be necessary, or as the OWNER may direct, for the protection and preservation of the property related to this contract which is in the possession of the CONTRACTOR in which the OWNER has or may acquire an interest.
- C. After receipt of a notice of termination, the CONTRACTOR shall submit to the OWNER his/her termination claim, in the form and with certification prescribed by the OWNER. Such claim shall be submitted promptly but in no event not later than sixty (60) days from the effective date of termination, unless one or more extensions in writing are granted by the OWNER, upon request of the CONTRACTOR made in writing within such period or authorized extension thereof. However, if the OWNER determines that the facts justify such action, he/she may receive and act upon any such termination claim at any time after such sixty (60) day period or any extension thereof. Upon failure of the CONTRACTOR to submit his/her termination claim within the time allowed, the OWNER may determine, on the basis of information available to him/her, the amount, if any, due to the CONTRACTOR by reason of the termination and shall thereupon pay to the CONTRACTOR the amount so determined.
- D. Subject to the provisions of Paragraph (C), the CONTRACTOR and the OWNER may agree upon the whole or any part of the amount or amounts to be paid to the CONTRACTOR by reason of the total or partial termination of WORK pursuant to this clause, which amount or amounts may include a reasonable allowance for profit on WORK done; provided that such agreed amount or amounts, exclusive of settlement costs, shall not exceed the total contract price as reduced by the amount of payments otherwise made and as further reduced by the CONTRACT price of work not terminated. The CONTRACT shall be amended accordingly, and the CONTRACTOR shall be paid the agreed amount. Nothing in Paragraph (E) of this clause, prescribing the amount to be paid to the CONTRACTOR in the event of failure of the CONTRACTOR and the OWNER to agree upon the whole amount to be paid to the CONTRACTOR by reason of the termination of work pursuant to this clause, shall be deemed to limit, restrict, or otherwise determine or affect the amount or amounts which may be agreed upon to be paid to the CONTRACTOR pursuant to this Paragraph (D).
- E. In the event of the failure of the CONTRACTOR and the OWNER to agree, as provided in Paragraph (D), upon the whole amount to be paid to the CONTRACTOR by reason of the termination of WORK pursuant to this clause, the OWNER shall pay to the CONTRACTOR the amounts determined by the OWNER as follows, but without duplication of any amounts agreed upon in accordance with Paragraph (D):
- (1) With respect to all CONTRACT WORK performed prior to effective date of the notice of termination, the total (without duplication of any items) of:
    - (a) The cost of such WORK;
    - (b) The cost of settling and paying claims arising out of the termination of WORK under subcontracts or orders as provided in Paragraph (B)(5) above, exclusive of the amounts paid or payable on account of supplies or materials delivered or services furnished by the Subcontractor prior to the effective date of the notice of termination under this CONTRACT, which amounts shall be included in the cost on account of which payment is made under (a) above; and
    - (c) A sum, as profit on (a) above, determined by the OWNER to be fair and reasonable; provided, however, that if it appears that the CONTRACTOR would have sustained a loss on the entire CONTRACT had it been completed, no profit shall be included or allowed under this subdivision (c) and an appropriate adjustment shall be made reducing the amount of the settlement to reflect the indicated rate of loss; and
  - (2) The reasonable cost of the preservation and protection of property incurred pursuant to Paragraph (B)(9); and any other reasonable cost incidental to termination of WORK under this CONTRACT, including expense incidental to the determination of the amount due to the CONTRACTOR as the result of the termination of WORK under this CONTRACT.
- The total sum to be paid to the CONTRACTOR under (E)(1) above shall not exceed the total CONTRACT price as reduced by the amount of payments otherwise made and as further reduced by the CONTRACT price of WORK not terminated. Except for normal spoilage, and except to the extent that the OWNER shall have otherwise expressly assumed the risk of loss, there shall be excluded from the amounts payable to the CONTRACTOR under (E)(1) above, the fair value, as determined by the OWNER of property which is destroyed, lost, stolen, or damaged so as to become

## General Conditions

- undeliverable to the OWNER, or to a buyer pursuant to Paragraph (B)(7).
- F. In arriving at the amount due the CONTRACTOR under this clause, there shall be deducted:
- (1) All unliquidated advance or other payments on account theretofore made to the CONTRACTOR, applicable to the terminated portion of this CONTRACT;
  - (2) Any claim which the OWNER may have against the CONTRACTOR in connection with this CONTRACT; and
  - (3) The agreed price for, or the proceeds of sale of, any materials, supplies, or other things acquired by the CONTRACTOR or sold, pursuant to the provisions of this clause, and not otherwise recovered by or credited to the OWNER.
- G. If the termination hereunder be partial, the CONTRACTOR may file with the OWNER a claim for an equitable adjustment of the price or prices specified in the CONTRACT relating to the continued portion of the CONTRACT (the portion not terminated by the notice of termination), and such equitable adjustment as may be agreed upon shall be made in such price or prices. Any claim by the CONTRACTOR for an equitable adjustment under this clause must be asserted within sixty (60) days from the effective date of the notice of termination, unless an extension is granted in writing by the OWNER.
- H. The OWNER may, from time to time, under such terms and conditions as he may prescribe, make partial payments and payments on account against costs incurred by the CONTRACTOR in connection with the terminated portion of this CONTRACT whenever, in the opinion of the OWNER the aggregate of such payments shall be within the amount to which the CONTRACTOR will be entitled hereunder. If the total of such payments is in excess of the amount finally agreed or determined to be due under this clause, such excess shall be payable by the CONTRACTOR to the OWNER upon demand, together with interest at a rate equal to the average rate at the time being received from the investment of state funds, as determined by the State Treasurer, for the period from the date such excess is repaid to the OWNER; provided, however, that no interest shall be charged with respect to any such excess payment attributable to a reduction in the CONTRACTOR's claim by reason of retention or other disposition of termination inventory until ten (10) days after the date of such retention or disposition, or such later date as determined by the OWNER by reason of the circumstances.
- I. Unless otherwise provided in this contract, or by applicable statute, the CONTRACTOR shall - from the effective date of termination until the expiration of three years after final settlement under this CONTRACT - preserve and make available to the OWNER at all reasonable times at the office of the CONTRACTOR, but without direct charge to the OWNER, all books, records, documents and other

evidence bearing on the costs and expenses of the CONTRACTOR under this CONTRACT and relating to the work terminated hereunder, or, to the extent approved by the contracting officer, photographs, micrographs, or other authentic reproductions thereof.

### 72. Liquidated Damages:

The CONTRACTOR is referred to Attachment C, Article 12 of the contract for conditions of liquidated damages.

### 73. Termination for Breach, Etc.:

If the CONTRACTOR shall be adjudged bankrupt, or if CONTRACTOR should make a general assignment for the benefit of his/her creditors, or if a receiver should be appointed on account of CONTRACTOR's insolvency, or if CONTRACTOR or any of his/her Subcontractors should violate any of the provisions of this CONTRACT, the OWNER may serve written notice upon CONTRACTOR of its intention to terminate said CONTRACT; and unless within ten (10) days after the serving of such notice, such violation shall cease, the OWNER then may take over the WORK and prosecute same to completion by CONTRACT or by any other method it may deem advisable for the amount and at the expense of the CONTRACTOR. The CONTRACTOR shall be liable to the OWNER for any excess cost occasioned the OWNER thereby and in such event, the OWNER may, without liability for so doing, take possession of and utilize in completing the WORK, such materials, appliances, paint, and any other property belonging to the CONTRACTOR as may be on the site of the work and necessary therefor.

### 74. Normal Daylight Hours:

Contractor shall perform WORK on the premises during normal daylight hours and shall not perform WORK on the site when artificial light would be required to safely perform the WORK.

### 75. Normal Working Days:

CONTRACTOR shall perform the WORK during normal working days and shall not work during Sundays, or recognized national and state holidays. CONTRACTOR may take the option of working on Saturdays if the WORK is scheduled regularly to be performed on Saturdays and is approved by OWNER.

### 76. Use of Explosives

The storage, possession or use of explosives on the site shall be strictly prohibited unless expressly authorized by the OWNER and approved by the State.

### 77. Compliance with Copeland Regulations

The CONTRACTOR shall comply with the Copeland Regulations of the Secretary of Labor (29 CFR Part 3) which are incorporated herein by reference.

### 78. Overtime Compensation

- A. The CONTRACTOR or Subcontractor shall not require or permit any laborer or mechanic in any

workweek in which he or she is employed under this CONTRACT to work in excess of forty hours in such workweek unless such laborer or mechanic receives compensation at a rate not less than one and one-half times the basic rate of pay for all hours worked in excess of forty hours in such workweek, whichever is the greater number of overtime hours.

- B. In the event of any violation of the provisions of paragraph (a), the CONTRACTOR or Subcontractor shall be liable to any affected employee for any amounts due, and to the State of Utah for liquidated damages. Such liquidated damages shall be computed with respect to each individual laborer or mechanic, including watchmen and guards, employed in violation of the provisions of paragraph (a) in the sum of \$10 for each calendar day on which such employee was required or permitted to work in excess of the standard forty hour workweek without payment of the overtime wages required by paragraph (a).

#### **79. Clean Air and Water**

The CONTRACTOR shall use best efforts to comply with all requirements and applicable regulations, standards, and implementation plans under the Clean Air Act (42 USC 7401 et seq.) and the Clean Water Act (33 USC 1251 et seq.). No part of the WORK shall be performed in a facility listed on the U.S. Environmental Protection Agency List of Violating Facilities during the term of the CONTRACT. CONTRACTOR further agrees to insert the substance of this clause in any Subcontract.

Clean air and water standards include any enforceable rules, regulations, guidelines, orders, or other requirements issued under the Clean Air Act, Clean Water Act, or Executive Order 11738; applicable approved implementation plans described in Sections 110(d), 111(c&d), or 112(d) of the Clean Air Act; and requirements contained in permits issued by the U.S. Environmental Protection Agency or state or local governments authorized by Sections 402 or 307 of the Clean Water Act. "Facility," as used here, means any building, plant, structure, mine, location, or site of operations owned, leased, or supervised by the CONTRACTOR or Subcontractor in the performance of the CONTRACT.

[Last Revised November 5, 2002.]



## **Supplemental General Conditions**

1. Statement Clarification of Terms:

The Division of Oil, Gas & Mining will assume responsibility for design and engineering on this project and will provide inspection. See Articles 36, 37, and 38.

2. Plan Checks:

Checks shall be made out to the Utah Division of Oil, Gas & Mining.

3. Equal Opportunity:

The CONTRACTOR agrees to abide by the provisions of Titles VI and VII of the Civil Rights Act of 1964 (42 USC 2000e) which prohibits discrimination against any employee or applicant for employment or any applicant or recipient of services on the basis of race, religion, color, or national origin. CONTRACTOR further agrees to abide by the following directives: Executive Order No. 11246, as amended, which prohibits discrimination on the basis of sex; federal regulation 45 CFR 90, which prohibits discrimination on the basis of age; Section 504 of the Rehabilitation Act of 1973 (29 USC 701 et seq), which prohibits discrimination on the basis of handicap; and Utah's Executive Order, dated June 30, 1989, which prohibits sexual harassment in the workplace.

4. Access to Records:

The CONTRACTOR agrees to provide the OWNER, the U.S. Office of Surface Mining, The Comptroller General of the United States, or any of their duly authorized representatives access to any books, documents, papers, and records which are directly pertinent to this CONTRACT for the purpose of making audit, examination, excerpts, and transcriptions. Such access will be made during normal business hours, or by appointment.

5. Retention of Records:

The CONTRACTOR agrees to retain and preserve any books, documents, papers, and records which are directly pertinent to this CONTRACT for a period of four years from the date of final payment for the WORK or from the date of Final Acceptance, whichever is later.

6. Variation in Estimated Quantities:

Variations Requiring Adjustments. Where the quantity of any item within the scope of this CONTRACT is an estimated quantity and where the actual quantity of such item varies by more than 15% above or below the estimated quantity stated in this CONTRACT, an adjustment in the CONTRACT price shall be made upon demand of either party. The adjustment shall be based upon any increase or decrease in costs due solely to variation above 115% or below 85% of the estimated quantity. If the quantity variation is such as to cause an increase in the time necessary for completion, the OWNER, upon receipt of a written request for an extension of time, prior to the date of final settlement of the CONTRACT, shall ascertain the facts and make adjustment for extending the completion date as in the judgment of the OWNER such facts justify.

7. Authority:

Provisions of this contract are pursuant to the authority set forth in Sections 63-56 UCA 1953 as amended, the Utah State Procurement Rules (*Utah Administrative Code*, Section R33), and related statutes which permit the OWNER to purchase certain specified services and other approved purchases for the State.

8. Conflict of Interest:

CONTRACTOR represents that none of its officers or employees are officers or employees of the State of Utah, unless disclosure has been made in accordance with Section 67-16-8, UCA 1953, as amended.

9. Separability Clause:

The declaration by any court or any other binding legal source that any provision of this contract is illegal and void shall not affect the legality and enforceability of any other provision of this contract unless the provisions are mutually dependent.

10. Debarment:

The CONTRACTOR certifies that neither it nor its principals are presently debarred, suspended, proposed for debarment, declared ineligible, or voluntarily excluded from participation in this contract by any governmental department or agency.

[Last Revised April 2, 1993.]



## **MIVIDA AND STANDARD SHAFT PROJECT**

### **TECHNICAL SPECIFICATIONS**

SECTION 0200	GENERAL SITE INFORMATION
SECTION 0220	MOBILIZATION/DEMOBILIZATION
SECTION 0225	RADIOLOGICAL PROTECTION
SECTION 0230	ACCESS IMPROVEMENT
SECTION 0240	DEMOLITION AND CLEAN-UP
SECTION 0250	MINE CLOSURES
SECTION 0254	POLYURETHANE FOAM SHAFT CLOSURES
SECTION 0270	SITE GRADING/EARTHWORK
SECTION 0280	DRAINAGE CONTROL AND STREAM PROTECTION
SECTION 0290	REVEGETATION
SECTION 0300	SPECIFIC SITE REQUIREMENTS

## 0200 General Site Information

### PART 1 - GENERAL

#### 1.01 WORK INCLUDED

The WORK consists of reclamation of abandoned mine features as described in Section 0300. The General Technical Specifications, Sections 0200 through 0290, outline WORK broadly applicable to all abandoned mine reclamation situations and that may not be required at each mine site in this project. Section 0300 provides the site-specific detail. Where there is a conflict between Section 0300 and the General Technical Specifications (0200's), Section 0300 shall govern.

#### 1.02 SUBMITTALS

- A. Submittals requested in the Technical Specifications to be submitted with the Bid Proposal shall be included in and submitted with the sealed bid proposal delivered to the Division of Purchasing.
- B. Submittals requested in the Technical Specifications to be submitted after award of the CONTRACT or during construction shall be delivered to the designated representative for the Division of Oil, Gas and Mining (DOGM), referred to in these Specifications as the OWNER.

CONTRACTOR shall submit within five (5) days after award of the CONTRACT a calendar of WORK for performing the WORK, including routine workdays and hours, anticipated holidays, and days that the project will remain idle. Schedule shall also indicate WORK schedules for subcontractors and their estimated start and completion days. Allowance in the schedule shall be made for routine delays due to weather or other site conditions as they occur. The OWNER shall approve said schedule. Any significant deviation from that schedule shall be submitted in writing to the OWNER in the form of an updated schedule as the WORK progresses.

#### 1.03 RELATED WORK

- A. Section 0220: Mobilization/Demobilization
- B. Section 0225: Radiological Protection
- C. Section 0230: Access Improvement
- D. Section 0250: Mine Closures
- E. Section 0254: Polyurethane Foam Mine Closures
- F. Section 0270: Site Grading/Earthwork
- G. Section 0280: Drainage Control & Stream Protection
- H. Section 0290: Revegetation
- I. Section 0300: Specific Site Requirements

#### 1.04 CONDITIONS AND RESTRICTIONS

- A. The project area and vicinity may contain several abandoned mine and/or town sites, but WORK will be limited to items specifically identified in Section 0300: Specific Site Requirements.
- B. *The pre-bid meeting is optional.* However, due to the nature of the WORK at these sites, the CONTRACTOR is strongly encouraged to participate in the entire prebid site tour and meeting in order to submit a responsible bid. The CONTRACTOR shall acknowledge in the bid that the site conditions have been examined and that the measurements and evaluations necessary to plan and bid the WORK have been made.
- C. Due to the hazards associated with abandoned mines, all WORK on mine portals shall be conducted under the supervision of a qualified person with current certification to do such WORK under the General Safety Orders of Utah Coal Mines (i.e. Mine Foreman and/or Fire Boss). This person is referred to as the "Certified Person" in these specifications hereafter. No

smoking or open flames shall be permitted within fifty feet of any mine opening. Welding in or near a mine opening is permitted with the approval of the Certified Person. No person shall be permitted to enter a mine opening unless the atmosphere of the opening is tested, the roof is adequately supported and tested, and only at the direction of the Certified Person.

- D. CONTRACTOR shall identify and develop rapid communication procedures with the closest available emergency medical response units and medical centers. All workers, foremen, superintendents, and managers shall be indoctrinated to emergency response procedures.
- E. CONTRACTOR shall be aware that underlying mine workings exist in the areas to be disturbed by the CONTRACTOR. The location, extent, and condition of the underground workings at each mine site are not well known. These workings or voids where workings have caved may be encountered unexpectedly during the course of the WORK and present a hazard to equipment operators and other workers at the site. The CONTRACTOR shall take every precaution to protect the safety of the workers during WORK on the project. Any voids or openings excavated or discovered shall be brought to the immediate attention of the OWNER.
- F. The WORK shall stop and the OWNER shall be notified immediately if an accident occurs or upon discovery of a hazard that threatens the safety of workers or the public. The OWNER shall be notified immediately of any situation that may cause environmental damage.
- G. CONTRACTOR shall provide, erect, and maintain temporary barriers, signs, and security devices as necessary to ensure the safety of the CONTRACTOR's personnel, the OWNER's personnel, and the general public.
- H. WORK shall occur normally during daylight hours and shall not be performed when darkness or other conditions required the use of artificial light to safely perform the WORK, without the prior written approval of the OWNER.
- I. WORK shall be performed during weekdays and shall not be performed during weekends or legal State and Federal holidays without the prior written approval of the OWNER. A schedule of holidays is available from the OWNER.
- J. WORK shall be conducted with minimum interference to public or private thoroughfares. Egress and access shall be maintained at all times.
- K. Roadways shall not be closed or obstructed without permits. The CONTRACTOR will close and lock gates at the landowner's request.
- L. All trucks transporting materials and debris shall be covered with tarps or other suitable coverings if necessary to eliminate loss of debris during transportation to off-site disposal areas.
- M. CONTRACTOR shall provide water and an adequate water supply system for dust suppression where dust will cause a public nuisance or as directed by OWNER. The CONTRACTOR will pay the cost of water and dust suppression.
- N. No materials shall be placed in or be situated such that they may enter any stream, tributary, or drainage channel.
- O. Relics, antiques, artifacts and similar objects as identified by the OWNER remain the property of the OWNER. CONTRACTOR shall notify the OWNER upon discovery of cultural features and obtain direction from OWNER regarding handling of features that interfere with performing the WORK. Relics and antiques include, but are not limited to:

Section 0200

1. Cornerstone and contents
  2. Commemorative plaques
  3. Archaeological relics or finds
  4. Historical relics
- P. CONTRACTOR shall remove and promptly dispose of any contaminated, vermin infested, or dangerous materials encountered. Transformers, oil-filled electrical equipment, or other toxic materials shall be called immediately to the attention of the OWNER. Disposal of such items shall be the responsibility of the CONTRACTOR and at the direction of the OWNER in accordance with EPA and State Health requirements.
- Q. CONTRACTOR shall remove from site all debris created during construction.
- R. Materials shall not be burned on site without appropriate permits and the approval of the OWNER.
- S. Blasting shall be permitted only with prior written approval of the OWNER and following submission by the CONTRACTOR of a blasting plan.
- T. Existing utilities, benchmarks, trees, vegetation, and landscaping materials which are not to be demolished, relocated, or otherwise disturbed shall be protected.
- U. Wildlife of any kind (except Norway rats) encountered during the WORK shall be left unharmed or, if captured, released unharmed offsite. Snakes, including rattlesnakes, shall not be harmed. Any wildlife inadvertently killed by the CONTRACTOR will be turned over to the OWNER to be disposed of under the Certificate of Registration (COR Number 6COLL5414) issued to the OWNER by the Utah DWR. CONTRACTOR shall immediately notify OWNER of any bats found in mine openings.
- V. CONTRACTOR shall compensate employees at a rate of no less than 1.5 times the base rate of pay for work beyond 40 hours in one week.
- W. CONTRACTOR shall submit to OWNER each week daily logs indicating the following: 1) weather conditions, 2) crew size, 3) hours worked, 4) equipment used, 5) work completed, 6) WORK approved, 7) delays, 8) equipment downtime, 9) injuries, 10) visitors, 11) access problems, etc. OWNER has provided a form for these logs in Appendix C.
- X. Should onset of adverse winter or extreme summer weather conditions force construction to stop prior to completion of the WORK, the sites shall be left in a condition that minimizes safety hazards and risk of erosion. Temporary erosion control structures may be required. Revegetation may be postponed to the fall if necessary.
- Y. Depending upon the bid submittals and the overall CONTRACTOR selection process, CONTRACTOR WORK may precede, follow, or occur during work by other CONTRACTORS at the same site and/or other sites in the Project Area.
- Z. CONTRACTOR shall select from a pre-determined number of staging areas identified in the specifications and secure all necessary permits, including camping permits, from the applicable land management agency.

#### 1.05 QUALITY ASSURANCE

- A. CONTRACTOR shall use only quality materials in performing the WORK.
- B. Quality of the WORK performed by the CONTRACTOR shall be subject to approval by the OWNER. CONTRACTOR shall assure that the WORK has been performed to the specifications and standards as described herein. The OWNER shall inspect and accept or reject the WORK as the WORK progresses. Payment shall be made only for WORK accepted and approved by the OWNER. CONTRACTOR shall warrant the WORK for a period of one year following final acceptance except that such material warranties and guarantees from manufacturers and suppliers that may be longer than one year shall carry for their term.

#### PART 2 - PRODUCTS

##### 2.01 GENERAL

Products and materials used in the WORK shall be as required in these Specifications.

##### 2.02 DELIVERY, STORAGE AND HANDLING

- A. CONTRACTOR shall be responsible for the delivery, storage and handling of all items and materials used in performing the WORK.
- B. CONTRACTOR shall be responsible for all materials used in conjunction with the WORK until said WORK is accepted and approved by the OWNER and shall warrant all materials as required by Part 1.05, Quality Assurance.

#### PART 3 - EXECUTION

##### PREPARATION

- A. Upon receipt of notice to proceed, the CONTRACTOR shall perform the WORK as required by these Specifications and Construction Drawings.
- B. CONTRACTOR shall obtain and provide proof of all licenses, permits, bonds, insurance and other such items as may be required by these Specifications and local, regional, State and Federal jurisdictions prior to execution of the WORK. CONTRACTOR shall select from a pre-determined set of staging areas identified in the specifications and secure all necessary permits, including camping permits, from the applicable land management agency.
- C. Upon receipt by the CONTRACTOR of the NOTICE TO PROCEED, the CONTRACTOR shall notify the OWNER of the starting date and execution of the WORK shall commence in accordance with the General Specifications as included with the Agreement and the Technical Specifications as presented herein. CONTRACTOR shall provide the OWNER with a schedule for the proposed WORK in calendar, bar chart, or critical path schedule form.

#### PART 4 - FORM OF AGREEMENT

##### 4.01 CONTRACT AGREEMENT

The CONTRACT agreement will be in the form of that included in the bid package. This agreement may be administered as a Division of Purchasing Purchase Order. If administered as a purchase order, the purchase order will reference the bid package, and all the terms and conditions of the

## Section 0200

solicitation, including the contract form, general and supplementary conditions, technical specifications, and addenda will apply to the agreement.

### 4.02 CHANGES TO THE AGREEMENT

- A. When these services are procured by an agency contract, OWNER shall require amendments to the Agreement to be in the form of a change order, signed by both parties. When these services are procured by a Division of Purchasing Purchase Order, amendments shall be on Form DP-28 "Request for Purchase Order Cancellation or Change."
- B. Change orders or Form DP-28's shall become attached to and part of the Agreement under the terms of the Agreement with changes as stipulated on the change order or Form DP-28. Change orders or Form DP-28's shall not release the CONTRACTOR from any other terms or conditions that apply and are a part of the Agreement.
- C. Any additional WORK must be authorized by the OWNER and must be in the form of a contract change order or Form DP-28 as an amendment to the Agreement. The change order or Form DP-28 must be fully executed prior to the CONTRACTOR undertaking any additional WORK.

## PART 5 - MEASUREMENT, PAYMENT, AND WORK INCLUDED

### 5.01 GENERAL

- A. The WORK included and measurement of and payment for that WORK shall be as described within each Section of the Technical Specifications and Supplementary Condition #6.
- B. Total contract amount, including any change orders, shall constitute full compensation for the WORK.
- C. Payments shall only be made for those items shown on the Bid Schedule. All other costs or incidentals shall be reflected in the Bid Schedule or shall be paid at the CONTRACTOR's expense.

### 5.02 RETAINAGE

Unless stated otherwise in the specific section of the Specifications, all final bid item payments shall have ten percent withheld as retainage until successful completion of the CONTRACT. The retainage shall be made from each progress payment, and be released upon written Final Acceptance by the OWNER.

### 5.03 PENALTIES

- A. The OWNER reserves the right to levy a penalty payment for areas unnecessarily disturbed during the WORK. These areas include any archeological sites, paleontological sites, or undisturbed upland vegetation areas.
- B. The penalty for unnecessary disturbance to archeological sites, paleontological, or upland vegetation areas will be based on the per acre disturbance at the CONTRACTOR's bid amount for revegetation of adjacent sites.

END OF SECTION 0200

## **0220 Mobilization/Demobilization**

### **PART 1 - GENERAL**

#### **WORK INCLUDED**

The item for payment for mobilization/demobilization is intended to compensate the CONTRACTOR for operations including, but not limited to, those necessary for the movement of personnel, equipment, supplies, and incidentals to and from the project area, movement between the various mine sites included within the project area, and for all other WORK and operations which must be performed or costs incurred prior to the initiation of meaningful work at the site.

### **PART 2 - PRODUCTS**

#### **2.01 DRINKING WATER AND SANITARY FACILITIES**

CONTRACTOR shall provide and maintain safe drinking water and sanitary facilities for all employees, all subcontractors' employees, and the OWNER. Drinking water and sanitary facilities shall comply with all regulations of the local and state departments of health and be approved by the OWNER.

#### **2.02 COMMUNICATIONS**

CONTRACTOR shall provide OWNER's onsite inspector or representative with an onsite communication system for the OWNER's exclusive use for the full duration of the project construction. The communication system shall be a cellular telephone and cellular service, or equivalent. Cell phones shall have sufficient power to allow clear transmissions from a majority of the project area. Any necessary accessories, such as antennas, batteries, battery charger, cigarette lighter adapter, and operating manuals, shall be provided. This item is not a separate bid or pay item; all telephone costs are subsidiary to and should be included in the overall cost for Mobilization/Demobilization.

### **PART 3 - EXECUTION**

#### **3.01 PREPARATION**

- A. Preparation of the WORK shall include obtaining all permits and other such incidentals as necessary to execute the WORK. CONTRACTOR shall select from a pre-determined set of staging areas identified in the specifications and secure all necessary permits, including camping permits, from the applicable land management agency.
- B. Permits shall be posted or readily available prior to start of construction activities as required by municipal, State, or Federal regulations.

#### **3.02 EXECUTION**

Upon receipt by the CONTRACTOR of due NOTICE TO PROCEED, the CONTRACTOR shall notify the OWNER of the starting date and execution of the WORK shall commence in accordance with the General Specifications as included with the Agreement and the Technical Specifications as presented herein. CONTRACTOR shall provide the OWNER with a schedule for the proposed WORK in calendar, bar chart, or critical path schedule form.

PART 4 - MEASUREMENT AND PAYMENT

4.01 BASIS FOR PAYMENT

No partial payments will be made for multiple equipment moves or for moving between sites. Only the following partial payment shall be made of the total lump sum for mobilization/demobilization. Payment of sixty percent (60%) of total lump sum for mobilization will be made when 10 percent of the overall BID PRICE has been earned from other bid items. Payment of the remaining forty percent (40%) of the total lump sum for demobilization will be made after issuance of the Certificate of Substantial Completion at the completion of CONTRACT. Payments for mobilization/demobilization are not subject to withholding of retainage. The BID PRICE for mobilization/demobilization will also include those incidental costs as required by the CONTRACTOR in order to commence the WORK such as permits, insurance, and other such items as may be required to perform the WORK.

4.02 MEASUREMENT

Measurement will be based on the amount of the WORK performed and accepted and approved by the OWNER. When 10 percent of the WORK has been earned, the CONTRACTOR may submit on the invoice sixty percent (60%) of the BID PRICE for mobilization/demobilization as set forth above. On completion of the CONTRACT and issuance of the Certificate of Substantial Completion, the CONTRACTOR may claim the remaining forty percent (40%) of the BID PRICE for mobilization/demobilization.

4.03 PAYMENT

The BID PRICE for mobilization/demobilization will be paid once only and will include complete mobilization, demobilization, and moves between sites regardless of the number of times equipment is moved or additional equipment is transported to or from the construction site. The BID PRICE will also include those incidental costs as required by the CONTRACTOR in order to commence with the WORK such as permits, insurance, and other such items as may be required to perform the WORK.

END OF SECTION 0220



## 0225 Radiological Protection

### PART 1 - GENERAL

#### 1.01 INTRODUCTION

- A. This Radiological Protection Plan describes the methods to be employed for health and safety at abandoned uranium mine sites. The guidelines in this plan are generic and allow for variations in site specific conditions.
- B. The main radiological concerns while working on this project are dust control, personal hygiene, and monitoring exposure. The object of this Technical Specification Section is to provide all personnel working on this project with information on how to reduce dust while the work is conducted, reduce the spread of contaminated dust between workers, and prevent the ingestion and inhalation of dust.
- C. The procedures in this Radiological Protection Plan are based on the principles of time, distance, and shielding. This is the idea that a person's exposure to radiation, and the potential health risks associated with that exposure, can be controlled by managing the time, distance, and protective barriers between the person and the source of radiation. CONTRACTOR shall strive to manage all construction activities at uranium mines with the goals of reducing worker time in radioactive areas, keeping workers away from radioactive materials, and shielding workers from radiation with protective clothing.

#### 1.02 SUBMITTALS

CONTRACTOR shall submit upon completion of the WORK the records of exposure to radon and the results of the thermoluminescent dosimeter (TLD) badge analyses for each employee.

#### 1.03 RELATED WORK

- A. Section 0250: Mine Closures
- B. Section 0300: Specific Site Requirements

#### 1.04 SAFETY TRAINING

- A. The CONTRACTOR and crew is required to attend a Health and Safety Training meeting after the bid is awarded and before construction begins. This meeting will be arranged by the OWNER. It shall include radiological safety training and will be presented by a Health Physicist from the Environmental Protection Agency or by the OWNER. All on-site crewmembers must go through the training. New workers hired or brought to the project after the start of construction must go through equivalent training before working on the project.
- B. The CONTRACTOR is required to hold a mandatory Health and Safety meeting once a week during the course of the work.

#### 1.05 PROJECT SPECIFIC INFORMATION

Radiation measurements for the project are presented in Section 0300, Part 2.04.B.

### PART 2 - DEFINITIONS

## 2.01 RADIOLOGICAL TERMS

- A. Rad (acronym for Radiation Absorbed Dose) is the deposition of energy into soft tissue (human body) by a specific form and energy level of radiation.
- B. Roentgen (R) is a unit for measuring the amount of radiation passing through air that an individual would be subjected to if he or she were to stand in that spot. It is defined as 1 electrostatic unit per cubic centimeter of air.
- C. Rem (acronym for Roentgen Equivalent Man) is the estimation of the biological risk associated with the radiation exposure regardless of the type of radiation or its energy level. Roentgen and Rem are considered equal measurements and are often used interchangeably.
- D. Radiation levels encountered in the field are usually very small fractions of the defined units. To simplify the expression of very small numbers, the following prefixes and symbols are commonly used:

mR stands for milli-Roentgen (R).

1 milli-Roentgen =  $10^{-3}$  Roentgen = 0.001 Roentgen = 1000  $\mu$ R

$\mu$ R stands for micro-Roentgen (R).

1 micro-Roentgen =  $10^{-6}$  Roentgen = 0.000001 Roentgen = 0.001 mR

- E. Working Level (WL) is a unit for measuring the concentration of radon gas and radon daughters in an atmosphere. One working level is equal to 200 pCi/l (pico-curies per liter of air). Exposure to radon gas is measured in working level months (WLM) or working level hours (WLH). Radon exposure is calculated by multiplying the exposure time (in hours or months) by the radon concentration (working level). For working level calculations, a month is defined as 173 hours. A WLM is thus equal to 173 WLH, or the equivalent of 173 hours exposure in a 1 WL area, 346 hours exposure in a 0.5 WL area, etc.

## 2.02 PERSONAL PROTECTION PRODUCTS/TERMS

- A. Coveralls. Coveralls shall have a full body and sleeves. Suspender type coveralls are not acceptable unless they are worn with a long sleeve jacket. Coveralls may be made of cotton or polyester fabric or some blend thereof. Coveralls must not have torn seams or holes. If coveralls tear during the course of the work they shall be mended or replaced. The CONTRACTOR may choose to wear Tyvek® suits instead of coveralls.
- B. Work Gloves. Leather and rubber-coated work gloves shall not have holes or broken seams. If gloves develop holes or broken seams during execution of the WORK they shall be immediately removed and replaced with new gloves.
- C. Glove Liners. Cotton glove liners shall be worn under the leather or rubber work gloves while personnel are within the Exclusion Zone. Cotton liners shall be changed regularly.
- D. Respirators. Respirators shall be NIOSH/MSHA approved. Cartridges shall be rated for radon daughters. Standard paper or fabric dust masks are not acceptable.
- E. TLD. A thermoluminescent dosimeter (TLD) is a badge worn to monitor gamma radiation dose. All personnel shall wear a TLD while working within the project boundary (not just within the Exclusion Zones). TLDs are available through the company listed below. For other vendors contact the Utah Department of Environmental Quality, Radiation Control at (801) 536-4250.  
Global Dosimetry Solutions, Inc.

P.O. Box 19536  
 Irvine, California 92623  
 phone: 800-251-3331 or 714-545-0100 ext 6925  
<http://www.globaldosimetry.com>

- F. Exclusion Zone. The Exclusion Zone is a restricted work area within which protective measures are required. The Exclusion Zone typically encompasses the mine dump and shaft or adit. This area may be delineated with flagging or staking. The Exclusion Zone shall have a single entrance/exit point, which should be clearly indicated. The size of the Exclusion Zone shall be dictated by the mine closure method. If the mine is to be backfilled, the Exclusion Zone shall include the area between the mine opening and the dump. All workers shall be aware of the Exclusion Zone. Only equipment and personnel actively engaged in mine closure work are allowed within the Exclusion Zone. All personnel working within the Exclusion Zone shall wear cotton coveralls or Tyvek® suits, safety boots, safety glasses, ANSI approved hard hats, and leather work gloves with cotton glove liners underneath. All personnel and equipment leaving the Exclusion Zone must be decontaminated.
- G. Decontamination Station. A Decontamination Station shall be set up in the Exclusion Zone entrance/exit. The location shall meet the OWNER's approval. This station shall be placed upwind of dust-generating activities if possible. All personnel entering and exiting the Exclusion Zone shall pass through this area to remove soil from boots, and to remove, dispose of, and store personal protective equipment. The CONTRACTOR shall provide the decontamination station with all materials necessary for personnel exiting the Exclusion Zone to clean boots, wash hands and wipe faces, and store protective gear.
- H. Wash Station. A Wash Station shall be set up in the Exclusion Zone entrance/exit at the decontamination station. The CONTRACTOR shall supply the Wash Station with liquid hand soap, paper towels, moist towelettes, water, and wash tubs. All personnel leaving the Exclusion Zone shall wash dust from exposed skin surfaces before being allowed to exit.

### PART 3 - EXECUTION

#### 3.01 RADIOLOGIC PROTECTION STANDARDS

- A. CONTRACTOR shall comply with all applicable standards of the Mine Safety and Health Administration (MSHA) published in "Safety and Health Standards Applicable to Underground Metal and Nonmetal Mining and Milling Operations" (30 CFR Part 57), in particular sections 57.5037 through 57.5047.
- B. The OWNER shall regularly measure concentrations of radon progeny and gamma radiation in each mine opening and at the mine dump. The date, location, and results obtained shall be recorded and submitted to the CONTRACTOR. CONTRACTOR shall maintain these records for at least two years.
- C. CONTRACTOR shall calculate and record complete individual exposures to radon daughters using the MSHA form "Record of Individual Exposure to Radon Daughters" (Form 4000-9) or acceptable equivalent. A suitable form is provided in Appendix B. Forms shall be submitted to the OWNER within 30 days of Substantial Completion and shall be made available to the exposed workers. CONTRACTOR shall maintain these records for at least two years.
- D. No worker shall be permitted to receive a radon daughter exposure in excess of 0.40 WLM (working level months) in any calendar year. The 0.4 WLM exposure limit is equal to 69.2 WLH

## Section 0225

(working level hours), or equivalent to 69.2 hours of work in a 1 WL area.

- E. All construction workers are required to wear TLDs to monitor their exposure to gamma radiation during the project. Readings will be recorded on a quarterly basis. All exposure information will be supplied to OWNER.
- F. No worker shall be permitted to receive a radiation exposure in excess of 100 mR in any calendar year.
- G. Workers shall wear respirators whenever dust is generated, when working under the brow of a mine, and during welding activities. No worker shall be exposed to air containing radon daughter concentrations exceeding 1.0 WL (working level) without a respirator. Where radon daughter concentrations exceed 10 WL, respirator protection against radon gas shall be provided by supplied air.
- H. The CONTRACTOR and all others on site must comply with the Health and Safety Plan developed for this project and these specifications.

### 3.02 SMOKING AND EATING RESTRICTIONS

- A. Smoking is prohibited within 300 feet of the Exclusion Zone due to the synergistic health effects of smoking and radiation.
- B. Eating, drinking, and chewing gum and tobacco are prohibited within 300 feet of the Exclusion Zone to prevent ingestion of radioactive dust.

### 3.03 DUST CONTROL

- A. Dust control is mandatory for all excavation and mine backfill work, whether done with machinery or manual labor. To minimize muddy conditions and maximize dust control at each mine site, small pesticide-type canister sprayers or similar devices shall be used to allow for local application of water for dust control. Water trucks may be used as long as the amount of water applied does not create a muddy work area (Exclusion Zone). During windy conditions work will be temporarily suspended until dust generation is minimized.
- B. Dust control is required for all rock drilling. Wet drilling (controlling dust with a light water spray) is the preferred method. A pesticide-type canister sprayer shall be used to mist rock drill sites with water while drilling holes for bat gate and grate anchor pins. Enough water shall be applied to keep the area damp, but not enough to make the site drip. Dry dust control systems (e.g. vacuum collectors) may be used with OWNER'S approval.

### 3.04 MINE VENTILATION

- A. A fan system or other device shall be installed in mine adits to circulate fresh outside air with the mine air to reduce worker exposure to radon gas during construction of bat gates and walls. Adequate ventilation is particularly important while welding due to the smoke and fumes generated. Fans should not be used in a way that stirs up dust. It may be necessary to dampen the work area to keep dust controlled.
- B. The CONTRACTOR may hang plastic sheeting or use other material to block the mine inside the brow to reduce radon gas levels at the brow of the mine where welding or other activities will take place.

### 3.05 BAT GATE OR BLOCK WALL INSTALLATION

- A. The CONTRACTOR shall wear respirators while working under the brow of the mine and during welding activities in accordance with Part 3.01.G of this Section.
- B. The CONTRACTOR shall reduce dust from drilling and site preparation and maintain adequate work area ventilation in accordance with Parts 3.03 and 3.04 of this Section.
- C. During bat gate construction the welder shall not wear Tyvek® suits because they melt when sparks land on them. The welder shall wear some type of polyester/cotton blend coverall with welding leather.

### 3.06 USE OF PERSONAL PROTECTIVE GEAR

- A. All construction workers are required to wear TLDs to monitor their exposure to gamma radiation during the project. Workers shall wear a TLD while working within the project boundary (not just within the Exclusion Zones). TLDs are to be worn underneath the coveralls to keep dust out of the badge to prevent a false radiation exposure reading.
- B. Cotton coveralls shall be worn while conducting the WORK described in these specifications. Coveralls must not have torn seams or holes. If coveralls tear during the course of the work they shall be mended or replaced. Coveralls shall be stored individually in heavy (8ml) plastic bags or equivalent when not in use. This is to prevent cross-contamination with coveralls worn by other workers. Coveralls shall be laundered regularly during the course of the WORK.
- C. If the CONTRACTOR opts to wear Tyvek® suits instead of cotton coveralls they shall be provided by the CONTRACTOR and worn while conducting the WORK described in these specifications. Tyvek® suits shall be removed and thrown away whenever they become torn or overly dirty. Tyvek® suits shall be removed at lunch time, breaks, and between shifts. Clean Tyvek® suits shall be donned before entering the Exclusion Zone and removed when leaving the Exclusion Zone at the Decontamination Station. A Tyvek® suit shall not have holes or open seams. If a Tyvek® suit is torn during execution of the WORK, the worker shall immediately go to the Decontamination Station to remove the torn suit and don another.
- D. Leather and rubber-coated work gloves shall be worn with cotton glove liners. Cotton liners shall be provided by the CONTRACTOR and replaced daily. Each pair of work gloves shall be stored in individually assigned self-sealing bags (e.g. Ziplock®) when not in use to prevent cross-contamination with gloves worn by other workers. Work gloves shall be replaced when holes wear through them or seams come undone.
- E. Workers shall wear respirators whenever dust is generated, when working under the brow of a mine, and during welding activities. No worker shall be exposed to air containing radon daughter concentrations exceeding 1.0 WL (working level) without a respirator. Where radon daughter concentrations exceed 10 WL, respirator protection against radon gas shall be provided by supplied air.
- F. Respirator cartridges shall be changed as needed. Respirators shall be maintained, kept free of dust, and individually stored in a self-sealing plastic bag when not in use. Respirators shall not be shared by multiple workers.
- G. Used Tyvek® suits, gloves, glove liners, respirator cartridges, towels, towelettes, plastic bags, and other disposable contaminated items shall be stored in plastic garbage bags and taken to a licensed landfill for disposal.

- H. Reusable clothing items (coveralls, glove liners) may be laundered and reused if they are contaminated at less than twice the background radiation level. Laundering may be done in a standard washing machine, but contaminated items should be washed separately from other laundry. Clothing contaminated at more than twice the background radiation level shall be stored in plastic garbage bags and taken to a licensed landfill for disposal.

### 3.07 DECONTAMINATION (DECON) PROCEDURE FOR PERSONNEL

- A. A designated area (Decon Station) shall be set up by the CONTRACTOR, with the approval of the OWNER, for the removal of gloves and coveralls and for brushing dirt off of boots. The Decon Station shall be at or near the entrance/exit to the Exclusion Zone. At the Decon Station, containers for gloves, coveralls, and respirators shall be left so that personnel can properly store these items as they leave the Exclusion Zone. Brushes and water shall be supplied to brush and/or rinse boots off.
- B. The order of decontamination shall be as follows:
  - 1. Soil and dust shall be brushed and/or rinsed off of boots.
  - 2. Leather gloves shall be removed and stored in a sealed plastic container.
  - 3. While still wearing the cotton glove liners, remove coveralls by rolling the inside away from the body, turning the coveralls inside out. This is done to contain dust on the outside of the coveralls. Store coveralls in a separate sealed plastic container or bag.
  - 4. While still wearing the cotton glove liners the respirator shall be removed and wiped free of dust. If the cartridges need to be changed, the used ones can be disposed of at this time. The respirator shall be stored in a sealed plastic container. Used cartridges shall be disposed of at a licensed landfill.
  - 5. The cotton gloves shall then be scanned for beta and gamma radiation. If the reading is below twice the background levels the cotton gloves may be kept in a separate bag and used again. If they measure twice the background level or higher they are to be stored in a plastic bag and disposed of at a licensed landfill.
  - 6. Proceed from this Decon Station to the Wash Station.
  - 7. ALL PERSONNEL will wash at the Wash Station whenever leaving the Exclusion Zone to remove dust from exposed skin surfaces. This is the final decon step before leaving the Exclusion Zone.
- C. Coveralls shall occasionally be frisked with a beta and gamma probe to determine level of contamination.

### 3.08 DECONTAMINATION (DECON) PROCEDURE FOR EQUIPMENT

- A. Tools used within the Exclusion Zone do not have to be decontaminated between mine sites if they are transported or stored in an open truck bed. If they are stored inside an enclosed storage area or inside a vehicle, all tools used in the Exclusion Zone shall be rinsed with water at the same Decon Station personnel pass through to remove all soil and dust particles. All tools shall be decontaminated before demobilizing at the end of the project.
- B. The interior and exterior of heavy equipment shall be decontaminated with a pressure washer

prior to final demobilization. The wastewater created by washing shall be contained on site for evaporation or infiltration into the soil on the project site. Wash Station sites and equipment shall be situated so that heavy equipment and vehicles do not drive through mud created by the washing process.

- C. No extra precautions in the handling of equipment air filters beyond standard practice is required because on-site dust shall be controlled at all times.
- D. All vehicles (passenger and other) driven to a mine site and not used as part of the WORK at the site shall be parked up-wind of dust-generating activities with the windows rolled up. These vehicles should be vacuumed and washed at a car wash before proceeding with off-site or weekend activities.
- E. Workers will occasionally have to drive between mine sites. Coveralls may be worn inside the vehicle if the seats and floors are covered with plastic sheeting provided by the CONTRACTOR. This will minimize getting dust in the upholstery.
- F. Equipment operators may tram between mine sites without going through the decon station, as long as they decontaminate themselves before leaving the last mine site. Operators must, however, go through Decon procedures before leaving the site at lunchtime or at the end of the day.

#### PART 4 - MEASUREMENT AND PAYMENT

##### 4.01 BASIS FOR PAYMENT

Payment will only cover items purchased to comply with this specification. The following items that apply are: respirators, respirator cartridges, plastic sheeting, liquid hand soap, paper towels, wet wipes, plastic tubs, stiff bristle brushes, leather and rubber work gloves, cotton glove liners, coveralls, car wash, laundry, storage containers, plastic bags, landfill charges, TLDs and readings, water, canister sprayers, flagging, and radiological specialist.

##### 4.02 MEASUREMENT

Measurement will be based on the amount of the WORK performed and accepted and approved by the OWNER. When 10 percent of the WORK has been earned, the CONTRACTOR may submit on the invoice sixty percent (60%) of the BID PRICE for radiological protection as set forth above. On completion of the CONTRACT and issuance of the Certificate of Substantial Completion, the CONTRACTOR may claim the remaining forty percent (40%) of the BID PRICE for radiological protection.

##### 4.03 PAYMENT

No partial payments will be made for radiological protection. Only the following partial payment shall be made of the total BID PRICE amount for radiological protection: Payment of sixty percent (60%) of the total BID PRICE for radiological protection will be made when 10 percent of the overall BID PRICE has been earned from other bid items. Payment of the remaining forty percent (40%) of the total BID PRICE for radiological protection will be made after issuance of the Certificate of Substantial Completion at the completion of CONTRACT. Payments for radiological protection are not subject to withholding of retainage. The BID PRICE for radiological protection will be paid once only and will include cost of all materials, products, and services.

END OF SECTION 0225

## 0230 Access Improvements

### PART 1 - GENERAL

#### 1.01 WORK INCLUDED

This item for payment is to develop and maintain site access or improve existing site access. Improvement is limited to the extent required to complete WORK at each mine site. It is not the intent of this WORK to construct roads. The WORK shall include temporary site access to reach sites of construction, and maintenance of existing permanent roads that must be used for movement of equipment, materials and labor. CONTRACTOR shall minimize disturbance resulting from site access improvements. In areas in which a passable road did not previously exist, the CONTRACTOR shall reclaim the access improvement in accordance with this Section upon completion of the WORK. Existing, permanent roads shall be left in a condition at a minimum as good as that prior to the WORK.

#### 1.02 SUBMITTALS

The CONTRACTOR shall submit *with the Bid Proposal* a description of access improvements to be performed at each site and shall not deviate from this plan without the written approval of the OWNER. For sites not easily accessible, the CONTRACTOR may choose to gain equipment access, do hand work, or access with a helicopter.

#### 1.03 RELATED WORK

- A. Section 0240: Demolition and Clean-up
- B. Section 0250: Mine Closures
- C. Section 0254: Polyurethane Foam Shaft Closures
- D. Section 0270: Site Grading/Earthwork
- E. Section 0300: Specific Site Requirements

### PART 2 - PRODUCTS

#### MATERIALS

- 2.01 CONTRACTOR may utilize local resistant materials or import road base materials to maintain access and minimize damage to the environment. If wet weather conditions prevail, OWNER may require CONTRACTOR to stockpile road base material at work sites in order to maintain the schedule.
- 2.02 CONTRACTOR may choose to temporarily place corrugated steel pipe or other conveyance structures in the access improvement. The CONTRACTOR shall comply with Section 0280: Drainage Control and Stream Protection unless otherwise directed by the OWNER.

### PART 3 - EXECUTION

#### GENERAL

- 3.01 The location, alignment and grade of any temporary access improvement shall be in accordance with Section 0300: Specific Site Requirements, subject to Section 0280: Drainage Control and Stream Protection, and subject to the approval of the OWNER.
- 3.02 Temporary access improvements shall be constructed so as to minimize disturbance to existing vegetation, and to minimize potential erosion.
- 3.03 Where temporary site access crosses perennial or intermittent streams, the CONTRACTOR shall



maintain the drainage by providing a temporary crossing in accordance with Section 0280: Drainage Control and Stream Protection, and subject to the OWNER'S approval. Upon completion of the WORK, CONTRACTOR shall restore drainages to approximate original condition, subject to the acceptance and approval of the OWNER.

- 3.04 When no longer required by the CONTRACTOR, temporary access improvements will be reclaimed in the following manner. Existing passable access shall be left in or returned to approximate original condition. Access previously impassable or newly created access shall be restored to blend with surrounding contours and reclaimed for erosion control as shown on the Drawings. The surfaces of such access shall be scarified and revegetated in accordance with Section 0290: Revegetation.

#### PART 4 - MEASUREMENT AND PAYMENT

##### 4.01 MEASUREMENT

Measurement shall be per mine site as access improvement WORK is completed, accepted and approved by the OWNER. Measurement shall be consistent with the BID PRICE. The OWNER's approval of mine site access development will be authorization for payment of 50 percent of the pay item which will also include consideration for maintenance of temporary access to the site throughout the WORK. The OWNER's acceptance of all WORK completed and approval of the temporary site access reclamation for the site will be authorization for payment of the balance of this pay item.

##### 4.02 PAYMENT

Payment for maintenance of existing paved and gravel-surfaced roads will be consistent with the BID PRICE for this item. Payment of 50 percent of the BID PRICE will be made upon receipt of the invoice submitted by CONTRACTOR. The balance of 50 percent of the BID PRICE may be invoiced and paid after approval of the site WORK and approval of site access reclamation. Payment of this item is subject to withholding of the retainage.

END OF SECTION 0230

## 0240 Demolition And Clean-Up

### PART 1 - GENERAL

#### 1.01 WORK INCLUDED

The WORK consists of the demolition and clean-up of designated structures and areas including, but not limited to, those indicated in Section 0300: Specific Site Requirements. The WORK shall include, but not be limited to, the removal and disposition of concrete slabs and foundations, miscellaneous wood, metal, stone and masonry structures, and debris associated with the abandoned mine operation or generated during construction. Clean-up of miscellaneous debris exposed at the surface and randomly located across any site has not been specifically identified due to the impracticality of such extensive identification. However, it is the intent of these Specifications to require removal and disposal of *all surface debris* associated with the abandoned mine operations. Such removal and disposal shall be included in the CONTRACTOR's scope of WORK.

#### 1.02 SUBMITTALS

- A. CONTRACTOR shall submit *with the Bid Proposal* demolition and removal procedures and schedule for approval. This should indicate if blasting is to be used in structure demolition.
- B. CONTRACTOR shall submit *after execution of the CONTRACT and prior to disposal* proof of permission for debris disposal off site at a licensed disposal site.

#### 1.03 RELATED WORK

- A. Section 0270: Site Grading and Earthwork
- B. Section 0300: Specific Site Requirements

#### 1.04 CONDITIONS AND RESTRICTIONS

- A. Demolition shall be conducted to minimize dust generation and public nuisance.
- B. CONTRACTOR shall provide, erect, and maintain temporary barriers and security devices as necessary to ensure safety of CONTRACTOR's personnel, the OWNER's personnel, and the general public.
- C. Debris burial in, mixing with, or covering by fill material is not allowed on site.
- D. Debris placement in mine openings is only allowed with site by site approval from the OWNER.
- E. Materials shall not be burned on site.

### PART 2 - PRODUCTS

CONTRACTOR may require materials for demolition and clean-up, such as wrappings or impermeable coverings not otherwise called for in other sections of these Specifications.

### PART 3 - EXECUTION

#### 3.01 PREPARATION

CONTRACTOR shall secure any and all required permits for the demolition and clean-up WORK at his or her expense.

3.02 EXECUTION

- A. CONTRACTOR shall demolish only those structures and appurtenances indicated. Demolition shall be performed in an orderly and careful manner. CONTRACTOR shall clean up and dispose of all debris exposed at the surface.
- B. Demolished materials of every nature shall become the property of the CONTRACTOR and shall be disposed of away from the site or at locations indicated in Section 0300: Specific Site Requirements or on the Drawings.
- C. Relics, antiques, artifacts and similar objects as identified by the OWNER remain the property of the OWNER. CONTRACTOR shall notify the OWNER prior to removal and obtain acceptance regarding method of removal. Relics and antiques include, but are not limited to:
  - 1. Cornerstone and contents
  - 2. Commemorative plaques
  - 3. Archaeological relics or finds
  - 4. Historical relics
- D. CONTRACTOR shall remove and promptly dispose of any contaminated, vermin-infested, or dangerous materials encountered. Transformers, oil-filled electrical equipment or other toxic materials shall be called immediately to the attention of the OWNER. Disposal of such items shall be at the direction of the OWNER in accordance with EPA and State Health requirements.
- E. CONTRACTOR shall remove foundation walls and footings to a minimum three feet below finished grade as indicated in the Drawings unless otherwise directed in Section 0300: Specific Site Requirements.
- F. CONTRACTOR shall remove all concrete slabs on grade as indicated in the Drawings unless otherwise directed in Section 0300: Specific Site Requirements.
- G. CONTRACTOR shall provide water and an adequate water supply system for dust suppression for haul roads and demolition WORK where dust will cause a public nuisance or as directed by the OWNER. The cost of water will be paid by the CONTRACTOR.
- H. Depressions resulting from demolition operations shall be filled with materials, approved by the OWNER, from on the site or from designated borrow areas unless located in an area where further excavation is required to yield the reclamation contours shown in the Drawings. The fill material shall be in accordance with Section 0270: Site Grading/Earthwork.
- I. CONTRACTOR shall grade and compact areas affected by demolition to maintain site grades and contours. In no case shall slopes exceed 3h:1v or natural site contours.
- J. CONTRACTOR shall remove demolished materials from site in an orderly fashion. CONTRACTOR shall leave site in clean condition for reclamation grading and earthwork.
- K. CONTRACTOR shall remove from site all debris created during construction.
- L. Final shape and completeness of the WORK shall be subject to approval by the OWNER.

## Section 0240

### 3.03 SALVAGING MATERIALS

All salvaged materials shall become the property of the CONTRACTOR with the exception of relics, antiques or artifacts identified by the OWNER. Salvaged materials from the structures may be stored on-site temporarily, but not beyond the date specified for completion of the CONTRACT. Any value of salvaged materials or costs associated with the removal of equipment, structures, or materials shall be reflected in the bid price amount for Demolition and Clean-up.

## PART 4 - MEASUREMENT AND PAYMENT

### 4.01 MEASUREMENT

- A. Measurement shall be per itemized structure or mine site (as specified on the bid sheet) as demolition and clean-up WORK is completed, accepted, and approved by the OWNER.
- B. The final quantities for major categorizations of materials may vary from the estimated quantities provided. The estimated quantities are based on information gathered and interpreted from surface investigations.

### 4.02 PAYMENT

Payment for the demolition and clean-up WORK shall be per itemized structure or mine site, at the BID PRICE upon approval of the OWNER for all of the WORK described in this Section.

END OF SECTION 0240

## 0250 Mine Closures

### PART 1 - GENERAL

#### 1.01 WORK INCLUDED

This section describes the various types of mine closures to be used to seal mine openings. The WORK described in this Section also includes preparation, excavation and backfilling of subsidence openings into mine voids. The requirements for furnishing and placing stone and block closures and backfill closures are described here and are indicated on the Drawings. The WORK includes all preparation, labor, materials, furnishing and placing materials, equipment and incidentals necessary to complete the mine closures.

#### 1.02 SUBMITTALS

- A. CONTRACTOR shall submit *with the bid proposal* a list of equipment to be used to complete this section of the WORK.
- B. CONTRACTOR shall submit *with the bid proposal* the proposed construction procedures in writing.
- C. CONTRACTOR shall submit *with the bid proposal* a copy of the certification of the Certified Person (see Part 1.04.E below) for approval by the OWNER.
- D. CONTRACTOR shall furnish the OWNER a set of as-built drawings upon completion of the WORK which shall be required for release of the retainage.

#### 1.03 RELATED WORK

- A. Section 0254: Polyurethane Foam Mine Closures
- B. Section 0290: Revegetation
- C. Section 0300: Specific Site Requirements

#### 1.04 JOB CONDITIONS

##### PROTECTION

- A. CONTRACTOR shall exercise precautions appropriate to working near, over, or in areas prone to subsidence. Such known areas should be flagged by the CONTRACTOR prior to the commencement of the WORK. Personnel shall be informed of special safety procedures for equipment usage and general work in these areas.
- B. Personnel shall not enter any mine opening unless under the direction of the Certified Person.
- C. No personnel shall be allowed to work under an unsupported mine roof. Temporary support shall be installed under the direction of a Certified Person qualified to determine roof conditions.
- D. Smoking or any open flame in or within 100 feet of the mine openings is prohibited.
- E. Before any personnel enter any openings a check for explosive and toxic gases shall be made by a Certified Person (a qualified person with current certification to do such WORK under the General Safety Orders of Utah Coal Mines i.e. Mine Foreman and/or Fire Boss). Continuing checks shall be made throughout the closure operation by the Certified Person.
- F. CONTRACTOR shall inspect openings for old dynamite prior to construction activities.

## Section 0250

- G. Personnel shall wear safety harnesses and be properly and securely anchored to a fixed anchor point while working within 15 feet of vertical openings, unless otherwise approved in writing by the OWNER.

## PART 2 - PRODUCTS

### A. CONCRETE BLOCK

Solid concrete block shall be high strength with a minimum compressive strength of 3,000 pounds per square inch. Hollow block used as shown on the Drawings must be concrete-filled.

### B. BACKFILL

Backfill material shall normally consist of mineral soil, subsoil, or a blend of mineral soil and subsoil. Backfill material shall be free from combustible materials. This shall include but not be limited to wood, wood products, trash and vegetation.

### C. MORTAR

Mortar shall be either Masonry Cement, 1:3 mix, Type N, or Portland Cement and Lime, 1:1:6 mix, Type N. Precautions must be taken to prepare and protect mortar during cold weather. Mortar will have a 28 day minimum compressive strength for 2-inch cubes of 700 psi.

### D. CONCRETE

Concrete shall be in accordance with Section 0251: Cast-in-Place Concrete.

### E. REINFORCEMENT

Reinforcement shall be in accordance with Section 0252: Concrete Reinforcement.

### F. FILTER CLOTH

Filter cloth shall be a non-woven geotextile fabric having a minimum thickness of 15 mil in accordance with ASTM D-1777 and a minimum permeability of  $10^{-2}$  centimeters per second, such as Fibertex 150 manufactured by Crown Zellerbach, or an approved equivalent.

### G. TEMPORARY MINE ROOF SUPPORTS

1. Mine roof supports shall be wooden posts or approved equal that have the following minimum requirements:
  - a. 4½ inch diameter.
  - b. Spruce or pine with a specific gravity between 0.35 and 0.48.
  - c. Moisture content between 10.8 and 14 percent.
  - d. Allowable unit stress of extreme fiber in bending of 750 psi for spruce or 700 psi for pine.
  - e. Maximum diameter of knots on one surface no greater than ½ inch.
2. Caps and wedges shall be used for installation of roof supports.
3. Mine roof jacks may be substituted for wooden posts with the approval of the OWNER.

## PART 3 - EXECUTION

### 3.01 PREPARATION FOR MINE CLOSURES

- A. CONTRACTOR shall clear and grub the face area of mine openings of all vegetation, wood and debris to the extent shown on the Drawings. CONTRACTOR shall inspect, scale and secure the mine openings to a degree which will make the WORK safe to perform. Particular care shall be taken to make WORK conditions safe in instances where, due to the condition of the opening and the probability of loose soil and rock above the opening, there is danger of a rockfall. For openings to be backfilled the CONTRACTOR shall excavate the brow back to a stable condition prior to initiation of closure operations, unless otherwise directed by the OWNER.
- B. The roof and ribs of the mine openings may contain loose rock. Such loose materials shall be scaled by use of tools or equipment extended into the openings before personnel enter the opening for placement of mine roof supports or for any other reason.
- C. Loose, unstable materials typically exist just inside the opening. These materials shall be removed from the working surface inside of the mine openings so a solid working surface exists on which to build the mine closures. The working surface shall be inspected, accepted and approved by the OWNER.
- D. Temporary mine roof supports shall be installed on no more than four foot centers before any personnel enter the opening for construction purposes.
- E. CONTRACTOR shall construct work pad as required.
- F. Bat Exclusion: CONTRACTOR shall exclude bats from mine workings prior to installation of permanent closures as required in these specifications. The exclusion process must be conducted during the warm season when bats are flying but before young bats are born (warm season and birthing dates vary depending on geographic location and should be specified by the bat biologist), or in the fall prior to the swarming behavior that leads to hibernation. An attempt to close mines before the warm season may entomb hibernating bats that cannot fly. The preferred method for exclusion of bats from an adit or shaft is to block the portal or shaft opening with 1-inch diameter chicken wire. The wire permits bats to escape and fly out of the mine, but they will not fly back through the wire into the mine. The wire should be placed over the entrance at least a week in advance and shall be left in place until the date of the closure. The wire should be removed during the day and closure should take place immediately.

### 3.02 INSTALLATION OF MINE CLOSURES

#### A. BLOCK WALL CLOSURE

- 1. CONTRACTOR shall construct walls in the adits as specified in Section 0300: Specific Site Requirements. Variation of the location of the walls will be allowed so that CONTRACTOR can select a suitable location for the walls, with approval of OWNER. Parameters for suitable location of the walls shall be as follows:
  - a. Select an area in which competent rock is found in the back, ribs, and sill (roof, walls, and floor) of the adit.
  - b. Utilize irregularities in the ribs and back where possible such that the wall can be "keyed" into the rock to provide more strength and integrity to the wall.

## Section 0250

- c. Locate the wall as far into the adit as is reasonable to reduce visibility of the wall from outside the opening and a maximum of 10 feet with competent brow unless otherwise approved by the OWNER. Allowance for the location of the walls is discussed in Section 0300. Where the remaining portion of the adit left open is unstable or unsafe, backfill shall be placed from the brow to the wall unless otherwise approved by the OWNER.
2. CONTRACTOR shall scale down back and ribs (roof and sides) of the adit, removing any loose rock from the area in which the wall is to be constructed and along access to bulkhead. Any mud, clay, moss or other materials shall be removed where the wall is to be constructed which would be deleterious to the integrity of the wall and would not allow good bonding of the mortar to the rock. CONTRACTOR shall excavate sill (floor) of adit to solid rock where the wall is to be constructed. Drainage shall be provided for any water that tends to accumulate on either side of the bulkhead as described in Part 3.02.A.6 of this Section. Excavated materials shall be cast into the adit behind the bulkhead to minimize surface disturbance in the area.
3. Concrete foundations shall be constructed unless competent foundation rock is encountered which is not friable, subject to deterioration, or otherwise unacceptable and the foundation rock is approved by OWNER. The foundation shall be a minimum of 18 inches in thickness and 30 inches wide to accommodate the 2-foot thick wall. The foundations shall be made of concrete as specified in Section 0251: Cast-In-Place Concrete. Concrete shall be reinforced with No. 4 rebar as shown on the Drawings and as specified in Section 0252: Concrete Reinforcement.
4. CONTRACTOR shall construct walls from foundation or solid rock base if approved by OWNER. Walls shall be constructed of concrete block, native stone, or imported stone. Concrete block walls shall be a minimum of 16 inches thick. Native stone and imported stone walls shall be constructed to a minimum thickness of 2 feet at the base and 18 inches at the top. The wall shall be free of any voids within the wall structure and shall be 100 percent rock and mortar construction. Hollow block bricks, when used, shall be concrete filled. Mortar shall be free of voids and air pockets and shall be firmly packed along ribs and roof of the opening to maintain the integrity of the wall and to make an effective seal.
5. CONTRACTOR shall use the natural shape and irregularities of the mine opening to "key" the wall to the mine opening to provide strength and protection of the wall from damage due to vandalism.
6. Designated openings shall require the installation of a drainage pipe. The drainage pipe shall be located near the base of the stone wall within 15 inches of the intersection of the floor material in the approximate center of the wall or near a low spot along the base. The drain pipe shall extend through the foundation or the base of the wall and a trap shall be formed out-by the wall near the brow as shown on the drawings. The drain pipe shall protrude a minimum of 12 inches on either side of the wall and shall be made from 6-inch nominal diameter, Schedule 80 PVC pipe. The inside end of the pipe shall be firmly supported by block or natural stone. Both the inside and outside ends of the pipes shall be clear of any obstructions which would impair or restrict flow. Both ends of the pipe shall be covered with a protective screen mesh. Gravel shall be installed over the ends of the pipes to protect the pipe from roof falls and plugging. Gravel shall form a drain and cover the top of the pipe with a minimum of 8 inches of material. The gravel drain shall be no less than 18 inches wide and shall extend to and from the end of the pipes a minimum of two feet. Gravel used in the drain channels shall be selected material ranging from 3/4 to 6 inch in size. CONTRACTOR shall extend a drainage channel away from the bulkhead if it is situated such that water could impound near the base.



7. As further protection, grout shall be used to seal the base of the bulkhead and shall be placed to partially cover the drainpipe. Grout should extend one foot to either side of the base of the wall.
8. The portal areas shall be cleared of all building materials, trash and debris. The site shall be left in a clean and finished appearance.
9. Revegetation of sites shall be completed as specified in Section 0290: Revegetation.
10. Final acceptance of the WORK shall be subject to field inspection by the OWNER.

**B. BACKFILL CLOSURE**

1. CONTRACTOR shall backfill mine openings as described in Section 0300: Specific Site Requirements or as directed by the OWNER. Backfill shall contain sufficient fines to minimize void space.
2. Drainage lines shall be extended, if required, to the projected limits of the backfill. The drain line shall be placed on a minimum slope of 2 percent and firmly bedded with well-compacted sand and gravel. The end of the pipe shall be protected as described in Part 3.03.A.7.
3. Backfill shall be placed in mine openings to minimum dimensions described and in a manner to eliminate voids. CONTRACTOR shall construct a work pad in front of the opening as required to allow for uniform access to ram the backfill into the opening utilizing a ram or backhoe bucket. Care should be taken not to push the wall out if one has been installed. Materials which require compaction shall be tamped to achieve compaction such that any additional settlement of the fill will not result in reopening of the portal.
4. Final shape of the fill shall be mounded over the opening and blended into surrounding contours as much as practical. Runoff and snowmelt shall be diverted away from and across the fill by use of small channels containing light riprap so that the fill does not erode or impound water.
5. Revegetation of sites shall be completed as specified in Section 0290: Revegetation.
6. The portal areas shall be cleared of all building materials, trash and debris. The site shall be left in a clean and finished appearance.
7. Final acceptance of the WORK shall be subject to field inspection by the OWNER.

**C. HAND BACKFILL CLOSURE METHOD**

1. Hand Backfill Closure Method shall be used only in places inaccessible to heavy equipment as designated in Section 0300: Specific Site Requirements. The backfill requirements of Section 0250: Mine Closure, Part 3.03.B apply except as provided for equipment or approved by the OWNER.
2. CONTRACTOR shall obtain backfill materials from areas specified in Section 0300: Specific Site Requirements, or as directed by the OWNER.
3. Backfill materials shall be placed in 12 inch thick horizontal lifts in the locations and to the extent shown on the Drawings.

## Section 0250

### D. WALL AND BACKFILL CLOSURE

Designated mine openings shall be backfilled after the installation of the wall. Bring backfill to the grades shown in the Drawings or as designated in Section 0300: Specific Site Requirements to blend with natural contours. Walls shall be installed per Section 0250, 3.02 A, B, and C.

### E. VERTICAL SHAFT BACKFILL CLOSURE METHOD

1. Timber and debris shall be removed from openings to the extent safely possible.
2. CONTRACTOR shall inspect the collar of the opening and determine required precautions for safe completion of WORK. Installation of a short conveyor belt or a ramp may be required.
3. Shaft shall be filled with backfill material to a height above the collar of the shaft to provide drainage away from the opening. The backfill shall be well-graded with a maximum particle size of approximately 2 feet in diameter.
4. Filter cloth shall be installed as shown on the Drawings.
5. CONTRACTOR shall place and compact the backfill starting five feet below the surface. Suitable compaction energy shall be applied in this zone in one-foot lifts by either pressure from the back of the backhoe bucket or other means accepted and approved by the OWNER. The upper five feet of backfill shall not contain any material that may have elevated sulfate concentrations.
6. The backfill shall be mounded a minimum of 24 inches above the adjacent grade, or shall be sloped at 3h:1v and extend a minimum 3 feet horizontal distance beyond the edge of the shaft.

## 3.03 MINE CLOSURE GRADING

- A. CONTRACTOR shall bring backfill to the grades shown on the Drawings or to blend with natural contours. Backfill shall be free of voids and shall be compacted by mechanized equipment or hand-held mechanical compactors in one foot lifts.
- B. CONTRACTOR shall extend the drainage line (if required) to the projected limits of the backfill. The drain line shall be placed at a minimum slope of 2 percent and firmly bedded with well compacted sand and gravel. The end of the pipe shall be protected as described in Part 3.03.A.7.
- C. The backfilled slopes shall be covered with a minimum of 6 inches of soil/rock fill available on site from areas designated by the OWNER.
- D. Revegetation and mulching of the disturbed areas shall be performed in accordance with Section 0290: Revegetation.
- E. Final shape and completeness of the WORK shall be subject to approval by the OWNER.

### 3.04 MINE LOCATION MONUMENTS

- A. CONTRACTOR shall install at each mine closure a permanent monument (aluminum survey cap). OWNER will provide and CONTRACTOR will install the survey cap.
- B. At backfill closures, monuments shall be installed on rebar stakes. Stakes shall be #5 (5/8-inch diameter) rebar, normally 3 to 4 feet long. The rebar shall be securely anchored in the ground with the end extending above the final grade 2 to 6 inches. CONTRACTOR may opt to use soil plates, deadmen, bends, or other devices to ensure that the rebar is securely anchored. The exposed end of the rebar shall be squarely cut and free of bends, flaring, mushrooming, or burrs that would prevent proper seating of the survey cap. Seating of the cap onto the rebar shall be done taking precautions not to mar the text. Where site conditions permit and with approval of OWNER, monuments may be set directly into bedrock with epoxy resin as described below.
- C. At structural closures (bulkheads or steel grates), monuments may be set in concrete footers, grade beams, or seams while the concrete is wet or set in bedrock with epoxy resin. Installation in bedrock requires drilling a 1¼-inch diameter by 2 inch deep hole to receive the cap.
- D. The placement of the monument will be determined by the OWNER, but typically it will be centered in or adjacent to the mine opening for backfill closures. Monuments should not be placed where it is necessary to climb onto the closures to read them. Monument positioning should consider the potential for vandalism and the potential for siltation that could bury the cap. Monuments may be installed in by grate closures, but not so deep that they cannot be easily read.

## PART 4 - MEASUREMENT AND PAYMENT

### 4.01 BASIS OF PAYMENT

Basis of payment for the WORK will be on the BID PRICE per opening for completion of all the WORK as described in this Section. Breakdown of the WORK into unit prices for individual mine openings shown in the Bid Schedule will be used in determining partial payment or adjustment of the total BID PRICE for this Section as the WORK progresses.

### 4.02 MEASUREMENT

Measurement for mine closures will be on the BID PRICE per mine opening. Measurement will be based on and compared to the dimensions and quantities identified on the bid sheets, these Specifications and Drawings. The OWNER will request intermediate measurements to determine progress of the WORK.

### 4.03 PAYMENT

- A. Payment for mine closures will be for each mine site at the BID PRICE. Payment will only be for those closures which are complete, accepted, and approved by the OWNER. No partial payments will be made for individual mine openings.
- B. Payment at the UNIT PRICE for additional quantities will be made for mine closures when final quantities are greater than 15 percent in excess of the estimated quantities shown on the bid sheet for a given mine site. Such unit price payment will require proof of additional quantities provided by the CONTRACTOR and approval of the OWNER, and shall be full compensation for the approved additional masonry or backfilling. Reduction of payment for lesser quantities of masonry or backfill will also be made by the OWNER for quantities greater than 15 percent

## Section 0250

below the estimated quantity shown on the bid sheet for a given mine. Such UNIT PRICE adjustment will require approval of the OWNER and will be full compensation for approved additional or reduced mine closure quantities.

END OF SECTION 0250

## 0254 Polyurethane Foam Mine Closures

### PART 1 - GENERAL

#### 1.01 DESCRIPTION

The polyurethane foam (PUF) closure of adits consists of installing a bulkhead form, installing PUF to specifications, and backfilling over the PUF with random fill. In shafts, the closure work consists of installing a bottom form, installing PUF to specifications, installing drainage material, topping the PUF with a layer of concrete, and backfilling over the PUF to the specified level with random fill. For shafts, one ventilation/drainage pipe is required. Refer to the drawings for construction details.

#### 1.02 SUBMITTALS

CONTRACTOR shall submit *with the bid proposal* the proposed construction procedures, including a description of the form materials to be used and the foam application equipment or method.

#### 1.03 RELATED WORK

- A. Section 0250: Mine Closures
- B. Section 0300: Specific Site Requirements

### PART 2 - PRODUCTS

#### MATERIALS

##### A. FORMWORK

1. The forms and cross members may consist of any commonly available building materials capable of sustaining the initial lift of two to four feet of PUF. Examples of acceptable forms and cross members include but are not limited to, the following:

##### CROSS-MEMBER & BOTTOM FORM

- Rebar & Plywood
- 2x4s & Cardboard or Chicken Wire
- Dowels & Paneling
- Cardboard Tubes & Carpeting
- Blocks of PUF (generated onsite)
- Waterbed Mattresses (inflated remotely in the shaft with a hose and air compressor)

2. Any combination of the above noted materials that achieves the required performance will be acceptable. Alternate bottom forms will be acceptable upon approval by the OWNER.
3. Any breach in the bottom form caused by vandals or rock fall is required to be repaired before the arrival of the PUF applicators to the site. The CONTRACTOR is responsible for the integrity of the bottom form, and the loss of any polyurethane should it fail.

##### B. POLYURETHANE FOAM (PUF)

PUF is required to have a minimum installed density of 1.85 pounds per cubic foot (pcf). PUF characteristics shall conform to the minimum following standards:

PUF CHARACTERISTIC	STANDARD	SPECIFIED IN
Density	1.85 pcf, nominal	
Closed cell content	90%	ASTM D-2856
Compressive strength	25 psi	ASTM D-1621
Water absorption	1% by volume	ASTM D-2127
Exothermic Reaction Rate	Low	
Fire Resistance	Low	ASTM D-1692

Polyurethane foam used may not contain any CFC's (chlorinated fluorocarbons).

C. PROPORTIONING UNIT

1. The proportioning unit shall be capable of attaining a minimum temperature of 125°F. The proportioning unit shall be Gusmer Model H-11 or equivalent. For remote sites, or with approval of the OWNER, smaller capacity proportioners will be acceptable. In this event, the proportioner shall be the Gusmer FF, or equivalent.
2. Minimum heated hose length from proportioner to gun shall be 80 feet. The hose shall maintain or increase component temperature from the proportioner. Longer heated hose lengths may be required depending upon distance from the proportioning unit to the reclamation site.

D. APPLICATION GUN

The application gun shall be capable of mixing plural components in the proper ratio at the minimum acceptable output of four pounds per minute. The gun shall be a Gusmer AR mechanically self-cleaning design, or equivalent.

E. PREPACKAGED, PRE-PROPORTIONED PUF KITS

PUF products consisting of factory prepared kits that are designed to combine and dispense pre-measured quantities of components in the proper ratios may be used in place of an onsite proportioning unit and application gun, with the approval of OWNER. One such product is the foam closure bag manufactured by Foam Concepts Inc. (see Part 2.01.J below). PUF kits shall be used according to the manufacturer's specifications.

F. CEMENT PLUG

Concrete for the cement plug shall have a minimum compressive strength of 3,000 psi in 28 days. The concrete shall be proportioned in accordance with ACI 211. The type of cement used shall be Portland, Type II (ASTM C150). Air entrainment shall be furnished in all concrete. Air content shall be 5%± 1%. Water/cement (W/C) ratio is approximately 0.49 with minimum cement content of 564 lbs/CY. Concrete mixed at the jobsite shall be in accordance with ACI

301, chapter 7. Ready mix concrete shall be in accordance with ASTM C94.

G. FILTER CLOTH

The filter cloth, either woven or non-woven at the CONTRACTOR's option, shall have a minimum thickness of 15 mil in accordance with ASTM D-1777 and a minimum permeability of  $10^{-2}$  cm/sec, such as Fibertex 150® manufactured by Crown Zellerbach or equivalent approved by OWNER. Prior to installation, the CONTRACTOR shall provide the OWNER with documentation that the filter cloth furnished meets the chemical, physical and manufacturing requirements of this Section.

H. VENTILATION/DRAIN PIPE

The ventilation/drain pipe shall consist of 2-inch diameter steel pipe.

I. RANDOM FILL MATERIAL

Random fill material shall consist of native, on-site soils and sandstone rock. The types of miscellaneous fill material to be used shall be approved by the OWNER prior to initiating the work.

J. SUPPLIERS OF PUF

Potential suppliers of polyurethane foam (PUF) are:

Foam Concepts, Inc.  
309 NE 9th Ave  
Grand Rapids, MN 55744  
(800) 556-9641  
(218) 327-1196 FAX  
E-mail: [sales@foamconceptsinc.com](mailto:sales@foamconceptsinc.com)  
<http://www.foamconceptsinc.com>

Progressive Marketing Group  
1906 Highway 71 North  
P.O. Box 860  
Okoboji, Iowa 51355  
(712) 332-9013  
(800) 373-2593  
(712) 332-9653 FAX  
(800) 398-2762 FAX  
(800) 806-1171 Dennis Gustafson  
E-mail: [pmgroup@rconnect.com](mailto:pmgroup@rconnect.com)  
Vendor of Equipmentless Foam Sealant™

## Section 0254

Utah Foam Products  
Ernest Wilson Co.  
3609 South 700 West  
Salt Lake City, Utah 84119  
Contact: Dennis Beckstead  
(801) 269-0600 Utah Foam Products  
(801) 265-9444 Ernest Wilson Co.  
(801) 269-0620 FAX  
E-mail: [info@utahfoam.com](mailto:info@utahfoam.com)  
UFP is a supplier of raw materials. EWC is the contracting arm of the company.

Ron Walker  
Azco Construction  
2055 West US Highway 50 East  
Penrose, Colorado 81240-9575  
(719) 372-6872  
General contractor with PUF equipment

A Urethane Service and Supply  
2200 West 2300 South  
West Valley City, Utah 84119  
(801) 974-0995  
(801) 974-3058 FAX  
E-mail: [urethane@qwest.net](mailto:urethane@qwest.net)  
Roofing contractor

T&W Wilson Spray Urethane  
7200 South 2700 West  
West Jordan, Utah 84084  
Contact: Terry Wilson  
(801) 566-1020  
(801) 566-6620 FAX  
Roofing contractor

Mine Seal, LLC  
P.O. Box 231329  
Las Vegas, NV 89123  
(888) 732-5783  
(888) 531-6883 FAX  
Mine Closure Consulting Firm  
[www.mine-seal.com](http://www.mine-seal.com)

Most roofing contractors that apply PUF roofing should be capable of providing the appropriate product for mine closure use.

These names are provided for the convenience of bidders. Other vendors may exist. The Utah Abandoned Mine Reclamation Program does not endorse or warrant the reliability or product of any of these vendors.

## PART 3 - SAFETY



### 3.01 MATERIALS

- A. Materials shall be stored per the manufacturer's specifications. All safety precautions outlined by the Polyurethane Division of the Society of Plastics Industries, NFPA, OSHA, EPA and the manufacturer's Material Safety Data Sheets (MSDS) shall be observed. MSDS and technical data sheets shall be on-site and available at all times.
- B. There shall be no welding, smoking or open flame within 100 feet of PUF application. A minimum 15-pound, class ABC fire extinguisher must be on site at the mine opening where the PUF is being applied during foam application.
- C. Oxygen Content of Working Area
  - 1. A flame safety lamp or oxygen meter must be used to test air before and during installation of the bottom forms. The flame safety lamp or oxygen meter will be supplied by the CONTRACTOR and operated only by the Certified Person. Refer to Section 0250, Part 1.04.
  - 2. Oxygen Meter. The oxygen meter shall be a National Mine Service (NMS) OX231 oxygen meter or equivalent. The oxygen meter shall continuously monitor oxygen levels and have an audible warning. If the oxygen content falls below 19%, all personnel must withdraw from the working area in the mine until the oxygen content increases to safe levels.
  - 3. Flame Safety Lamp. The flame safety lamp shall be lowered to the intended level of the bottom form from the surface. If the flame safety lamp is extinguished upon withdrawal then the mine may not be entered until the oxygen level increases. The flame safety lamp shall accompany the bottom form installer during the time in the mine. If the quality and/or intensity of the flame decreases, then the installer must withdraw from the working area until the oxygen content increases.
  - 4. Any remedy for increasing oxygen content of the working area and/or providing ventilation from the surface must be determined in consultation with the OWNER and the Certified Person.

### 3.02 HANDLING

PUF shall be applied by workers wearing organic respirator masks and safety glasses or goggles. State or Federal regulations requiring additional equipment shall supersede these specifications.

### 3.03 TRANSPORT

The CONTRACTOR shall follow all applicable State and local regulations for transport and use of PUF and chemicals required for cleanup. The CONTRACTOR shall also obtain any necessary permits for transportation. The CONTRACTOR shall be aware of agencies and jurisdictions requiring notification in the event of a component leak or spill. In the event of a leak or spill, the CONTRACTOR shall notify the appropriate parties.

## PART 4 - EXECUTION

### 4.01 SHAFT CLOSURE INSTALLATION

A. CLEARING DEBRIS

Clear debris other than fixed, attached or permanent structures from the shaft before PUF is installed *as directed by the OWNER*. Historic structural features shall be preserved and maintained. Any historic debris removed shall be placed neatly to the side of the opening.

B. FORMWORK

1. The formwork shall be installed below the surface of the shaft at the bottom of the foam depth level. The depth of foam required to plug a shaft shall be determined by the following formulas, where “a” is the smaller dimension of a rectangular shaft opening and “b” is the larger dimension, with both “a” and “b” measured in feet:
  - a. for shafts where  $a = b$ , the depth of foam should be:  $2a$ .
  - b. for shafts where  $a < b < 3a$ , the depth of foam should be:  $2a + \frac{1}{2}(b-a)$
  - c. for shafts where  $b > 3a$ , the depth of foam should be:  $3a$ .
2. Cross-member supports may be placed at an angle not more than 20 degrees from horizontal as long as both ends are seated in the shaft. The bottom form shall be set over the cross-members.
3. Bottom forms shall be completed prior to application of any polyurethane foam. The installed depth to bottom form shall be indicated on the as-built drawings for polyurethane foam closures. Any breach in the bottom form caused by vandals or rock fall shall be repaired prior to arrival of PUF applicators at that site. The CONTRACTOR is responsible for the integrity of the bottom form, and the loss of any polyurethane should it fail.

C. VENTILATION/DRAIN PIPE

1. The ventilation/drain pipe shall be placed over a portion of the bottom form unobstructed by cross-members. The ventilation/drain pipe shall be open to the shaft after installation of the foam. The ventilation/drain pipe shall be supported by a tripod or other load-bearing device such that the load is not placed on the bottom form.
2. The 2-inch steel ventilation/drain pipe shall be installed into the approximate center of the PUF installation and shall extend vertically to the lines and grades as shown on the Standard Drawings.
3. The steel ventilation/drain pipe shall extend up through the entire PUF and concrete plug installation to provide ventilation and a watercourse through the entire structure. The 2-inch steel pipe shall be cut off level at the top of the concrete plug.

D. POLYURETHANE FOAM (PUF)

1. PUF shall be applied in lifts with a maximum rise of 1.5 feet. Installed PUF lifts shall pass through the tack free stage before applying the next lift. At no time shall sprayed or poured PUF cut into rising foam. The PUF shall be applied in such a manner that the entire void is filled, and that shadow zones or voids are not created during PUF application, and does not raise the temperature to unsafe levels. At the discretion of the OWNER, thermocouples may be used to monitor exothermic generation. PUF application shall cease if heating or

off-ratio foam is observed. The CONTRACTOR shall remedy off-ratio foam and demonstrate proper quality PUF to the OWNER before application resumes. See Part 5 below for characteristics of off-ratio foam.

2. The surface of the void to be filled shall be as free as possible of grease and standing water. PUF shall not be applied to surfaces with running water. Remedial action for such situations shall be specified by the OWNER. Polyurethane foam shall not be applied directly to a debris plug, but must be applied to a bottom form of known physical and chemical properties. PUF shall not be applied during rain unless the foam is protected from interaction with water by a physical barrier.
3. If off-ratio PUF is observed, the applicator must stop, correct the imbalance and continue application with the proper ratio PUF. Correction and determination of the foam ratio shall be done on a plastic sheet away from the work area. Any lift of off-ratio PUF comprising over two percent (2%) of the intended PUF column height shall be removed. An amount of off-ratio PUF less than two percent (2%) of the specified volume may remain if allowed to cool, and if the outer perimeter of off-ratio foam is removed.
4. The CONTRACTOR shall be responsible for any lost or damaged equipment. In addition, damages or claims arising from PUF overspray shall be the responsibility of the CONTRACTOR. Under no circumstances shall foreign material be placed in the PUF unless specifically authorized by the OWNER. Non-PUF materials must be non-toxic, non-hazardous and not compromise the strength or water saturation characteristics of the PUF.
5. Upon reaching the specified grade as shown on the Standard Drawings, the CONTRACTOR shall clean up PUF operations and wait a minimum of one hour before initiating construction of the concrete plug.

#### E. CONCRETE PLUG

1. The concrete plug shall be placed directly on top of the polyurethane foam (PUF) as shown on the Standard Drawings and be one foot thick, covering the entire width of the opening. There shall be complete contact along the entire perimeter of the plug with the opening walls.
2. The CONTRACTOR shall determine the means of concrete plug placement and submit it to the OWNER for approval prior to the start of construction.
3. The top of the concrete plug shall be reasonably smooth and completed to provide drainage to the 2-inch steel ventilation/drain pipe.
4. Placement of backfill on top of the concrete plug will not be allowed until the structure has cured for a minimum of 24 hours.

#### F. FILTER CLOTH

1. The geotextile filter cloth shall be placed in all required structures in a manner acceptable to the OWNER.
2. Fabric shall be rejected at the time of installation if it has defects, rips, holes, flaws, deterioration or damage incurred during manufacture, transportation or storage. Fabric damaged before or during the installation shall be replaced at the CONTRACTOR's

expense.

3. The fabric shall be placed without stretching and shall lie smoothly in contact with the concrete plug surface. Each strip shall be continuous in width with no joints. The fabric shall be placed with overlapping seams perpendicular to the long axis of the opening. When end overlapping of strips is necessary, the joints shall be overlapped a minimum of two feet. End overlaps shall be made in the direction of the long axis of the opening. The work shall be scheduled so that not more than one day elapses between the placement of the fabric and the time it is covered with the specified material.
4. The filter cloth shall be installed over the top of the concrete plug and 2-inch PVC ventilation/drain pipe so that free drainage is possible.

G. RANDOM FILL MATERIAL

1. Random fill material shall consist of on-site, native materials as approved by the OWNER. Fill material shall be placed to the thickness shown on the Standard Drawings.
2. Materials for random fill material shall be placed by methods to produce a uniform mass. The first two-foot lift shall be placed by hand or bucket to lower the velocity of impact against the concrete plug. The final surface of the backfilled opening shall be mounded a minimum of one foot above the original ground. Care should be taken not to plug the drain pipe with fill material.

H. SITE CLEAN-UP

All construction-generated trash and debris, such as scrap materials and spilled PUF or concrete, shall be cleaned up and removed. CONTRACTOR shall avoid spraying foam at undesignated targets. Improperly applied PUF and overspray shall be removed.

I. MODIFIED PUF CLOSURE (TYPE B— RECESSED SURFACED)

The standard PUF closure design is modified for shafts designated as historically significant. For these openings, the top surface of the random fill material shall be recessed inside the shaft opening to within three feet of the adjacent ground surface. The minimum thickness of the random fill layer shall be two feet. The positions of the bottom form, PUF, and concrete are lowered accordingly. The intent of the recessed fill is to maintain the original appearance of the opening while still eliminating a serious fall hazard. Shafts designated as historically significant and requiring a recessed closure are listed in Section 0300: Specific Site Requirements and/or the appendices.

4.02 ADIT PUF CLOSURE INSTALLATION

A. CLEARING DEBRIS

Clear debris other than fixed, attached, or permanent structures from the adit before PUF is installed *as directed by the OWNER*. Historic structural features shall be preserved and maintained. Any historic debris removed shall be placed neatly to the side of the opening.

## B. FORMWORK

1. The formwork shall be installed in by the brow of the adit to allow for a minimum foam thickness of two feet.
2. Cross-member supports may be placed at an angle not more than 20 degrees from vertical as long as both ends are seated in the adit.
3. Forms shall be completed prior to application of any polyurethane foam. The installed depth to form shall be indicated on the as-built drawing for polyurethane foam closures. Any breach in the form caused by vandals or rock fall shall be repaired prior to arrival of PUF applicators at that site. The CONTRACTOR is responsible for the integrity of the form, and the loss of any polyurethane should it fail.

## C. VENTILATION/DRAIN PIPE

Designated openings shall require the installation of a drainage pipe. The drainpipe shall be located near the base of the closure within 15 inches of the intersection of the floor material in the approximate center of the closure or near a low spot along the base. The drainpipe shall extend through the base of the closure. The drainpipe shall protrude a minimum of 12 inches on either side of the seal and shall be made from 6-inch nominal diameter steel pipe. The inside end of the pipe shall be firmly supported by block or natural stone. Both the inside and outside ends of the pipe shall be clear of any obstructions which would impair or restrict flow. Both ends of the pipe shall be covered with a protective screen mesh. Gravel shall be installed over the ends of the pipes to protect the pipe from roof falls and plugging. Gravel shall form a drain and cover the top of the pipe with a minimum of 8 inches of material. The gravel drain shall be no less than 18 inches wide and shall extend to and from the end of the pipes a minimum of two feet. Gravel used in the drain channels shall be selected material ranging from 3/4 to 6 inch in size. CONTRACTOR shall extend a drainage channel away from the bulkhead if it is situated such that water could impound near the base.

## D. POLYURETHANE FOAM (PUF)

1. PUF shall be applied in lifts with a maximum rise of 1.5 feet. Installed PUF lifts shall pass through the tack-free stage before applying the next lift. At no time shall sprayed or poured PUF cut into rising foam. The PUF shall be applied in such a manner that the entire void is filled, and that shadow zones or voids are not created during PUF application, and does not raise the temperature to unsafe levels. At the discretion of the OWNER, thermocouples may be used to monitor exothermic generation. PUF application shall cease if heating or off-ratio foam is observed. The CONTRACTOR shall remedy off-ratio foam and demonstrate proper quality PUF to the OWNER before application resumes. See Part 5 below for characteristics of off-ratio foam.
2. The surface of the void to be filled shall be as free as possible of grease and standing water. PUF shall not be applied to surfaces with running water. Remedial action for such situations shall be specified by the OWNER. Polyurethane foam shall not be applied directly to a debris plug, but must be applied to a form of known physical and chemical properties. PUF shall not be applied during rain unless the foam is protected from interaction with water by a physical barrier.
3. If off-ratio PUF is observed, the applicator must stop, correct the imbalance, and continue

## Section 0254

application with the proper ratio PUF. Correction and determination of the foam ratio shall be done on a plastic sheet away from the work area. Any lift of off-ratio PUF comprising over two percent (2%) of the intended PUF column height shall be removed. An amount of off-ratio PUF less than two percent (2%) of the specified volume may remain if allowed to cool, and if the outer perimeter of off-ratio foam is removed.

4. The CONTRACTOR shall be responsible for any lost or damaged equipment. In addition, damages or claims arising from PUF overspray shall be the responsibility of the CONTRACTOR. Under no circumstances shall foreign material be placed in the PUF unless specifically authorized by the OWNER. Non-PUF materials must be non-toxic, non-hazardous and not compromise the strength or water saturation characteristics of the PUF.
5. Upon reaching the specified grade as shown on the Standard Drawing, the CONTRACTOR shall clean up PUF operations and wait a minimum of one hour before initiating construction of the concrete plug.

### E. RANDOM FILL MATERIAL

1. Random fill material shall consist of on-site, native materials as approved by the OWNER. Fill material shall be placed to a minimum thickness of three feet.
2. Materials for random fill material shall be placed by methods to produce a uniform mass. The material may be placed by hand or equipment. The final surface of the backfilled opening shall be graded to blend with the surrounding contour.

### F. SITE CLEAN-UP

All construction-generated trash and debris, such as scrap materials and spilled PUF shall be cleaned up and removed. CONTRACTOR shall avoid spraying foam at undesignated targets. Improperly applied PUF and overspray shall be removed.

## PART 5 - FIELD QUALITY CONTROL

### INSPECTIONS

- A. Periodic checks of the quality of PUF applied shall be made by the OWNER. The main check on quality will be visual. Acceptable PUF shall be tan-white to buff in color with no vesicles and a smooth to coarse orange peel surface. Any one of the following conditions shall cause PUF application to cease, and efforts to correct the off-ratio condition begin.

CONDITION	POSSIBLE CAUSE
Dark PUF Color Smooth and Glassy Friable or Brittle PUF Improper Density	Excess A Component
Light to White in Color Bad Cell Structure Mottled Appearance Blowholes or Pinholes	Excess B Component

Slow rise Poor Cell Structure Frequent Equipment Clogging Slow Curing Bad Physical Properties	Bad Material
---	--------------

- B. At any time during PUF application, the OWNER may call for a density test. The applicator shall fill a container provided by the OWNER for this purpose, and the sample will be tested for density. The density of the sample shall be within eight percent (8%) of the nominal 2 pounds per cubic foot density, with a minimum installed density of 1.85 pounds per cubic foot. Density tests indicating PUF installed is not within the minimum specified density shall cause corrective action resulting in PUF within the acceptable nominal range, less deviation due to barometric pressure changes from STP (Standard Temperature and Pressure).
- C. Density tests of PUF shall be conducted at no cost to the OWNER. At the discretion of the OWNER, density tests showing PUF in the acceptable range may be taken in the center of the cavity to which PUF is being applied. A sampling box constructed of sheet aluminum and lined with polyethylene may be lowered into the cavity to take a representative sample of PUF just above the level of installed polyurethane.

## PART 6 - MEASUREMENT AND PAYMENT

### 6.01 SPECIAL CONSIDERATIONS

- A. The CONTRACTOR's attention is specifically directed to the following.
- B. The final quantities for the major categorizations of materials may vary from the quantities shown on the site-specific summary sheets in Appendix B. The quantities estimated are based on information gathered and interpreted from surface investigations.
- C. The boundaries of classified materials, along with the volumes are estimates and intended to serve as a guide in outlining the scope of work and evaluating the bids.

### 6.02 QUANTITY MEASUREMENTS

- A. Polyurethane foam closures will be paid for at the contract Bid Price per each closure completed. Payment at the Bid Price shall be full compensation for furnishing, placing all materials, including all labor, equipment, tool, and incidentals necessary to complete closure installation in accordance with the Standard Drawings and Specifications.
- B. Installation of PUF, fabrication of the concrete plug, placement of filter cloth and ventilation/drain pipes, backfill, revegetation, and cleanup will not be measured for direct payment but will be considered subsidiary to PUF closures.
- C. No payment shall be made for off-ratio PUF.

END OF SECTION 0254

## 0270 Site Grading/Earthwork

### PART 1 - GENERAL

#### 1.01 WORK INCLUDED

This section covers the WORK necessary for general earthwork and site grading. The principal items of WORK include, but are not limited to, grading and/or burial of mine dumps, placement of soil material over mine dumps, transportation and placement of mine dump material, installation of riprap ditches and placement of soil materials.

#### 1.02 SUBMITTALS

- A. CONTRACTOR shall submit *with the bid proposal* a list of equipment to be used to complete this section of the WORK.
- B. CONTRACTOR shall submit *with the bid proposal* locations of borrow areas for fill and topsoil for the approval of the OWNER when such areas are not shown on the Drawings.

#### 1.03 RELATED WORK

- A. Section 0250: Mine Closures
- B. Section 0290: Revegetation
- C. Section 0300: Specific Site Requirements

#### 1.04 PROTECTION

CONTRACTOR shall conduct grading and earthwork operations in a fashion to minimize erosion during and after construction. This shall include limiting disturbance of existing vegetation, working equipment parallel to contours, use of temporary drainage control where appropriate, and other practices as directed by the OWNER. Drainage and irrigation ditches shall be kept clear.

### PART 2 - PRODUCTS

#### MATERIAL DEFINITIONS

##### A. VEGETATION

Naturally occurring plant growth including: trees, shrubs, grasses, weeds, sagebrush, etc.

##### B. TOPSOIL

Mineral soils, with organic matter, free of large roots, rocks, debris, and large weeds, obtained from the areas and to the maximum depths specified on the Drawings.

##### C. SUBSOIL

Mineral soils, free of organic matter and excessive amounts of construction debris and rubble, naturally or artificially (fill) occurring between topsoil and bedrock, including rocks and boulders.

##### D. MINE DUMP MATERIAL

Material produced in the process of mining, generally found on the site in waste piles and spread over subsoils and fill in thin veneers. The dump material typically consists of overburden materials, ore and fines, and intermixed subsoils. Material size ranges from silts and sands to rock greater than 18 inches in diameter.



E. RANDOM FILL

Artificially placed material consisting of mine dump material, excavated subsoils and unclassified materials. Material for use as random fill shall be free of wood, roots, weeds, construction debris, and other combustible materials. Random fill shall not contain material sizes or gradations which preclude compaction.

F. UNCLASSIFIED EXCAVATION

As described by these Specifications, excavation is unclassified and includes in-situ soils as well as buried rubble and construction debris. It is not the intent of these Specifications to require the excavation of bedrock. Should bedrock be encountered, the OWNER shall be immediately notified so that field adjustments to the reclamation contours as shown in the Drawings can be made.

G. SOIL/ROCK FILL

Locally available material consisting of organic-free rock and coarse soils. Materials for use as soil/rock fill shall be designated on site by the OWNER.

PART 3 - EXECUTION3.01 STRIP VEGETATION

WORK shall consist of removing vegetation, roots, and surficial debris from areas of reclamation as directed by the OWNER. The resulting debris shall be disposed of off-site, or may be buried on-site in an area approved by the OWNER. However, in no case may combustible materials be buried or otherwise placed in coal refuse\*\*\*.

3.02 SITE GRADINGA. GENERAL

The intent of this WORK is to develop the reclaimed contours shown in the Drawings and to establish favorable drainage conditions and erosion protection at all sites. Random fill shall be placed directly to meet the specified reclamation surface contours. Lines and grades as defined on the Drawings are subject to modification, dependent on the field conditions encountered. Unless identified on the Drawings or Specifications, the lower limit of excavation shall be the top of competent bedrock. The steepest allowable slope of reclaimed areas shall be 3:1, unless otherwise stated in these Specifications or shown on the Drawings. Site grading shall be performed to provide a reclamation area which blends well with natural conditions in adjacent areas.

B. DRAINAGE GRADING

1. At the location of each mine opening, CONTRACTOR shall grade the existing topography to allow surface water to drain freely away from the mine closure. Efforts shall be made to minimize the extent of this grading and limit the disturbance of existing vegetation.
2. Regraded surfaces for waste dump reclamation, burial of mine dump material, and reshaping of drainage channels shall be sloped to drain freely and shall include water bars, intermediate benches, and other such devices as shown on the Drawings to control

precipitation runoff and prevent erosion.

C. STRIP MINE DUMP MATERIAL TO MINERAL SOILS

In the areas designated on the Drawings, CONTRACTOR shall strip existing mine dump material to sufficient depth to expose natural soils. Refuse from these areas shall be utilized as fill for site grading. Stripping depths shown are approximate only, and all mine dump material present shall be removed from the area. After mine dump material removal, soils within the stripped area shall be regraded to approximate the reclamation contours shown on the Drawings. CONTRACTOR shall not be required to import fill to the stripped area to create the contours shown.

D. EXCAVATION

CONTRACTOR shall excavate to the lines and grades shown on the Drawings or as directed by the OWNER. Excavated materials conforming to the definition of random fill, including subsoils, mine dump material, and unclassified materials, shall be placed directly as fill in designated fill areas. Concrete and other inert materials may be buried at depth greater than 36 inches with the approval of the OWNER. CONTRACTOR shall be responsible for all surveying necessary to perform the WORK and determine pay quantities. CONTRACTOR shall confirm that the survey base used is consistent with the plans provided by the OWNER. The OWNER shall have surveys performed at its discretion for confirmation purposes.

E. FILL

Where fill is required, CONTRACTOR shall use excavated material acceptable as either random fill or soil/rock fill. Rocks and boulders greater than 12 inches in diameter shall be removed for use as riprap, buried in fill in accordance with grading tolerances below, or left on finished grade either singly or in groupings to blend with the natural surroundings. Construction debris may be incorporated in the fill providing such materials are properly broken down and placed in such a manner that no open voids exist. The placement of debris in the fill shall be subject to the approval of the OWNER. The distribution of materials throughout a fill shall be such that there shall be no lenses, pockets, streaks or layers of material differing substantially in texture and gradation from the surrounding material in the fill. Fill materials to be compacted with hauled or self-propelled compactors shall be placed and spread in horizontal lifts not exceeding 24 inches loose measure. Fill materials to be compacted by hand-guided or hand-operated equipment shall be placed and spread in horizontal lifts not exceeding 12 inches loose measure.

F. FILL COMPACTION

Each lift of material placed as fill shall be compacted by a minimum three (3) passes of a compactor exerting a minimum pressure of one hundred (100) pounds per square inch or as specified in Section 0300: Specific Site Requirements. Water shall be used as necessary in the compaction operation for dust control and to achieve the required compaction.

G. GRADING TOLERANCES

1. The reclaimed surface shall be constructed to produce the contours shown on the Drawings within a tolerance of plus or minus one foot. Where field conditions warrant a modification in the grading plan, top of subgrade shall be as directed by the OWNER. The top two feet of the subgrade shall consist only of clean subsoils or \*\*\*coal refuse which have been cleaned of cobbles and boulders exceeding twelve (12) inches in diameter.
2. Abrupt changes in grade shall be rounded to provide a pleasant visual effect.

3. Depressed areas shall be graded to prevent ponding or standing water.

#### H. SCARIFICATION

Scarification or discing shall be completed when the veneer of \*\*\*coal refuse is generally less than 6 inches thick. Scarification shall be accomplished with a tractor or bulldozer-hauled scarifier or disc-harrow. Where inaccessibility precludes the use of hauled equipment, scarification shall be completed manually with hoes and mattocks.

#### I. TOPSOIL PLACEMENT

1. Areas to be covered with topsoil shall be scarified to a minimum depth of 4 inches.
2. Following completion of regrading and earthwork to the contours required by these specifications, designated disturbed areas shall be covered with topsoil placed to a minimum thickness of 12 inches unless otherwise directed by the OWNER. On slopes of 3:1 or flatter, topsoil materials shall be compacted in the same manner as fill material. On slopes steeper than 3:1, the top-soil surface shall be stabilized by means of erosion control blanket, vegetation, riprap, or as otherwise directed by the OWNER. The topsoil shall be obtained only from the borrow areas shown and to the maximum depths specified on the Drawings.

#### J. DEBRIS BURIAL

Construction debris may be incorporated in fill providing such materials are properly broken down and placed in such a manner that no open voids exist. The placement of debris in fill shall at all times be subject to the approval of the OWNER.

### PART 4 - MEASUREMENT AND PAYMENT

#### 4.01 MEASUREMENT

- A. Measurement will be based on and compared to the dimensions and quantities identified in the bid sheets, these Specifications and Drawings. The OWNER may request intermediate measurements to determine progress of the WORK.
- B. Measurements of cubic yards of Earthwork will be required for each mine site. Such measurement shall be used by the OWNER for comparison with the estimated quantity shown on the bid sheets.
- C. CONTRACTOR shall complete surveys before and after any site grading or earthwork as directed by OWNER. Volume of material removed or placed shall be calculated by the average-end-area method based on cross-sections developed from CONTRACTOR'S surveys. The OWNER will have surveys performed at OWNER's discretion for confirmation purposes.
- D. Should the CONTRACTOR estimate the cubic yards of materials to be greater than 15% more than the quantities shown in the Bid Schedule, a CHANGE ORDER must be negotiated with the OWNER for ADDITIONAL WORK prior to the CONTRACTOR undertaking ADDITIONAL WORK. Measurement for quantities shall be determined prior to the WORK.
- E. When the actual quantity of Site Grading/Earthwork performed as determined by measurement is greater than 15% less than the estimated quantity on the bid sheet, the OWNER will negotiate

## Section 0270

a reduction in the BID PRICE by the amount of variance using the UNIT PRICE. This adjustment shall be executed by a CHANGE ORDER.

### 4.02 PAYMENTS

- A. Payment for Site Grading/Earthwork will be for each mine site at the BID PRICE, as modified by any CHANGE ORDERS. Payment shall be authorized by the OWNER only for completed Site Grading/Earthwork. No partial payments shall be made.
- B. Payment at the UNIT PRICE for additional quantities of Site Grading/Earthwork will be made for quantities greater than 15 percent in excess of the estimated quantity shown on the bid sheet for a given mine site. Reduction of payment for lesser quantities of Site Grading/Earthwork will also be made by the OWNER for quantities greater than 15% below the estimated quantity shown on the bid sheet for a given mine. Such UNIT PRICE payment will require approval of the OWNER, and will be full compensation for approved additional or reduced Site Grading/Earthwork.
- C. Payment for additional topsoil placement at individual sites designated by the OWNER will be at the UNIT PRICE bid. For bidding it will be assumed that additional topsoil can be readily excavated from the designated borrow area with standard earthwork equipment, no access improvement to the area will be required, and the haul distance will not exceed two miles.

END OF SECTION 0270

## 0280 Drainage Control & Stream Protection

### PART 1 - GENERAL

#### 1.01 WORK INCLUDED

- A. Drainage control shall be required for a number of applications in the WORK, backfilling subsidence openings, and site grading/earthwork. This section covers the WORK necessary for construction of permanent and temporary drainage control including ditches, water bars, road crossings, stream crossings and energy dissipators.
- B. This item also consists of WORK to be performed for protection of the aquatic environment while performing any WORK on site. The specific goal of the item is to limit additional sedimentation of the aquatic environment during construction activities and while vegetation is reestablishing. Streams of primary concern are those listed in the Utah State Health Department's Wastewater Disposal Regulations Part II and those identified by OWNER. Streams of concern in the project area are specified in Section 0300: Specific Site Requirements. For streams of primary concern, any increase in turbidity must be limited to no more than 10 Nephelometric Turbidity Units (NTU) above background conditions when they range from 0 to 100. If background NTU is greater than 100, then maximum allowable increase in turbidity cannot exceed 10 percent.

#### 1.02 SUBMITTALS

- A. CONTRACTOR shall submit *with the Bid Proposal* the schedule and plan for implementing drainage control measures and for utilizing riprap, gabion mattress, or a combination of systems in accordance with these Specifications and Drawings. If a combination of systems is planned, specific locations for each item shall be identified. Also included shall be specifications of riprap or gabion mattress fill material if supplied as import, and specifications for gabion mattress to be used.
- B. The CONTRACTOR shall submit *with the Bid Proposal* a description of and location of stream protection measures to be used at each site.
- C. CONTRACTOR shall submit *with the Bid Proposal* the location of borrow areas intended for riprap unless otherwise specified in Section 0300: Specific Site Requirements, or the Drawings.
- D. CONTRACTOR shall submit *with the Bid Proposal* the specifications for materials and installation if either culverts or bridges are proposed for use.

#### 1.03 RELATED WORK

- A. Section 0230: Access Improvement
- B. Section 0240: Demolition and Clean-up
- C. Section 0270: Site Grading/Earthwork
- D. Section 0280: Drainage Control and Stream Protection
- E. Section 0290: Revegetation
- F. Section 0300: Specific Site Requirements

#### 1.04 PROTECTION

- A. CONTRACTOR shall conduct the WORK in a manner to minimize disturbance of existing trees and vegetation.
- B. CONTRACTOR shall conduct the WORK in a manner not to increase surface erosion due to

## Section 0280

alteration of natural drainage patterns.

### PART 2 - PRODUCTS

#### 2.01 DEFINITIONS

The terms Random Fill, Topsoil, and Coal Refuse shall be as defined in Section 0270: Site Grading/Earthwork.

#### 2.02 RIPRAP

Riprap shall be rock that is dense, sound, and resistant to abrasion and shall be free from cracks, seams, and other defects that would tend to unduly increase its destruction by water and frost actions. The rock shall be solid, angular or sub-angular fragments of quarry stone. Round, riverbed-type rock is not acceptable. Neither breadth nor thickness of a single stone shall be less than one-third its length. The unit weight of stone shall be no less than 155 pounds per cubic foot. Rocks susceptible to solution and disintegration upon contact with standing or flowing water shall not be used as riprap.

Riprap shall be reasonably well-graded with rock diameters specified below, or as specified in Section 0300 or on the Drawings:

<u>Rock Size</u>	<u>Percent Finer by Weight</u>
2 inch	15 percent (D15)
12 inch	50 percent (D50)
15 inch	100 percent (D100)

The thickness of the riprap should be at least as large as the largest diameter stone in the riprap.

#### 2.03 GRAVEL FILTER BLANKET

- A. Materials used for the underlining gravel filter for riprap and culverts shall be clean gravel composed of hard, durable stone and shall be free of fine sand, silt, or clay.
- B. The allowable particle size shall be between 0.8 and 2.0 inches. Alternative gradations shall be only at the OWNER'S approval.

#### 2.04 GEOTEXTILE FILTER BLANKET

Geotextile fabric used in the lining of drainage channels as a filter blanket beneath riprap shall consist of Mirafi 500X or equivalent (such as DuPont Typar 3401, Polyfelt TS800, or Trevira 1135).

#### 2.05 IN-STREAM FABRIC CHECK DAM

Fabric check dams shall consist of Mirafi 140N, UV resistant fabric or equivalent supported with 6 inch x 6 inch mesh (or smaller) fence anchored into the stream bottom with steel posts.

#### 2.06 SILT FENCE

Silt fences shall consist of Mirafi 500X, UV resistant fabric or equivalent supported with steel fence posts and/or 6 inch mesh fence.

## 2.07 WATER BARS

Water bars shall be elongated mounds of compacted soil constructed at an angle with respect to the slope of the terrain so that runoff is conveyed away from disturbed areas thereby alleviating rill and gully erosion.

## 2.08 STRAW BALE CHECK DAMS

Straw bale check dams shall consist of straw bales supported with steel stakes (T-posts, rebar, mine roof bolts). Wooden stakes are not acceptable as they tend to rot and do not penetrate stony ground well.

# PART 3 - EXECUTION

## 3.01 GENERAL

- A. All earthwork associated with construction of drainage control shall be in accordance with Section 0270: Site Grading/Earthwork.
- B. Wherever possible the CONTRACTOR shall install permanent drainage prior to the initiation of earthwork to minimize the need for temporary drainages.
- C. Two types of stream protection structures shall be used: in-stream check dams and silt fences between construction areas and streams.

## 3.02 TEMPORARY DRAINAGE DITCHES

- A. Prior to the initiation of earthwork, the CONTRACTOR shall effect temporary drainage control in the form of swales or ditches upgradient of WORK areas to minimize erosion during construction. Such drainage will be constructed with minimum disturbance to existing vegetation, and upon completion of work shall be graded to blend with surrounding contours and revegetated per Section 0290: Revegetation.
- B. On inclined surfaces, temporary access roads shall be cut or crowned to slope in toward the hillside at a grade of not less than 2 percent. At the intersection of the inside edge of the access road with the slope, a shallow ditch shall be formed. Water bars shall be installed across the access road and roadside ditch. If the WORK is scheduled during wet weather, a catch basin and culvert shall be constructed at the base of the access road as directed by OWNER.

## 3.03 FABRIC CHECK DAMS

- A. In-stream fabric check dams, when approved by OWNER, shall consist of at least three sets of dams constructed immediately downstream from temporary stream crossings and major construction activities adjacent to streams. Spacing of the fabric dams shall be designated by OWNER. The bottom of the fabric of the dam shall be anchored with rock. For added stability, the top of the dam can be anchored onto a pole laid horizontally across the stream. Holes should be cut approximately 6 inches long with a knife at the approximate normal water level to allow flow of water through the dam. Fabric check dams shall be placed with the approval of the OWNER at locations on the watercourse that maximize sediment settling between dams.
- B. CONTRACTOR shall install dams before any other WORK begins on site including access improvement. CONTRACTOR shall inspect dams at least every other day and after every storm

## Section 0280

and clean them when necessary to the approval of the OWNER. Sediments pulled from behind the dams shall be disposed of in a designated fill area and not on the streambank. Fabric shall be replaced when necessary to maintain the integrity of the dam.

### 3.04 SILT FENCES

- A. Silt fence fabric shall be supported either on minimum 6 inch mesh hog wire fence anchored with steel posts spaced no more than six feet apart or with steel fence posts alone spaced no more than three feet apart. At least 12 inches of the lower edge of the fabric shall be securely anchored with rocks or buried with soil material. The fabric shall be attached with at least four wire ties to the posts. In situations where the silt fence will be in use past the construction season, the wire fence backing shall be used. In all cases, guy wire shall be used to support the fabric top. The height of the silt fence shall be no more than three feet high. About 9 to 12 inches of the fabric shall be draped over the top of the wire fence and fastened to fence posts with wire. On slopes of disturbed areas, distances between lengths of silt fences shall not exceed 100 feet. With the approval of the OWNER, silt fences may be positioned to take advantage of natural drainage at sites in order to minimize the length of the fence.
- B. At the discretion of the OWNER, the fences shall be maintained for one year after all construction activity has been completed at each site. The CONTRACTOR shall maintain fences until final demobilization from the project area. After demobilization, the OWNER will be responsible for maintenance and removal.

### 3.05 STRAW BALE CHECK DAMS

- A. Straw bale check dams shall be installed as required in ditches and swales to provide temporary erosion control.
- B. Straw bale check dams consist of a series of straw bales placed end to end and anchored with stakes. The bales should be placed on their sides so that the straw fibers are vertical and the binder twine is not in contact with the ground. The bales should be keyed into a shallow (4-6 inches deep) trench so that there is no gap between the bales and the ground surface. The excavated soil from the trench should be banked against the upslope side of the bales for an additional seal. Adjacent bales should be placed tightly together and anchored with at least two stakes per bale to prevent the bales from turning. Loose straw shall be stuffed between bales to fill any gaps.
- C. Straw bale check dams should extend far enough to each side from the center of the ditch so that the elevations of the bases of the end bales are higher than the top of the center bale (that is, so impounded water overflows at the center of the dam instead of at the ends).
- D. Rotted, silt-clogged, or broken bales should be replaced as necessary. The CONTRACTOR shall maintain straw bale check dams until final demobilization from the project area. After demobilization, the OWNER will be responsible for maintenance and removal.

### 3.06 TEMPORARY DRAINAGE CROSSINGS (LOW WATER CROSSINGS)

- A. Temporary crossings shall be designated on a site-specific basis depending on stream classification, time of year intended for use, the frequency and duration of use, discharge of stream and number of vehicles to cross. The design of such crossings shall at all times be subject to the approval of the OWNER.
- B. In the drainages, the preferred crossing shall consist of the placement of 6 to 9 inch nominal size clean rock in the channel to facilitate equipment access. The clean gravel shall be placed only



to the extent necessary to provide a stable base for equipment crossing. Alternative temporary crossings shall be made only with the approval of the OWNER. These may include the construction of temporary bridges and culverts. In areas where access improvement is not required, stream crossings shall be made only with the approval of the OWNER.

- C. All crossings will be installed after required dams and fences are in place and in accordance with Section 0280, Part 3.03 and 3.04. Temporary bridge and culvert crossings must be removed as soon as possible after the construction activity is complete. Gravel crossings shall be left in place.

### 3.07 PERMANENT DRAINAGE CONTROL

- A. Ditches shall be constructed at the locations and to the dimensions shown on the Drawings.
- B. Where ditches cross areas of coal refuse, the bottom and sides shall be covered with a minimum of 24 inches of compacted soil.
- C. Place riprap or gabion mattresses in the locations and to the dimensions shown on the Drawings.

### 3.08 GEOTEXTILE FILTER BLANKET PLACEMENT

The geotextile fabric filter blanket shall be placed in the incised channel commencing at the downstream end and working upstream using care not to stretch or tear the material. At least a foot of the fabric shall be keyed into the sideslopes near the top of the channel and covered with soil. In channels where the width of the fabric material is less than the channel itself, the fabric must be overlapped in the channel bottom at least two feet. In addition, end lengths of the fabric shall be also overlapped at least two feet. Care shall be exercised in the placement of gravel or riprap on the surface of the fabric to prevent tearing.

### 3.09 GRAVEL FILTER BLANKET PLACEMENT

The gravel filter blanket shall be placed in the incised channel beneath all riprap and gabion materials as directed by the OWNER. The gravel shall be placed in one operation using methods that will not cause segregation of particle sizes. The surface of the finished layer should be reasonably even and free from mounds and windrows. The gravel need not be compacted in place, but shall be placed in such a manner as will result in uniform layers of material for riprap of the specified thickness.

### 3.10 RIPRAP PLACEMENT

- A. Before riprap is placed, the surface to be covered shall be fully compacted and graded to the required slope as shown on the Drawings. Cut-off trenches shall be excavated to the dimensions shown on the Drawings.
- B. Geotextile fabric filter and/or gravel filter blanket shall be placed to the dimensions shown on the Drawings.
- C. Riprap shall be placed directly on the filter blanket in the locations and to the contours shown on the Drawings. Riprap placement shall be done in a manner which will produce a reasonably well-graded mass of stone with the minimum practicable percentage of voids. The entire mass of stone should be placed in conformance with the lines, grades, and thickness shown on the Drawings. The riprap should be placed to its full course thickness at one operation and in such

## Section 0280

a way a manner as to avoid displacing the underlying material. Care should be exercised to prevent mixture of embankment and riprap materials.

- D. Riprap should typically be placed by end dumping to prevent segregation by sizes. It should be dumped from a vertical height of no more than 5 feet and should never be pushed downhill with a dozer, placed in layers, or conveyed down a chute as these operations cause segregation of particles. Where riprap is placed directly on filter fabric, the dump height should be no more than 3 feet to prevent tearing of fabric. Torn fabric shall be replaced with proper overlap as required.
- E. The large stones should be well distributed and the entire mass of stone should conform to the gradation specified. The riprap should be placed and distributed so that there will be no large accumulations of either the larger or smaller sizes of stone.
- F. Some roughness of the surface is acceptable and desirable, but the mass should be fairly compact with all sizes of material placed in their proper proportions. Hand placing or rearranging of individual stones by equipment may be required to achieve the results specified.

### 3.11 WATER BARS

- A. CONTRACTOR shall construct water bars on temporary access roads, in water courses, and at such other locations as shown on the Drawings or as directed by the OWNER.
- B. Water bars shall be constructed perpendicular to the gradient in order to deflect surface runoff toward catchments and drainage ditches or to otherwise reduce the velocity of runoff below the erosion threshold.
- C. Water bars shall consist of gravel-filled trenches excavated to a depth of 12 inches and a minimum width of 18 inches. The trenches shall be backfilled 4 to 6 inches above adjacent site grade. The surface of water bars on access roads shall be as directed by the OWNER.
- D. Unless otherwise specified, water bars shall be spaced at intervals of not more than 500 feet on slopes that are flatter than 15:1 (horizontal:vertical) and 300 feet on slopes between 15:1 and 10:1. On steeper slopes, the spacing of water bars shall be as directed by the OWNER.

## PART 4 - MEASUREMENT AND PAYMENT

### 4.01 MEASUREMENT

- A. Measurement will be based on and compared to the dimensions and quantities identified in the Bid Schedule, these Specifications and Drawings for each mine site. The OWNER may require the CONTRACTOR to provide measurements to determine progress and completion of the WORK.
- B. Measurements shall be required for a given mine site for cubic yards of riprap or bedding, square yards of geotextile fabric filter blanket, or lineal feet of ditch, streambank riprap, or fencing. Such measurement will be used by the OWNER for comparison with the estimated quantities shown on the Bid Schedule.
- C. Should the CONTRACTOR estimate the quantity of materials to be greater than 15% more than the quantities shown in the Bid Schedule, a CHANGE ORDER must be negotiated with the OWNER for ADDITIONAL WORK prior to the CONTRACTOR undertaking ADDITIONAL WORK. Measurement for quantities shall be determined prior to the WORK.

- D. When the actual quantity of Drainage Control performed as determined by measurement is greater than 15% less than the estimated quantity on the bid sheet, the OWNER will negotiate a reduction in the BID PRICE by the amount of variance using the UNIT PRICE. This adjustment shall be executed by a CHANGE ORDER.

4.02 PAYMENT

- A. Payment for Drainage Control will be for each mine site at the BID PRICE, as modified by any CHANGE ORDERS. Payment shall be authorized by the OWNER only for completed Drainage Control. No partial payments will be made.
- B. Payment at the UNIT PRICE for additional quantities of Drainage Control will be made at the approval of the OWNER for quantities greater than 15 percent in excess of the estimated quantity shown on the bid sheet for a given mine site. Reduction of payment for lesser quantities of Drainage Control will also be made by the OWNER for quantities greater than 15% below the estimated quantity shown on the bid sheet for a given mine. Such UNIT PRICE payment shall be full compensation for approved additional Drainage Control.

END OF SECTION 0280

## 0290 Revegetation

### PART 1 - GENERAL

#### 1.01 WORK INCLUDED

The WORK consists of revegetation of the disturbed areas, including areas disturbed by the WORK. Revegetation shall include:

- A. Site preparation
- B. Seedbed preparation
- C. Topsoil placement as required
- D. Seeding
- E. Mulching
- F. Erosion control netting
- G. Seedling and cutting planting

#### 1.02 SUBMITTALS

- A. CONTRACTOR shall submit *with the bid proposal* the names of one seed supplier, and alternate, to be used for the seed mixtures required by these specifications.
- B. CONTRACTOR shall submit *with the bid proposal* a written description indicating equipment to be used to perform the work required in this section.
- C. CONTRACTOR shall submit *during construction* empty container labels, tags, and receipts for mulch material and seed for verification of materials being used.

#### 1.03 RELATED WORK

- A. Section 0230: Access Improvement
- B. Section 0250: Mine Closures
- C. Section 0270: Site Grading/Earthwork
- D. Section 0300: Specific Site Requirements

#### 1.04 DELIVERY, STORAGE, AND HANDLING

- A. CONTRACTOR shall deliver seed in original containers showing analysis of seed mixture, percentage of pure live seed (PLS), year of production, net weight, date of packaging and location of packaging. Seed must be stored under dark, cool, and dry conditions. Damaged packages are not acceptable.
- B. Erosion control netting shall be stored out of direct sunlight.

## PART 2 - PRODUCTS

### 2.01 PLANT MATERIALS

- A. A combination of plant materials that may include seed, seedlings, containerized stock, and cuttings shall be used in revegetation. The use of the plant materials shall be in accordance with Section 0300: Specific Site Requirements and as shown on the Drawings.
- B. CONTRACTOR shall make a concerted effort to obtain all components of the plant materials mixture. Seed and nursery sources may require greater than six weeks notice to obtain specific species. More than one source may be required to furnish all seed or plant varieties. If all sources have been exhausted, or if available seed or stock of a given species is of unacceptable quality, that species may be deleted or another species substituted. Any changes in the seed mixture shall require the written approval of the OWNER prior to execution of the contract.
- C. CONTRACTOR must submit name of company and alternate that will supply seed, see Section 1.02. A.

### 2.02 SEED

- A. The species composition and planting rates of the seed mixtures to be used are specified in Appendix A. Unless specified otherwise, seeding rates given are for broadcast seeding.
- B. All seed mixes shall be fresh, clean, new crop seed.

### 2.03 SEEDLINGS

- A. Seedlings include containerized stock, tubelings, and bare root stock obtained from nurseries. The species composition and planting rates of the seedlings to be used are specified in Appendix A.
- B. Seedlings must be healthy and vigorous and not desiccated at time of planting. OWNER reserves the right to refuse payment for decadent plants.
- C. Bare root stock shall have roots that are not withered, dry, or partially dead due to improper transport and/or storage by the CONTRACTOR. All bare root stock shall be stored and delivered with roots in a damp medium.

### 2.04 DORMANT PLANT MATERIALS

- A. Dormant plant materials will be used for riparian area revegetation. Dormant plant materials include cuttings of live logs, twigs, or whips from wild tree stock.
- B. CONTRACTOR shall obtain dormant materials only from areas identified by the OWNER, and the OWNER shall approve and accept or reject the individual material cut. CONTRACTOR shall cut plant materials just prior to the breaking of dormancy, usually late March to early April. As dormancy is partially a function of temperature, cutting and planting of the materials may be required at a moment's notice (dependent on spring weather) to ensure material is planted while still in a dormant state.
- C. CONTRACTOR shall be responsible for all rooting hormones, sealants, paints, and shock-reducing vitamins.

## Section 0290

- D. All dormant vegetative plant materials shall be alive and dormant and not dried or otherwise damaged. Payment will not be made for substandard plant material, as determined by OWNER.
- E. Dormant plant materials shall consist of the following species planted at the indicated spacing, unless otherwise specified in Section 0300: Specific Site Requirements:

<u>Common Name</u>	<u>Scientific Name</u>	<u>Spacing</u>
Cottonwood	<i>Populus fremontii</i> (or) <i>Populus angustifolia</i>	1 every 20 feet
Endemic Willow	<i>Salix</i> spp.	2 rows on 3-foot centers - offset

### 2.05 MULCH

- A. Mulch, when required, shall consist of native hay or straw free of noxious weeds or any foreign material detrimental to plant life. *Alfalfa will not be permitted.*
- B. Mulch must meet the requirements of the Utah Noxious Weed Act (4-17-3, UCA; Regulation A700-04-09) and the Utah Phytosanitation Act. Mulch must be tested and found clean by an official Utah Department of Agriculture Inspector. CONTRACTOR shall contact the state inspector and arrange testing. Payment will not be made without certificate of inspection from Agricultural Inspector. Untested mulch may be used only with the prior written approval of the OWNER.
- C. Hay used as mulch may be old, but it shall be dry and not moldy.

### 2.06 EROSION CONTROL BLANKET

- A. Uniform, open weave, erosion control blanket which combines mat of seasoned wood excelsior of consistent thickness with photodegradable plastic mesh (AMXCO Curlex Blankets or equivalent) shall be used on slopes of 2h:1v or greater. The blanket shall be used in combination with straw mulch on sites where slope, soil texture, drainage pattern, or exposure will lead to excessive soil loss from erosion.
- B. Staples for installation of erosion control blanket shall be made of wire (diameter 0.091 inches or greater), U-shaped with 6-inch legs and 1-inch groin. Size and gauge of staples may vary with soil conditions.

### 2.07 TOPSOIL

- A. Topsoil shall be as defined in Section 0270: Site Grading/Earthwork.

## PART 3 - EXECUTION

### 3.01 GENERAL

- A. Areas to be revegetated are all those which have been disturbed during reclamation construction. Those areas shall include, but are not limited to, portal closure areas, subsidence areas, grading areas, access routes, staging areas, and other areas disturbed by CONTRACTOR in performing the WORK.

- B. CONTRACTOR shall take necessary precautions to avoid disturbance of surrounding native areas and will not travel on previously undisturbed soil, unless directed by OWNER.
- C. When machinery is specified, all operations will be conducted along the contour. On level sites (area permitting) all equipment operations shall be conducted perpendicular to the prevailing wind direction when wind erosion potential is considered to be high.

### 3.02 SITE PREPARATION

- A. CONTRACTOR shall remove and bury foreign materials and debris collected during topsoil spreading. Tree stumps and large shrubs may also be removed, buried, or stockpiled for distribution on the site following top-soiling, as specified in Section 0300 or as directed by OWNER.
- B. Areas that are not fill areas with imported topsoil shall be chiseled or ripped to a depth of 12 inches. This particularly applies to areas that have soils compacted from construction activities and includes haul roads and site access roads. Ripping shall be repeated until the compacted area is loose and friable.
- C. Areas of fill to be covered with imported topsoil shall be chiseled or ripped to a depth of 12 inches. Ripping of fill materials shall be completed by a bulldozer equipped with single or a twin set of ripper shanks. Ripping shall be done on 4-foot centers to a depth of 12 inches and shall follow final grading and precede seedbed material (topsoil) application. Ripping shall be completed at a speed which maximizes ripper shank action and promotes soil material disruption to the specified depth. Ripping shall be repeated until the compacted area is loose and friable.
- D. Topsoil shall be placed on fill areas immediately following ripping to a minimum depth of 24 inches, or other minimum depth as specified in Sections 0270 or 0300, in all areas designated by the OWNER.

### 3.03 MULCHING

- A. All sites not designated for erosion control blanket shall be mulched unless otherwise specified by the OWNER in Section 0300: Specific Site Requirements.
- B. Mulching shall be performed AFTER topsoil is in place, and PRIOR to seeding. Mulch shall be spread by hand or mechanical blower, in an even manner, at a rate of 2,000 pounds per acre over the site to be mulched. Mulch application shall be initiated at the top of the slope, working downhill, where possible.
- C. Mulch shall be crimped with hand tools where equipment cannot gain access or where soil surface roughness (see Part 3.05 below) is already adequate following topsoil distribution and further equipment activity would level the surface.

### 3.04 SEEDBED PREPARATION/SURFACE ROUGHENING

- A. AFTER topsoil placement and mulching, and PRIOR to seeding, the ground surface shall be roughened and gouged to create hummocks and depressions with up to 12 inches of relief. This relief will reduce ground surface wind disturbance and create water catchment basins. Roughening can be achieved by gouging with a backhoe or excavator bucket. Surface roughness can also be created during topsoil distribution by leaving intact the mounds and windrows from each dump truck or loader bucket dump. Furrows, basins, and ridges created by

## Section 0290

the roughening should run predominantly along the contour to minimize runoff. The roughening process should incorporate the mulch into the top of the soil and some will be buried; however, care should be taken to minimize the mulch buried at depth. CONTRACTOR shall exhibit caution during the gouging and roughening process to ensure that subsurface \*\*\*coal refuse is not uncovered or brought up to the surface.

- B. Boulders, both large and small, may be left on site after topsoiling and prior to seeding, either singly or in groupings to blend with the natural surroundings, as directed by OWNER. OWNER may require that additional boulders be placed on site prior to seeding to enhance visual variation and provide wildlife habitat.
- C. Seedbed preparation shall be considered to be complete when the soil surface is completely roughened.
- D. Unless the soil is severely compacted, seedbed preparation shall not be required for discontinuous, isolated areas of disturbance less than 0.05 acres (approximately 2500 square feet or 50 feet by 50 feet), such as areas around mine portal closures.

### 3.05 SEEDING

- A. All seeding shall be broadcasting as directed by OWNER. When broadcast seeding, passes shall be made over the site to be seeded such that even distribution of seed shall be obtained. Broadcast seeding shall take place immediately following the completion of final seedbed preparation. Broadcast seeding shall not be conducted when wind velocities would prohibit even seed distribution. Broadcast seeding shall be followed by hand raking, manual use of a drag chain, or sweeping with sturdy tree or shrub branches to cover seed. This shall be done over the entire site but will not be so extreme as to reduce the extent of soil relief.
- B. Broadcast seeding of large areas shall be done using hand-operated "cyclone-type" mechanical seeders. All seeding equipment used shall be equipped with a metering device and set to the appropriate seeding rate.
- C. Broadcast seeding of small areas of disturbance less than 0.05 acres (approximately 2500 square feet or 50' x 50') may be done by hand scattering. Raking of small areas is not necessary if there is sufficient surface roughness to ensure that seeds will fall into crevices and other micro-topographic depressions so that weather and gravity will cause them to be covered and stay in place.
- D. After completion of the broadcast seeding and seed covering, organic debris such as logs, tree stumps, and grubbed vegetation shall be randomly redistributed across the sites. This shall be done at the OWNER's direction for the purpose of creating visual variation and production of wildlife habitat. Care shall be exhibited to avoid leveling the soil surface.

### 3.06 SEEDLING PLANTING

- A. Planting of bare-root and/or containerized plant seedling stock, when required, shall occur following ground surface roughening. No seedling planting shall be attempted in frozen seedbed material. Seedling spacing shall be as stated in the Section 0300 revegetation plans. Seedling stock shall be delivered to the planting site as close to the time of planting as possible.
- B. At each individual planting site, a circular area (planting circle) shall be cleared of mulch materials or inhibiting debris. The size of the circle shall be approximately 12 inches in diameter. The receiving hole shall then be dug with the depth of the hole extending 2 to 4 inches deeper than necessary for planting. The hole shall be of sufficient size to allow



positioning the seedling and tamping the backfill. After the hole has been formed, it shall be partially backfilled with loose soil to allow planting at the proper depth. The seedling shall then be placed in the hole and the hole  $\frac{1}{2}$  backfilled. The hole shall then be filled with water and the remainder of the seedbed material backfilled into the hole as rapidly as possible without displacing water from the hole. The backfill shall be firmly tamped around the seedling. Planting depth shall not exceed the depth at which the seedling was grown in the container.

- C. A basin, which slopes gently from the outside of the planting circle to the seedling stem, shall be formed in the soil to aid in water catchment. The basin shall be mulched with straw (or the mulch replaced when a seedling is planted into a mulched site) and the straw anchored with gravel and seedbed material. Planting holes may be dug by hand or with a power auger. Planting shall be completed randomly over the disturbed area in clumps, as specified in Section 0300.

### 3.07 WILLOW CUTTINGS

- A. Willow Cuttings shall be planted along the borders of water courses as designated in Section 0300: Specific Site Requirements. Cuttings shall be gathered and planted in the spring (April or May) of the year.
- B. Cuttings shall be collected from locally occurring, dormant plants free from disease. All cuttings shall be of stem material and be approximately two (2) to six (6) feet long. Stem material, 2 to 4 years old at the maximum, shall be considered acceptable for use. The basal cut shall be made at an angle immediately below a node. Cuttings shall be planted immediately after collection, keeping the cuttings moist throughout the process. Should storage be necessary, cuttings shall be placed in a plastic bag with a wet paper towel or cloth wrapped around the bases to prevent desiccation.
- C. To complete the planting procedure, the base end of the cutting shall be pushed into a prepared seedbed such that 1 to 2 feet of cutting remains above the seedbed surface. The base *must* be in contact with the water table. A metal bar may need to be pounded into the soil to develop a pathway for the willow cutting to follow. The base end shall be dipped into a solution of "Rootone F" prior to planting to aid in root formation.

### 3.08 DORMANT LOG PLANTING

- A. OWNER shall be responsible for locating and securing the necessary permits for obtaining dormant log materials. OWNER shall also identify and tag all materials to be cut, and be on site during the cutting process. CONTRACTOR shall be responsible for cutting, transporting, and handling dormant plant material; site preparation for planting; application of all rooting hormones, transplant shock reducers, paints, and sealers; and placing the plants into the ground at the locations specified in Section 0300.
- B. Dormant logs may be a mix of Narrowleaf Cottonwood, *Populus angustifolia*, and Fremont Cottonwood, *Populus fremontii*. All logs shall be alive and dormant, and not dried or otherwise damaged. All logs shall be between 2 and 6 inches in diameter at the base, and 6 to 18 feet in length. All dormant logs shall be cut at an angle at the base (rooting) end and flat at the top (vegetative) end. The bottom two feet of the log shall be scored with an ax to expose the cambium layer (see drawing). Side limbs will be removed from the logs and all exposed cuts including the top saw cut shall be sealed with an accepted tree paint.
- C. Holes for dormant logs shall be augured to a depth that reaches into the water table. Planting areas adjacent to streams and rivers may be composed entirely of river rock, or closely packed,

## Section 0290

competent rock. Auguring through this material into the water table may be extremely difficult. An auger with a chisel bit operating off of a power take off (PTO), some other drilling rig, or a backhoe with a narrow bucket may be necessary. Dormant logs shall be planted in holes that barely accommodate the diameter of the logs. If larger holes are necessary because of digging conditions, the excess volume shall be carefully backfilled under the direction of the OWNER. Dormant log spacing shall be as stated in Section 0300. Planting shall occur in the spring (March, April, or May) of the year.

- D. CONTRACTOR shall make every effort to minimize damage to vegetation and environmental disturbance at the tree source area. Unused or excess brush, branch trimmings, logs, etc. shall be disposed of properly. CONTRACTOR shall leave the site neat and in a condition acceptable to OWNER and the landowner.

### 3.09 EROSION CONTROL BLANKET

- A. The area to be covered shall be properly prepared and seeded prior to application of erosion control blanket. All roads and debris shall be removed prior to seeding and installation.
- B. Seeded slopes shall be covered with excelsior-type erosion control blanket where shown on the Drawings.
- C. CONTRACTOR shall roll blanket down over slopes without stretching or pulling and lay blanket smoothly on soil surface, burying and securing the top end of each section in a narrow (6-inch) trench. CONTRACTOR shall leave 12 inches overlap from top roll over bottom roll and four inches overlap over adjacent section. The blanket shall be placed with the netting on top and the fibers in contact with the soil over the entire area.
- D. The staples shall be installed per erosion control netting manufacturer's recommendations and spaced over the blanket on no less than 6-foot intervals. Outside edges and overlaps shall be at 36-inch intervals.
- E. CONTRACTOR shall lightly dress slopes (manually) with topsoil and cobbles to ensure close contact between blanket and soil.

## PART 4 - MEASUREMENT AND PAYMENT

### 4.01 MEASUREMENT

- A. Measurement will be based on and compared to the quantities identified in the bid sheets, these Specifications and Drawings for each mine site. The OWNER will request intermediate measurements to determine progress of the WORK.
- B. Measurements by CONTRACTOR will be required for a given mine site for acres of revegetation and/or square yards of erosion control blanket. Such measurements will be used by the OWNER for comparison with the estimated quantities shown on the bid sheets.
- C. Should the CONTRACTOR estimate the quantity of materials to be greater than 15% more than the quantities shown in the Bid Schedule, a CHANGE ORDER must be negotiated with the OWNER for ADDITIONAL WORK prior to the CONTRACTOR undertaking ADDITIONAL WORK. Measurement for quantities shall be determined prior to the WORK.
- D. When the actual quantity of Revegetation performed as determined by measurement is greater than 15% less than the estimated quantity on the bid sheet, the OWNER will negotiate a reduction in the BID PRICE by the amount of variance using the UNIT PRICE. This adjustment

shall be executed by a CHANGE ORDER.

4.02 PAYMENTS

- A. Payment for Revegetation will be for each mine site at the BID PRICE, as modified by any CHANGE ORDERS. No partial payments will be made.
- B. Payment at the UNIT PRICE for additional quantities of Revegetation will be made for quantities greater than 15 percent in excess of the estimated quantity shown on the bid sheet for a given mine site. Reduction of payment for lesser quantities of Revegetation will also be made by the OWNER for quantities greater than 15% below the estimated quantity shown on the bid sheet for a given mine. Such unit price payment will require approval of the OWNER, and will be full compensation for additional or reduced revegetation and/or erosion control blanket.
- C. Payment will not be made without:
  - 1. Seed: seed testing certification, certification to be submitted with invoice, and
  - 2. Mulch [only if specified]: Phytosanitary Certificate for certification of compliance with the Utah Noxious Weed Act. Certification shall be submitted with invoice.

END OF SECTION 0290



## **0300 Specific Site Requirements**

**PART 1 – GENERAL**

**PART 2 – SPECIAL TERMS AND CONDITIONS**

**PART 3 – EXECUTION**

**PART 4 – MINE SITE DESCRIPTIONS AND SPECIFIED CLOSURES**

### **LOCATIONS AND WORK DESCRIPTIONS**

### **TWO SITES**

**McCormic Adit**

**Site 1**

**Standard Shaft**

**Site 2**

## 0300 SPECIFIC SITE REQUIREMENTS

### PART 1 - GENERAL

#### 1.01 WORK INCLUDED

- A. This section describes the location, features present, and the WORK to be performed at the MiVida and Standard Shaft Project located in San Juan County, Utah. The items of the WORK shall be performed according to the appropriate sections of these specifications.
- B. It is the intent of these Specifications that the site-specific scope of WORK is as described in this Section. The General Technical Specifications, Sections 0200 through 0290, outline WORK broadly applicable to all abandoned mine reclamation situations and that may not be required at each mine site in this project. Where there is a conflict between Section 0300 and the General Technical Specifications (0200's), Section 0300 shall govern.
- C. The access, site description and specific requirements for each closure method are described in this Section. Details and dimensions are shown on the drawings in Appendix D. CONTRACTOR shall be aware that the dimensions on the Drawings are shown as typical. CONTRACTOR shall also be aware that minimum or maximum dimensions on the Drawings or given in the Specifications are specific and are to be adhered to unless the OWNER approves changes in writing. The quantities presented in the specific site sections should be considered an estimate with a tolerance of plus or minus 15 percent. CONTRACTOR shall visit each site and determine the quantities and amounts required in performing the WORK as intended in these Specifications and on the Drawings.

#### 1.02 PROJECT LOCATION AND ACCESS DESCRIPTION

- A. The project area includes the McCormic Tunnel and the Standard Shaft mine. There is one open adit at the McCormic mine site and one open shaft at the Standard mine site.
- B. Access: To reach the McCormic and Standard mine sites from Monticello, Utah travel north 22 miles along highway 191 to the Lisbon Valley Industrial Area/Steen Road. Turn east on Steen Road (San Juan County road 114). Drive 5.1 miles east on Steen Road to an intersection with County roads 111 and 114. Continue up County Road 114/Steen Road another 2.6 miles. This road is mostly paved up to the McCormic Mine site. The access to the McCormic mine site is currently blocked with boulders and requires foot travel for 0.1 miles to the mine opening. To access the Standard mine continue up the main road past the McCormic site turn off. For 0.1 miles to where the road forks take the east turn and travel another 0.78 miles directly to the shaft. Travel time is about 35 minutes from Monticello.
- C. The formal project boundary takes in the following sections:  
T30S, R24E, Section 11
- D. The MiVida and Standard Shaft Project boundary falls within the Sandstone Draw USGS 7 ½' (1:24,000 scale) quadrangle.

#### 1.03 MINE FEATURE DESCRIPTIONS

- A. The MiVida and Standard Shaft Project area includes two abandoned uranium mine sites with two identified abandoned mine openings, a steel loading bin, mine cars, track, miscellaneous trash and debris.
- B. Site ID Numbers (Tag Numbers): Each mine opening or feature is identified by a unique site identification number such as 3411308HO002. The ID number consists of seven digits, one or two letters, and one to three digits. The first digit indicates the quadrant around the Salt Lake baseline and meridian (or the Uinta special meridian). Townships south and east of the SLBM are coded "4." The second and third digits indicate the township, the fourth and fifth digits indicate the range, and the sixth

and seventh digits indicate the section. These numbers are followed by letters indicating the type of mine opening or feature (H = horizontal adit, I = inclined adit, V = vertical shaft, SH = subsidence hole, PR = prospect, TR = trench, PT = open pit, TA = tailings) and, in the case of shafts and adits, letters indicating whether the mine is open (O) or closed (C). These letters are followed by numbers that are sequential numbers assigned as the openings were encountered during the field inventory. Thus, site number 4060318HO003 is the third horizontal opening (HO) inventoried in Township 6 South, Range 3 East, Section 18. The leading zeros in the sequential number part of the ID number are frequently omitted (i.e. HO3 instead of HO003).

C. Specific features of the MiVida and Standard mines are as follows:

4302411HO001

This is the McCormick Mine Tunnel located north of the steel ore bin. It is an adit approximately 10.5 feet high by 8.5 feet wide. The adit is currently closed by a earthen backfill which begins approximately 40 feet inside a timber supported opening. Several ore cars are lined up inside the opening leading outside to an electric motor engine on narrow gauge rail. The adit backfill has been excavated near the top to create an opening 2 feet high by 2 feet wide. The adit sits at the base of a cliff face with the mine dump creating a large pad area. The narrow gauge rail comes out of the adit across the pad and on a suspended section over to the metal ore bin.

4302411VO001

This is the Standard Mine located south east of the McCormick Mine Tunnel. It is a shaft approximately 30 by 22 feet and estimated to be 600 feet deep. There is a possibility that a fan is bridged across the shaft at a depth of 140 feet. An exact measurement could not be taken due to the hazardous conditions. The shaft is currently open and is undercutting beneath the collar 2 to 8 feet. The shaft has orange fencing around it with signs posted "Danger Open Mine Shaft". There are a couple of concrete foundations around the site and a wood structure on the dump. These features are not to be disturbed.

## 1.06 LAND STATUS

- A. The MiVida and Standard Shaft Project area contains land owned or controlled by several parties. OWNER is responsible for obtaining the necessary rights of entry to perform the reclamation work. OWNER will have maps showing boundaries of property tracts available during construction for consultation.
- B. Gas pipelines are present along the access road to the McCormick adit inside the canyon. The pipeline is managed by T.B.I. Pipeline Co. Phone Number 435-868-2271.
- C. The Standard Mine site occurs on public land managed by the Bureau of Land Management (BLM).  
For more information, contact:  
  
 Jeff Brown, Petroleum Engineering Technician  
 Bureau of Land Management  
 Monticello Field Office  
 435 North Main Street  
 P. O. Box 7  
 Monticello, Utah 84535  
 Telephone: (435) 587-1500
- D. CONTRACTOR shall not perform WORK on sites on BLM administered land until OWNER has obtained authorization from BLM (expected prior to Notice to Proceed).

PART 2 - SPECIAL CONDITIONS AND RESTRICTIONS

2.01 CULTURAL RESOURCE PROTECTION

- A. Except as specified in this section, removal of historic or prehistoric artifacts or rock specimens is prohibited. This includes, but is not limited to bottles, bottle fragments, china and glass fragments, tools, tin cans, buckets, pipe, wire, nails, spikes, bolts, track, machinery, ore cars, vehicles, lumber and other wood, arrowheads and other stone tools, ore samples, petrified wood, and fossils.
- B. While features such as cabins, head frames, and ore chutes are obviously important, many of the historically important features present in the project area are not readily apparent. For example, ore sorting areas may appear simply as a patch of differently colored rock on a dump. Much of what is significant at the site might typically be dismissed as "trash" somewhere else. Often, the mine opening itself, or cribbing within an opening, is important and needs to be treated appropriately.
- C. Access improvement, excavation, and other ground disturbing activities shall be limited to the minimum necessary to achieve the goals of the WORK. Alteration or removal of structures or structural elements of mine openings, such as props, lagging, cribbing, retaining walls, foundations, and doorways shall be limited to the minimum necessary to safely and effectively install the closure. Any such alteration shall be planned in consultation with and executed as directed by the OWNER.
- D. One of the key features of the MiVida and Standard Shaft Project area that makes it historically important is its surviving "historic landscape", the overall appearance of the terrain dotted with mine dumps and workings offering a glimpse of the past. To preserve this historic appearance, when possible, mine dumps used, as a source of backfill shall be excavated in a way that maintains the outer lines and grades of the dump. This can be done by uniformly removing material from all surfaces, by removing material from the top down, by slightly "hollowing out" the dump, or by removing one lobe of a multi-lobed dump. The idea is to avoid leaving the dump with an uneven, gouged look.
- E. CONTRACTOR shall stop work and notify OWNER immediately if human burial remains are discovered.
- F. Any petroglyph or pictograph panels shall be not harmed.

2.02 BAT CONSERVATION

- A. OWNER has performed surveys to determine which mines are used for bat habitat. Where bats are present in a mine, they will be excluded from the mine prior to installing airtight closures (see Section 0250, Part 3.01.F). **Standard Shaft will require exclusion prior to closure.**
- B. The length of the exclusion period may be reduced from one week to three fair weather days with OWNER's approval. Rainy or cold weather inhibits bat activity and will increase the length of the exclusion accordingly, up to the one week maximum.
- C. The recreational use of the project area raises the possibility that vandals may damage or remove the chicken wire seals during the exclusion period. Should this occur, damaged seals shall be replaced and the exclusion period started over.
- D. The exclusion process is effective only in warm seasons when bats are active.
- E. Vertical shafts covered with chicken wire for bat exclusion shall be flagged with warning tape.



## 2.02 LAND PROTECTION

- A. Trash, containers, wrappings, empty mortar and concrete mix bags, concrete block fragments, rebar cuttings, welding rod scraps, waste PUF, pallets, water jugs, buckets, broken tools, discarded materials, food wrappers, beverage containers, paper towels, and other such litter generated by the reclamation activities shall be kept contained during construction and shall be cleaned up and removed from the site upon completion.
- B. CONTRACTOR shall exercise care with open flames when welding or cutting to avoid starting range fires. CONTRACTOR shall submit a written range fire prevention and fire response plan to OWNER at the start of construction.
- C. CONTRACTOR shall be responsible to reimburse landowners or lease holders for livestock or other property lost, injured, or damaged by CONTRACTOR's operations on access roads.

## 2.03 ACCESS RESTRICTIONS

- A. Mechanized access to the sites is limited to a single trip on the designated old mining road. Ground disturbance shall be minimized. Vehicle tracks shall be raked out thoroughly upon completion and the old mine road shall be blocked.
- B. Vehicles shall stay on existing roadways as much as possible and avoid cross-country trips across undisturbed areas except where necessary. CONTRACTOR shall select from a pre-determined number of staging areas identified in the specifications and secure all necessary permits, including camping permits, from the applicable land management agency.

## 2.04 WORKER HEALTH AND SAFETY

- A. The CONTRACTOR shall comply with all applicable standards of the Mine Safety and Health Administration (MSHA) published in "Safety and Health Standards Applicable to Underground Metal and Nonmetal Mining and Milling Operations" (30 CFR Part 57), in particular sections 57.5037 through 57.5047.
- B. The project area contains uranium mines and radioactive minerals. CONTRACTOR shall comply with the radiation health and safety protocols of Section 0225: Radiological Protection. The highest known gamma radiation reading taken within the project area is  $1700\mu\text{ R/hr}$ . The reading was taken inside the McCormic Mine Tunnel at the toe of the backfill. The highest known radon reading was over 100WL. This reading was also taken inside the McCormic Tunnel at the toe of the backfill. Background radiation in the immediate area ranges from  $80\mu\text{ R/hr}$  to  $400\mu\text{ R/hr}$ . All measurements were taken at waist level.
- C. Rodents often nest in abandoned mines and leave accumulations of droppings and nest debris. In theory, these nests and droppings could host the potentially lethal Hantavirus, although no mine closure work has ever been linked to a case of Hantavirus. As a precaution, workers should avoid stirring up dust or rodent droppings in mines and use standard hygiene and sanitation practices (washing before eating, etc.). Workers are encouraged to learn to recognize the symptoms of Hantavirus infection and seek proper medical attention if indicated.
- D. Standard safety gear (hard hat, steel-toed shoes) are required for all personnel. Fatigue, heat stress, and dehydration are inherent medical risks of heavy manual labor in desert environments. Frostbite and hypothermia are risks of winter work. Workers should take appropriate precautions for the site conditions.

#### Section 0300

- E. CONTRACTOR is required to hold regular safety meetings and is encouraged to have a response plan in place in the event of accidents, personal injury, animal bites, or other medical emergency.
- F. San Juan County is covered by 911 emergency telephone services. This project area has no reliable cell phone coverage.

### PART 3 - EXECUTION

#### 3.01 WORK REQUIRED AT ALL SITES

The following WORK shall be performed at the sites:

- A. Improve access to the site along the routes described to the degree required to conduct the WORK. All access improvement shall be performed in accordance with Section 0230, Access Improvement. Where access has been created, the access shall be closed following construction in accordance with Section 0230, Access Improvement. Access grading shall be in accordance with Section 0270, Site Grading/Earthwork.
- B. Items specifically identified for demolition shall be demolished and disposed of in accordance with Section 0240, Demolition and Clean-up.
- C. Trash and debris created during construction shall be removed and disposed of in accordance with Section 0240, Demolition and Clean-up.
- D. Mine openings and subsidence holes shall be sealed or closed in accordance with the mine closure method identified for the specific site as specified in this Section and in accordance with Section 0250, Mine Closures as shown on the Technical Specification Design Drawings in Appendix E.
- E. Site grading and earthwork required shall be performed in accordance with Section 0270, Site Grading/Earthwork.
- F. CONTRACTOR shall finish all openings reclaimed by the backfill closure method by mounding the collar and/or building berms or ditches as appropriate for each site. The purpose of the mounds, ditches or berms is to divert runoff around the edge of the backfill to keep drainage from contributing to deterioration and saturation of the fill. Typical details for mounds, berms and ditches are described in Section 0250, Mine Closures, and are shown on the Technical Specification Design Drawings in Appendix D.
- G. CONTRACTOR shall clear any timber or debris caught in the upper portion of vertical openings that may cause bridging of the backfill. Likewise, any timber or debris that will interfere with backfilling adits shall also be cleared. Timbers removed from mine openings do not have to be disposed of. They must be either left on site or the CONTRACTOR may take the wood for his or her needs. All material other than wood removed from a mine opening shall be hauled off the site and disposed of at an approved landfill or used for scrap.
- H. Adjacent or nearby dumps will be used for backfill prior to use of natural soil material. Where existing dumps do not contain adequate material to backfill the open mine site, it is assumed for revegetation purposes that 1 foot of material over an appropriately sized area will be used to meet the backfill requirements.
- I. Finished grading of backfill pursuant to Sections 0250, Mine Closures; Section 0270, Site Grading/Earthwork; and this Section 0300, Specific Site Requirements will be completed prior to completion of the CONTRACT. Where revegetation is planned, the revegetation shall be performed in

accordance with Section 0290, Revegetation.

- J. Rights of Entry from the Landowners have been obtained on all the sites contained in the WORK.
- K. **CONTRACTOR shall protect all pipelines within the project area during construction activities.** If access requires crossing any pipeline, the pipeline will be adequately protected to avoid any potential damage to the pipeline.

### 3.02 CONSTRUCTION SCHEDULING

- A. Notice to proceed with construction is contingent upon OWNER receiving authorization from the BLM. OWNER expects authorization to be in place by the June 1, 2005 bid date. However, if either is lacking, WORK will be postponed accordingly.
- B. Work Priorities: Placement of the backfill at the McCormic Tunnel is dependent on the radon gas readings. Typically radon gas readings are lower in the morning, when the temperature is cooler. Higher readings may require rescheduling of backfill in the McCormic Tunnel to a cooler season.
- D. Most of the site reclamation for the MiVida and Standard Shaft Project is not weather dependent. It is conceivable that the project work could be suspended for the summer because of the high radon gas readings. The CONTRACTOR shall account for this potential shutdown within the mobilization/demobilization cost. The mine closure costs quoted on the bid schedule apply for the duration of the reclamation. The start-up date for resumption of WORK suspended due to high radon gas readings or other conditions will be determined by OWNER in consultation with CONTRACTOR and will depend upon the nature of the uncompleted WORK.

### 3.03 MINE CLOSURES:

Close the two mine openings in accordance with Section 0250: Mine Closures and as follows:

- A. 4302411HO001: The McCormic Tunnel: Backfill this adit from the existing recessed backfill out to the surface.
  - 1. Install a temporary seal in the small 2 feet x 2 feet excavation and along the top of the existing backfill using PUF materials. This work will require radon respirator protection at all times.
  - 2. All Mechanized Machinery (backhoe/tracker/loader etc.) shall be positive pressure enclosed cab. PPI shall be required to be worn while using machinery. Using machinery, remove the mine cars and the electric motor from inside and at the mouth of the opening to allow access to the adit. Do not remove or damage the wooden supports. The motor and mine cars will eventually need to be placed on the track outside of the mine opening in a similar fashion.
  - 3. Place backfill inside the opening beginning at the end of the existing backfill. Backfill the opening out to the surface using adjacent dump materials. This may include a conveyor or mine mucker. With machinery compact the backfill from the surface.
  - 4. Regrade the excavated dump area in accordance with section 0270 Grading and Earthwork, and to avoid erosion of the existing dump face.
  - 5. Reseed the affected areas. No Mulch will be required for the revegetation work. Seed mix Appendix A.
  - 6. Surface roughen the mine access road on the way out to enhance revegetation and prevent

Section 0300

vehicle access.

- B. 4302411VO001: Exclude for bats before backfilling, Section 0300, 2.02. Using equipment, backfill the shaft with adjacent dump and loading pad material. The shaft is 30 by 22 feet and estimated to be 600 feet deep. The shaft is possibly bridged with a fan that fell into the shaft about 140 feet down. The dump is 36 feet to the south west of the shaft and is about 55 by 91 feet across the top. The estimated backfill volume is 13,300 cubic yards.
1. Regrade the excavated dump area in accordance with section 0270 Grading and Earthwork, and to avoid erosion of the existing dump face.
  2. Reseed the affected areas. No Mulch will be required for the revegetation work. Seed mix Appendix A.

END OF SECTION 0300

## **APPENDIX A**

### **REVEGETATION SEED MIX**



## Appendix A: Revegetation Seed Mix

### Seed Mix Species Composition

<u>Common Name</u>	<u>Scientific name</u>	<u>Preferred Variety</u>	<u>Pounds PLS/Acre</u>
White Yarrow	<i>Achillea millefolium</i>		0.10
Palmer Penstemon	<i>Penstemon palmerii</i>	<i>Palmeri</i>	0.25
Tansyleaf aster	<i>Aster tanacetifolius</i>		0.10
Blue grama	<i>Boutelous gracilis</i>		1.75
Galleta Grass	<i>Hilaria jamesii</i>		2.00
June Grass	<i>Koeleria macrantha</i>		0.10
Western Wheatgrass	<i>Pascopyrum smithii</i>		2.50
Sandberg Bluegrass	<i>Poa secunda</i>		0.20
Alkali Sacaton	<i>Sporobolus airoides</i>		0.10
Indian Rice Grass	<i>Stipa hymenoides</i>		1.25
Big Sagebrush	<i>Artemisia tridentate</i>		0.25
Four-wing salt bush	<i>Atriplex canescens</i>		4.00
TOTAL			12.60

The planting rate indicated (pounds PLS/acre) is for drill seeding. Double for broadcast seeding.





## **APPENDIX B**

### **SITE DESCRIPTIONS and MINE CLOSURE SCHEDULE**



## APPENDIX B

### SITE DESCRIPTIONS And MINE CLOSURE SCHEDULE

Note: Refer to Section 0300, Part 1.03.C of the specifications for a description of the site ID numbering (tag number) system.

Use the following specification section and standard design drawing in Appendix E for each closure type referenced in Appendix A:

<u>Closure Type</u>	<b>Specification Section</b>	<b>Standard Mine Closure Design Drawing Appendix E</b>
BACKFILL (ADIT): Hand or Equipment	0250, Part 3.02	E1
BACKFILL (SHAFT): Hand or Equipment	0250, Part 3.02	E2
WALL (BLOCK)	0250, Part 3.02	E3
WALL (STONE)	0250, Part 3.02	E4
BAT GATE	N/A	E6 and E7
REBAR GRATE (GRADE BEAM & I-BEAM)	N/A	E14, E15, and E16
REBAR GRATE (PINNED)	N/A	E17

Note: Standard mine closure design drawings for the following closure types are not included in Appendix E because none are specified for this project: Wall & Backfill, CMP Bat Gate.

Refer to Section 0300, Part 1.03.C of the Specifications for a description of the site ID numbering (tag number) system. There are many small prospects for which no work is planned that are tagged or mapped and are simply included in the descriptions of tagged features.

Site ID	UTM Coordinates (m)		Description of Opening (all dimensions in feet)	Special Conditions	Closure Method	Estimated Quantity (Cyds)
	Northing	Easting				
4302411HO001	4228153	652451	10.5'h x 8.5'w x 40'd , 2'x2' opening 40 feet inside portal, several ore cars lined up at portal.		Equip. Backfill	200
4302411VO001	4227752	653235	30'x22'x600'd, fan wedged down shaft ~140' down, shaft is undercutting the collar by 2 - 8 feet	Bat Exclusion	Equip. Backfill	13,300

All Locations and dimensions are approximate. Construction quantities are estimated and will be confirmed at time of construction. UTM coordinates are all in Zone 12.  
Dimensions are in feet. h=high/height, w=wide/width, l=long/length, d=deep/depth, diam=diameter, unk=unknown, w=with, ~approx=approximately.  
Special conditions: Bat excl=bat exclusion required, NR Elig=National Register eligibility site, BLM Mon= work to be monitored by BLM archeologist.



## **Appendix C: Contractor Report Forms**

**DAILY CONSTRUCTION PROGRESS REPORT**

**RECORD OF INDIVIDUAL EXPOSURE TO RADON**

**CONTRACTOR PERFORMANCE RATING**



DAILY CONSTRUCTION PROGRESS REPORT

-- CONTRACTOR --

Project: MiVida Date: \_\_\_\_\_ M T W Th F

Crew: \_\_\_\_\_ Supervisor: \_\_\_\_\_ Hours: \_\_\_\_\_ to \_\_\_\_\_

Equipment: \_\_\_\_\_

\_\_\_\_\_ down from \_\_\_\_\_ to \_\_\_\_\_ for \_\_\_\_\_

General description of work performed, equipment/material deliveries, etc:

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_

\_\_\_\_\_ (Attach as-built drawings as required.)

WORK items approved: \_\_\_\_\_

\_\_\_\_\_

Problems/delays and proposed or actual resolution. DOGM action required? Yes No

\_\_\_\_\_

\_\_\_\_\_

Visitors &amp; purpose: \_\_\_\_\_

\_\_\_\_\_

Temp: 20 30 40 50 60 70 80 90 100 Comments:

Sky: fair pc mc cldy ovrcst rain snow

Ground: dry wet muddy snow \_\_\_\_" frozen

Project is approximately ☐ on schedule

Contract expires:

\_\_\_\_\_ days behind schedule

\_\_\_\_/\_\_\_\_/\_\_\_\_

\_\_\_\_\_ days ahead of schedule

Contractor: \_\_\_\_\_ \_\_\_\_/\_\_\_\_/\_\_\_\_

Project Mgr: \_\_\_\_\_ \_\_\_\_/\_\_\_\_/\_\_\_\_

AMR Admin: \_\_\_\_\_ \_\_\_\_/\_\_\_\_/\_\_\_\_





# RECORD OF INDIVIDUAL EXPOSURE TO RADON

MiVida and Standard Shaft Project

San Juan County, Utah

[SAMPLE]

Contractor	Employee Name	Employee EIN
<i>Smith Construction</i>	<i>Hank Jones</i>	<i>000-00-0000</i>

DATE	WORK AREA	RADON CONC. IN AREA (WL)	EMPLOYEE TIME IN AREA (HR)	EXPOSURE LEVEL* (WLH)
03/15/2001	3211519H02	0.5	4	2
03/15/2001	3211519H03	1.0	4	4
03/16/2001	3211518H01	0.2	8	1.6
03/17/2001	3211518H02	1.0	2	2
3/17/2001	3211518H03	0.5	4	2
3/17/2001	3211518H01	0.2	2	0.4
TOTAL			24	12

CUMULATIVE EXPOSURE = TOTAL EXPOSURE/173 = 0.07 WLM

\*Calculate Exposure Level by multiplying the working level in column 3 times the exposure time in column 4.



### CONTRACTOR PERFORMANCE RATING

Contractor: \_\_\_\_\_

Project: MiVida and Standard Shaft AMR/037/909/C

Start Date:    /   /   

End Date:    /   /   

Duration:        days

**Rating:** Satisfactory= 1; Unsatisfactory= 0

- 1.Achieved the specified level of project quality and quantity.
- 2.Prompt, diligent, and systematic prosecution of work.
- 3.Adequate personnel (number and skill level).
- 4.Adequate equipment (number, type, and operating condition).
- 5.Effective on-site management and supervision of work.
- 6.Cooperation, responsiveness, and communication with inspector and project manager.
- 7.Cooperation and timely response in negotiation of contract changes.
- 8.Cooperation in negotiation of claims.
- 9.Record of prompt payment for labor, materials, equipment, and subcontract work.
- 10.On-time submission of necessary documents and reports.
- 11.Compliance with all applicable federal, state, and local laws and regulations.
- 12.Minimized the adverse effect of construction activities on the public and the environment.
- 13.Cooperation with landowners and/or utilities.
- = **Total = Performance Rating**

Attach explanations of all "Unsatisfactory" ratings.

Rated by: \_\_\_\_\_ Date \_\_\_\_\_

Reviewed by: \_\_\_\_\_ Date \_\_\_\_\_

A contractor with a Performance Rating (or average rating if there is more than one rating) of 9 or less fails to pre-qualify.

0869P-1  
7/20/88 Rev 7/25/91

**CONTRACTOR PERFORMANCE RATING**

Contractor: \_\_\_\_\_

Project: MiVida and Standard Shaft AMR/037/909/C

Explanations of all "Unsatisfactory" ratings:

Item:

Item:

## **Appendix D**

### **Project Location Site Maps**

#### **Map Title**


Project Area Location & Access Map

Sheet 1 of 2

McCormick Tunnel and Standard Mine

Sheet 2 of 2






<p>Utah Oil Gas and Mining Abandoned Mine Reclamation Program Drafted: October 20, 2004 - By ANF</p>	<h2 style="text-align: center;">MiVida Project</h2> <p style="text-align: center;">AMR/037/909</p> <p style="text-align: center;">Project Area Location &amp; Access</p> <p style="text-align: center;">Sheet 1 of 2</p>	<div style="text-align: center;"> <p>N</p> </div> <div style="text-align: center;"> <p>4,000 2,000 0 4,000 Feet</p> <p>1 inch equals 4,000 feet</p> </div>	<h3 style="text-align: center;">Legend</h3> <table style="width: 100%;"> <tr> <td style="width: 50%; vertical-align: top;"> <p> HO</p> <p> VO</p> </td> <td style="width: 50%; vertical-align: top;"> <p> Highway</p> <p> Paved Road</p> <p> ATV</p> </td> </tr> </table>	<p> HO</p> <p> VO</p>	<p> Highway</p> <p> Paved Road</p> <p> ATV</p>
<p> HO</p> <p> VO</p>	<p> Highway</p> <p> Paved Road</p> <p> ATV</p>				











## **Appendix E**

### **Technical Specification Design Drawings**


<b>Sheet E1</b>	<b>Adit Backfill Closure</b>
<b>Sheet E2</b>	<b>Shaft Backfill Closure</b>
Sheet E3	Block Wall Closure
Sheet E4	Native Stone Wall Closure
Sheet E5	Wall and Backfill Closure
Sheet E6	Bat Gate Closure
Sheet E7	Bat Gate Closure Details
Sheet E8	Bat Gate With Door Closure
Sheet E9	Bat Gate With Door Closure Details
Sheet E10	CMP Bat Gate Closure
Sheet E11	CMP Bat Gate Closure Details
Sheet E12	CMP/Rebar Closure
Sheet E13	CMP/Rebar Closure Details
Sheet E14	Rebar Shaft Grate Closure
Sheet E15	Rebar Shaft Grate (With I-Beam)
Sheet E16	Rebar Shaft Grate (Pinned)
Sheet E17	Rebar Shaft Grate Grade Beam Details
Sheet E18	One-way Trap Door Closure Details
Sheet E19	Shaft PUF Closure (Polyurethane Form)








 <p><b>UTAH</b> <b>NATURAL RESOURCES</b> Oil, Gas and Mining Abandoned Mine Reclamation Program</p>		<p><b>MINE RECLAMATION</b> <b>PROJECT</b></p>		<p><b>SHAFT BACKFILL CLOSURE</b></p>	
		<p>Scale: as noted</p>		<p>Design: LAA Drafting: JCR</p>	
		<p>Refer to Spec Section 0200's</p>		<p>Sheet E2 of E19</p>	

TYPICAL ELEVATION



TYPICAL SECTION



PILASTER DETAIL



UTAH  
NATURAL RESOURCES  
Oil, Gas and Mining  
Abandoned Mine Reclamation Program

MINE RECLAMATION  
PROJECT

BLOCK WALL CLOSURE


Scale: as noted

Design: LAA Drafting: JCR


Refer to Spec Section 0200's

Sheet E3 of E19

TYPICAL ELEVATION



TYPICAL SECTION



Utah Oil Gas and Mining

**UTAH  
NATURAL RESOURCES  
Oil, Gas and Mining**

Abandoned Mine Reclamation Program

**MINE RECLAMATION  
PROJECT**

**NATIVE STONE WALL CLOSURE**


Scale: as noted

Design: LAA Drafting: JCR

Refer to Spec Section 0200's

Sheet E4 of E19





Utah Oil Gas and Mining

**UTAH  
NATURAL RESOURCES**  
Oil, Gas and Mining

Abandoned Mine Reclamation Program

**MINE RECLAMATION  
PROJECT**

**WALL AND BACKFILL CLOSURE**

Scale: as noted

Design: LAA Drafting: JCR


Refer to Spec Section 0200's

Sheet E5 of E19



TYPICAL ELEVATION

TYPICAL SECTION



NOTE: ALL GATE STEEL TO BE 12-14% MANGANESE STEEL (MANGANAL OR EQUIV.)



**UTAH**  
**NATURAL RESOURCES**  
**Oil, Gas and Mining**  
Abandoned Mine Reclamation Program

**MINE RECLAMATION**  
**PROJECT**

**BAT GATE CLOSURE**

Scale: as noted


Design: LAA Drafting: JCR

Refer to Spec Section 0200's


Sheet E6 of E19



TYPICAL ELEVATION



TYPICAL SECTION



NOTE: ALL GATE STEEL TO BE 12-14% MANGANESE STEEL (MANGANAL OR EQUIV.)

FOOTING DETAIL  
PLAN VIEW

BARS FILLET WELD ALL INTERSECTIONS



**UTAH**  
**NATURAL RESOURCES**  
**Oil, Gas and Mining**  
Abandoned Mine Reclamation Program

**MINE RECLAMATION**  
**PROJECT**


**BAT GATE WITH DOOR CLOSURE**

Scale: as noted


Design: LAA Drafting: DR

Refer to Spec Section 0200's


Sheet E8 of E19



### HASP DETAIL




### LOCK BOX DETAIL



NOTE: ALL GATE STEEL TO BE 12-14% MANGANESE STEEL (MANGANAL OR EQUIV.)

### HINGE DETAIL



Utah Oil Gas and Mining

**UTAH  
NATURAL RESOURCES**  
Oil, Gas and Mining  
Abandoned Mine Reclamation Program

**MINE RECLAMATION  
PROJECT**


### BAT GATE WITH DOOR CLOSURE DETAILS

Scale: as noted

Design: LAA Drafting: DR

Refer to Spec Section 0200's

Sheet E9 of E19



**UTAH**  
**NATURAL RESOURCES**  
**Oil, Gas and Mining**  
 Abandoned Mine Reclamation Program

**MINE RECLAMATION**  
**PROJECT**

**CMP BAT GATE CLOSURE**


Scale: as noted

Design: LAA Drafting: JCR


Refer to Spec Section 0200's

Sheet E10 of E19


TYPICAL ELEVATION




TYPICAL SECTION



NOTE: ALL GATE STEEL TO BE 12-14% MANGANESE STEEL (MANGANAL OR EQUIV.)

 <b>UTAH</b> <b>NATURAL RESOURCES</b> <b>Oil, Gas and Mining</b> Abandoned Mine Reclamation Program	<b>MINE RECLAMATION PROJECT</b>	<b>CMP BAT GATE CLOSURE DETAILS</b>	
		Scale: as noted	Design: LAA Drafting: JCR
		Refer to Spec Section 0200's	Sheet E11 of E19



**UTAH**  
**NATURAL RESOURCES**  
**Oil, Gas and Mining**  
 Abandoned Mine Reclamation Program

**MINE RECLAMATION**  
**PROJECT**



**CMP/REBAR CLOSURE**

Scale: as noted

Design: LAA Drafting: MEM

Refer to Spec Section 0200's

Sheet E12 of E19



Note: Field dimensions may vary slightly



UTAH  
NATURAL RESOURCES  
Oil, Gas and Mining  
Abandoned Mine Reclamation Program

MINE RECLAMATION  
PROJECT

CMP/REBAR CLOSURE DETAILS


Scale: as noted

Design: LAA Drafting: MEM


Refer to Spec Section 0200's

Sheet E13 of E19





TYPICAL SECTION



TYPICAL PLAN



Utah Oil Gas and Mining

**UTAH  
NATURAL RESOURCES**  
Oil, Gas and Mining  
Abandoned Mine Reclamation Program

**MINE RECLAMATION  
PROJECT**


**REBAR SHAFT GRATE CLOSURE**

Scale: as noted

Design: LAA Drafting: JCR

Refer to Spec Section 0200's

Sheet E14 of E19



Utah Oil Gas and Mining

**UTAH**  
**NATURAL RESOURCES**  
**Oil, Gas and Mining**  
Abandoned Mine Reclamation Program

**MINE RECLAMATION**  
**PROJECT**

**REBAR SHAFT GRATE (WITH I-BEAM)**


Scale: as noted

Design: LAA Drafting: JCR


Refer to Spec Section 0200's

Sheet E15 of E19

# CROSS-SECTION 12" x 12" GRADE BEAM



# CROSS-SECTION 12" x 18" GRADE BEAM



Utah Oil Gas and Mining

**UTAH**  
**NATURAL RESOURCES**  
**Oil, Gas and Mining**  
Abandoned Mine Reclamation Program

**MINE RECLAMATION**  
**PROJECT**


## REBAR SHAFT GRATE GRADE BEAM DETAILS

Scale: as noted

Design: LAA Drafting: JCR

Refer to Spec Section 0200's

Sheet E16 of E19



Utah Oil Gas and Mining

**UTAH  
NATURAL RESOURCES**  
Oil, Gas and Mining  
Abandoned Mine Reclamation Program

**MINE RECLAMATION  
PROJECT**


**REBAR SHAFT GRATE (PINNED)**

Scale: as noted

Design: LAA Drafting: JCR

Refer to Spec Section 0200's

Sheet E17 of E19



NOTE: STEEL OR PVC PIPE TO EXTENT 12 INCHES  
INBY AND OUTBY WALL OR FILL MATERIAL



Utah Oil Gas and Mining

**UTAH  
NATURAL RESOURCES**  
Oil, Gas and Mining  
Abandoned Mine Reclamation Program

**MINE RECLAMATION  
PROJECT**


**ONE-WAY TRAP DOOR CLOSURE DETAILS**


Scale: as noted

Design: LAA Drafting: DR

Refer to Spec Section 0200's

Sheet E18 of E19



 <p><b>UTAH</b> <b>NATURAL RESOURCES</b> <b>Oil, Gas and Mining</b> Abandoned Mine Reclamation Program</p>		<p><b>MINE RECLAMATION PROJECT</b></p>	
<p><b>SHAFT PUF CLOSURE (PolyUrethane Foam)</b></p>		<p>Scale: as noted</p>	<p>Design: LAA Drafting: JCR</p>
		<p>Refer to Spec Section 0200's</p>	<p>Sheet E19 of E19</p>